

RUDIMENTARY TREATISE

ON THE

CONSTRUCTION OF LOCKS.

LONDON:
PRINTED BY LEVEY, ROBSON, AND FRANKLYN,
Great New Street and Fetter Lane.

RUDIMENTARY TREATISE

ON THE

CONSTRUCTION

OF

DOOR LOCKS,

FOR

COMMERCIAL AND DOMESTIC PURPOSES.

SECOND ISSUE.

WITH MR. SMYTH'S LETTER ON THE BRAMAH LOCKS.

LONDON:

JOHN WEALE, 59, HIGH HOLBORN.

M.DCCC.LVIII–IX.

PREFACE.

THE reader is entitled to know the origin of the small work which he holds in his hands.

In August 1852, being about to write a short article on Locks for a Cyclopædia of Useful Arts, of which I am the editor, I consulted my esteemed and lamented friend, the late Professor Cowper, of King's College, as to the desirability of explaining to the general reader the defects of some of our English locks, which, previous to the celebrated "lock controversy" of 1851, had borne a high character for skilful construction, beauty of workmanship, and undoubted security. Professor Cowper expressed his strong conviction that by exposing the defects of our locks, the cause of mechanical science, as well as the public in general, would be benefited; that if our locks were defective, inventors would be stimulated to supply the defects, and the art of the locksmith would be raised accordingly. He considered that Mr. Hobbs had made a considerable step in advance in the constructive details of his art, not only in having detected the weak points of some of our best English locks, but also in having introduced two or three new locks, which appeared to be more secure than any of those previously produced. Professor Cowper gave me an introduction to Mr. Hobbs, who placed at my disposal a variety of literary materials relating to the history and construction of locks, and stated his intention at some future time of bringing out a small book on the subject, if he could meet with a publisher. I recommended him to offer the work to Mr. Weale, for insertion in his series of Rudimentary Works. This was accordingly done, and I was invited to prepare the work; but as my engagements did not leave me sufficient leisure to write the book, I requested my friend Mr. George Dodd to put the materials together, and to search for

more. Mr. Dodd acceded to my request; and having completed his part of the work, I subjected it to a careful revision, and added various details which seemed to be necessary to completeness, at least so far as the narrow limits of a small rudimentary work would admit of completeness. The manuscript was then sent to press: each sheet as it was received from the printer was submitted to Mr. Hobbs, who read it with care, and made his annotations and corrections thereon. Mr. Hobbs and I then had a meeting, when the additions and corrections were read and discussed, and admitted or rejected as the case might be. The sheet having been thus corrected was sent to press.

It should also be stated that, during the progress of the work, Mr. Weale, at my request, wrote to Messrs. Bramah, and also to Messrs. Chubb, informing them that a Rudimentary Treatise on the Construction of Locks was being prepared, and requesting them to state in writing what alterations or improvements they had made in their locks since the date of the Great Exhibition. The communications which we have received from these celebrated firms are inserted *verbatim*, in their proper places, in the present work.

Such is the mode in which this small volume has been prepared. I have endeavoured to perform an editor's duty conscientiously, without entertaining the feeling of a partisan in the matter. My chief object in superintending the production of this book (an object in which the Publisher fully participates) is to advance the cause of mechanical science, and to supply a deficiency in one of the most interesting portions of its English literature.

C. TOMLINSON.

Bedford Place, Ampthill Square,
July 1853.

CONTENTS.

CHAP.		PAGE
I.	On Locks and Lock-literature	1
II.	Ancient Locks: Grecian, Roman, Egyptian	8
III.	Lock classification. The Puzzle-Lock and the Dial-Lock	16
IV.	Warded Locks, with their varied appendages	27
V.	On Tumbler, or Lever Locks	43
VI.	The Bramah Lock	64
VII.	American Locks	82
VIII.	The Lock Controversy: previous to the date of the Great Exhibition	102
IX.	The Lock Controversy: during and since the time of the Great Exhibition	115
X.	Effects of the Great Exhibition of 1851 in improving English Locks	140
XI.	The Lock and Key Manufacture	154
XII.	English Patents for Locks. Aubin's Lock trophy. Conclusion	164

ON THE

CONSTRUCTION OF LOCKS.

CHAPTER I.

ON LOCKS AND LOCK-LITERATURE.

The manufacture of locks, and a consideration of the mechanical principles involved in their construction and security, have never yet been treated with any degree of fulness in an English work. Lock-making has occupied a large amount of ingenuity, and lock-patents have been obtained in considerable number, though not always, we are satisfied, with a commensurate return for the expense incurred,—but lock-philosophy (if so it may be designated) has not been largely attended to.

And yet it may safely be said that much which is both mechanically and commercially important is comprised in a lock. Every improvement in the manufacture of iron, steel, and brass—that is, in the tool-making and machine-making processes—may be made to reflect its light on the lock-manufacture; the stamping, the casting, the planing, the slotting, the screw-cutting, the polishing of metals,—all, in proportion as they are improved, impart some of their aid to the lock-maker. Then, in the finer kinds of locks, the works are so delicate as to approach to the nicety of clock-work; thereby combining the manipulative skill of a talented

artisan with the rougher mechanical work of the smith. The principles of mechanical science are also appreciated by many lock-makers. The lever, the inclined plane, the eccentric, the cam, the screw, the wheel and pinion, the ratchet, the spring, —all are brought to bear on the internal mechanism of locks, frequently in many novel combinations.

The commercial importance of locks—though of course never seriously questioned when once fairly brought before one's attention—has been recently rendered so apparent as to have risen to the position of a public topic. If a strong room, containing gold and silver, notes and bills, books and papers—if such a room be necessarily shielded from intrusion, it becomes no less necessary that the shield should be really worthy of its name, trusty and reliable: a good lock is here nearly as indispensable as a faithful cashier. And without dwelling on such an auriferous picture as a room full of gold, we shall find ample proof of the commercial importance of lock-making in the ordinary circumstances by which we are every day surrounded. Until the world becomes an honest world, or until the honest people bear a larger ratio than at present to the dishonest, the whole of our movables are, more or less, at the mercy of our neighbours. Houses, rooms, vaults, cellars, cabinets, cupboards, caskets, desks, chests, boxes, caddies,—all, with the contents of each, ring the changes between *meum* and *tuum* pretty much according to the security of the locks by which they are guarded.

A commercial, and in some respects a social, doubt has been started within the last year or two, whether or not it is right to discuss so openly the security or insecurity of locks. Many well-meaning persons suppose that the discussion respecting the means for baffling the supposed safety of locks offers a premium for dishonesty, by shewing others how to be dishonest. This is a fallacy. Rogues are very keen in their profession, and know already much more than we can teach them respecting their several kinds of roguery. Rogues knew a good deal about lock-picking long before locksmiths dis-

cussed it among themselves, as they have lately done. If a lock—let it have been made in whatever country, or by whatever maker—is not so inviolable as it has hitherto been deemed to be, surely it is to the interest of *honest* persons to know this fact, because the *dishonest* are tolerably certain to be the first to apply the knowledge practically; and the spread of the knowledge is necessary to give fair play to those who might suffer by ignorance. It cannot be too earnestly urged, that an acquaintance with real facts will, in the end, be better for all parties. Some time ago, when the reading public was alarmed at being told how London milk is adulterated, timid persons deprecated the exposure, on the plea that it would give instructions in the art of adulterating milk; a vain fear—milkmen knew all about it before, whether they practised it or not; and the exposure only taught purchasers the necessity of a little scrutiny and caution, leaving them to obey this necessity or not, as they pleased. So likewise in respect to bread, sugar, coffee, tea, wine, beer, spirits, vinegar, cheap silks, cheap woollens—all such articles as are susceptible of debasement by admixture with cheaper substances—much more good than harm is effected by stating candidly and scientifically the various methods by which such debasement has been, or can be produced. The unscrupulous have the command of much of this kind of knowledge without our aid; and there is moral and commercial justice in placing on their guard those who might possibly suffer therefrom. We employ these stray expressions concerning adulteration, debasement, roguery, and so forth, simply as a mode of illustrating a principle—the advantage of publicity. In respect to lock-making, there can scarcely be such a thing as dishonesty of intention: the inventor produces a lock which he honestly thinks will possess such and such qualities; and he declares his belief to the world. If others differ from him in opinion concerning those qualities, it is open to them to say so; and the discussion, truthfully conducted, must lead to public advantage: the discussion stimulates curiosity, and the

curiosity stimulates invention. Nothing but a partial and limited view of the question could lead to the opinion that harm can result: if there be harm, it will be much more than counterbalanced by good.

The literature of lock-making is, as we have implied, very scanty, both in England and America. The French and Germans, though far below our level as lock-makers, are very superior to us in their descriptions of the construction and manufacture of locks. Take, for instance, the French treatise published more than eighty years ago by the *Académie des Sciences*, and forming part of a folio series of manufacturing treatises, illustrated very fully by engravings. It is worth while to examine this work, to see how minutely and faithfully the writers of such treatises performed their task nearly a century ago. The *Art du Serrurier*, with the distinguished name of M. Duhamel du Monceau as the author or editor, was published in 1767. It occupies 290 folio pages, and is illustrated by 42 folio plates. The first chapter gives us an introduction and general principles, in which the choice and manipulation of materials are touched upon; the different qualities of iron and steel; and the processes of forging, founding, welding, stamping, filing, polishing, &c. In the copper-plates representing these smiths' operations and the tools employed,* there is a smithy, with about a dozen smiths engaged in all these various occupations, with stockings down, and a due amount of workshop slovenliness. The next chapter takes us into what may perhaps be called "smith's work in general," or at least it treats of the manufacture of various kinds of ironmongery for doors, windows, and house-fittings generally. Then the third chapter treats of "smith's work which serves for the security of houses," consisting of railings, palings, bars, and gates of various kinds—such at least as are made of iron. In chapter four we have a notice of such kinds of

* It is worthy of remark, that the tools described are the same as those which are used by the locksmith at the present day; shewing how little improvement has been made in the means of producing locks.

smith's work as relate to the fastenings for doors, windows, closets, chests, &c.; such as hinges, hasps, latches, bolts, and other contrivances less complex than an actual lock. This brings us, by a natural transition, to locks in general, which form the subject of chapter five, to which is attached the illustrious name of M. de Réaumur as the author. Here are given a hundred folio pages of description, illustrated by twenty folio plates relating to locks, lock-making, and locksmiths. The sixth chapter relates to the iron-work of carriages, or the labours of the coachsmiths; while chapter seven, to wind up the work, relates to bell-hanging.

That chapter of the work which has reference to locks is the only one with which we have to do here. It is arranged in a systematic manner, beginning with the simpler locks, without wards or tumblers, and proceeding thence to others of more complex construction. The period at which the work was written was too early to lead us to expect to find a tumbler-lock described and delineated: there are, however, numerous examples of single tumbler-locks, many of them of great ingenuity. The use of multiple bolts, that is, of many bolts shot at once by one action of the key, seems to have been familiar enough to the locksmiths of those days. One lock represented is remarkable; it is attached to a strong and ponderous coffer or chest. The chest is open; and the whole under or inner surface of the cover is seen to be occupied by a lock of intricate construction; there are no less than twelve bolts, three on each long side, one on each short side, and one in each corner; these bolts are so placed as to catch under a projecting rim fixed round the top of the coffer. The collection of keys, exhibited on a separate plate, is remarkable for the great variety of forms given to them. We shall by and by copy some of the drawings of this curious work.

It was to be expected that in the *Encyclopédie Méthodique*, published in the same country and in the same century, the locksmith's art would be treated at some such length as in the work just described. Among the two hundred volumes of

which the *Cyclopédie* consists, several are devoted to arts and manufactures; and one of them contains the article in question. It occupies 168 quarto pages, and is illustrated by 35 copper-plate engravings, shewing in detail not only the parts of various locks, but the tools used by the lockmaker. It is proper, however, to remerk, that much of the letterpress and many of the plates relate to smith's work generally, and not exclusively to lock-work; the French name *serrurerie* being applied not only to lock-making, but to most of the smith's work required in dwelling-houses. This affords, indeed, a striking illustration of the fact, that until lately a lock-maker has been regarded rather as a smith than as a machinist, rather as a forger and filer of pieces of iron, than as a fabricator of delicate mechanism. One of the most curious features in this treatise is a vocabulary, containing, in alphabetical arrangement, a minute account of all the French technical terms employed in the locksmith's art. This vocabulary alone occupies 38 quarto pages.

The Germans, like the French, bestow great attention on their treatises relating to the manufacturing arts. Some of these are, indeed, worked up to a degree of minnteness which would seem superfluous, where little distinction is drawn between the importance of fundamental principles and that of mere technical details. Locks have had their due share. The article on locks in Prechtl's *Technological Encyclopædia* written by Kermarsch, and published in 1842, occupies about 140 pages. Locks are very minutely classified by the author, according to their purposes and their modes of action, and are illustrated by many plates. One of his classifications is into *German*, *French*, and *Bastard* locks, referring in part to the extent to which the key turns round in the lock; and the last of the three having an intermediate character between the other two. After treating of the ordinary warded locks, he comes to the combination principle; and it is profitable here to notice, how well the works of our machinists are understood on the continent, when they have

any thing to recommend them; there are a dozen closely printed pages devoted to a minute description of Bramah's invention, with all the separate parts illustrated by copper-plate engravings. After this comes a more general account of the details and manufacture of locks, similarly illustrated by engravings.

Whatever may be the merits of the different articles relating to locks in the various English cyclopædias, there are none approaching in length to the article in Prechtl's work. But when we consider that Prechtl devotes twenty large volumes to technological or manufacturing subjects, he is of course able to devote a larger space to each article than is given in English works. Both in England and in America, men are more disposed to do the work than to describe it when done. In the *Encyclopædia Britannica*, in Rees' *Cyclopædia*, in Hebert's *Engineers' and Mechanics' Cyclopædia*, in the *Encyclopædia Metropolitana*, in the *Penny Cyclopædia*, and in other similar works, locks are described as well as can be expected within the limits assigned to the articles. Mr. Bramah's essay on locks, and on his own lock in particular, is one of the few English pamphlets devoted expressly to this subject. An excerpt from the proceedings of the Institute of Civil Engineers, in 1851, gives an interesting paper on locks by Mr. Chubb; and shorter reports of papers and lectures have been published in various ways. Perhaps the best account of locks which we have, considering the limited space within which a great deal of information is given in a very clear style, is that contained in Mr. Tomlinson's *Cyclopædia of Useful Arts*.

CHAPTER II.

ANCIENT LOCKS: GRECIAN, ROMAN, EGYPTIAN.

Locks and door-fastenings have not, until modern times, been susceptible of any classified arrangement according to their principles of construction. They have been too simple to require it, and too little varied to permit it. That some such fastenings must be employed wherever doors of any kind are used is sufficiently apparent; and there is a little (though only a little) information obtainable, which shews the nature of the fastenings adopted in early times. The bolt, the hasp, the chain, the bar, the latch, the lock, all were known, in one or other of their various forms, in those ages which we are accustomed to consider classical. Travellers, generally speaking, do not descend to locks, or rather they do not think about them; otherwise they might have collected much that would have been novel and applicable to the present work; and, indeed, there is some ground for the assertion, that a notice of the door-fastenings of all nations would reveal to us something of the social and domestic habits of various members of the great human family. Be this as it may, however, we may profitably make a little inquiry into the locks of ancient times.

In the volumes of Lardner's *Cyclopædia* relating to the "Manners and Customs of the ancient Greeks and Romans," we do not find any mention of the kinds of locks used by those nations; but the author, while describing the houses, says:—"Doors turned anciently upon large pivots in the centre, let into sockets in the lintel and threshold, so that one of the sides opened inwards, the other outwards; and Plutarch gives the following curious reason why persons were to knock and

alarm the porter, viz. lest the visitor entering unawares should surprise the mistress or daughter of the family busy or undressed, or servants under correction, or the maids quarreling." As the visitors had thus the power (if permitted so to do) to open the outer door of a house, it would appear that very little in the nature of a lock was employed under ordinary circumstances, unless indeed it were a mere latch. In respect to Roman houses it is stated, that "the doors revolved upon pivots, which worked in a socket below, and were fastened by bolts which hung from chains." There is no mention of locks here. Mr. St. John, in his work on the same subject, says: "The street-door of a Grecian house, usually, when single, opened outwards; but when there were folding-doors they opened inwards, as with us. In the former case it was customary, when any one happened to be going forth, to knock, or call, or ring a bell, in order to warn passengers to make way." After describing the various kinds of wood of which the doors were made, he proceeds: "The doors at first were fastened by long bars passing into the wall on both sides; and by degrees smaller bolts, hasps, latches, and locks and keys, succeeded. For example, the outer door of the thalamos in Homer was secured by a silver hasp, and a leathern thong passed round the handle, and tied, perhaps, in a curious knot.

Mr. Yates, in a learned article on this subject in Smith's *Dictionary of Greek and Roman Antiquities*, collects numerous details scattered through various early writers. We will string together a few of these details, so far as they have any relation to the fastenings of doors. The outer door of a Roman house was generally called *janua;* whereas the inner doors were called *ostia.* The doorway, when complete, consisted of four indispensable parts—the threshold or sill, the lintel, and the two jambs. The threshold, on which the feet trod, was often regarded with a kind of superstitious reverence; the lintel, which crossed the doorway at the top, having a considerable superincumbent weight to bear, was usually made of one piece of timber or stone of great strength; the jambs, or side

uprights, were also made in one piece each. The doorway, in every building of the least importance, contained two doors folding together; even the internal doors had their bivalve construction. But in every case each of the two valves was wide enough to allow persons to pass through without opening the other; in some cases even each valve was double, so as to fold like our window-shutters. These doors, or valves, were not hinged to the side-posts, as with us, but were, as has already been stated, pivoted to the lintel above and the threshold below. The fastening usually consisted of a bolt placed at the base of each valve or half-door, so as to admit of being pushed into a socket made in the sill to receive it. The doorways in some of the houses at Pompeii still shew two holes in the sill, corresponding to the bolts in the two valves. At night, the front door of the house was further secured by means of a wooden and sometimes an iron bar placed across it, and inserted into sockets on each side of the doorway; hence it was necessary to remove the bar in order to open the door. Chamber-doors were often secured in the same manner. In the *Odyssey* there is mention of a contrivance (adverted to by Mr. St. John) for bolting or unbolting a door from the outside; it consisted of a leather thong inserted through a hole in the door, and by means of a loop, ring, or hook, capable of taking hold of the bolt so as to move it in the manner required. We have here evidently the elements of a more complete mechanism; for the bolt was a rude lock in the same degree that the thong was a rude key. That the Romans afterwards had real locks and keys is clear; for the keys found at Herculaneum and Pompeii, and those attached to rings, prove that a kind of warded lock must have been well known.* There are the remains of a tomb at Pompeii, the door of which is made of a single piece of marble, including the pivots, which were encased in bronze, and turned in sockets of the same metal; it is three feet high, two feet nine inches wide, and

* An examination of the Roman keys in the British Museum sufficiently attests this fact.

four and a quarter inches thick; it is cut in front to resemble panels, and thus approaches nearer in appearance to a modern wooden door; and it was fastened by some kind of lock, traces of which still remain.

The same facts frequently become more clear when described in different words by different writers. We shall make use of this circumstance. Mr. Donaldson, in his *Essay on Ancient Doorways*, presents us with details which illustrate many of the foregoing remarks. "Homer describes the treasures and other valuable objects (mentioned in the *Odyssey*) as being kept in the citadel, secured merely by a cord intricately knotted. This, of course, was soon found to be a very insufficient protection, and therefore a wooden bar was adopted inside the doors of houses, to which it was attached by an iron latch, fastened or removed by a key adapted to it; this key was easily applied from within; but in order to get at it from without, a large hole was made in the door, allowing the introduction of the hand, so as to reach the latch and apply the key. The lock called the Lacedæmonian, much celebrated by ancient writers, was invented subsequently; it was especially fitted for the inner chambers of houses, the bar fastenings continuing to be employed for closing the outer doors of dwellings and the entrance-gates to cities. The Lacedæmonian lock did not require a hole to be made in the door, for it consisted of a bolt placed on that side of the entrence-door which opened, and on the inside of a chamber-door. When a person who was outside wished to enter, it was necessary for him to insert the key in a little hole and to raise the bolt; and in time this species of fastening was improved by the insertion of the bolt in an iron frame or rim permanently attached to the door by a chain, and fastening the door by the insertion of the hasp, through the eye of which was forced the bolt inside the lock by applying the key." After quoting a Latin sentence from Varro in elucidation of his subject, Mr. Donaldson proceeds to observe, that for the most part the locks of the ancients were different in principle from those of modern days, not being in-

serted or mortised into the doors, nor even attached except by a chain; they were, in fact, padlocks.

One of the passages in the *Odyssey* alluding to the primitive mode of fastening the valves or folding-doors of a house runs thus:—

> "Whilst to his couch himself the prince addressed,
> The dutcous nurse received the purple vest:
> The purple vest with decent care disposed,
> The silver ring she pulled, the door reclosed;
> The bolt, obedient to the silken cord,
> To the strong staple's inmost depth restored,
> Secured the valves."

Most of the other great nations of antiquity resembled either the Egyptians or the Greeks and Romans, more or less closely, in their domestic and domiciliary arrangements; or, at any rate, so far as such humble matters as locks and keys are concerned, we need not seek far from those nations for examples. The Nineveh and other Assyrian explorations have, however, revealed many curious and unexpected facts; from the temples and the palaces we may by and by penetrate into the houses and rooms of the citizens sufficiently to know how their doors were fastened. In the mean time ancient Egypt awaits our notice.

Sir J. Gardner Wilkinson, in his *Manners and Customs of the Ancient Egyptians*, gives the following information concerning the doors and door-fastenings of that remarkable people, on the authority of models, sculptures, and paintings, still existing. The doors were frequently stained so as to imitate foreign and rare woods. They were either of one or two valves, turning on pieces of metal, and were secured within by a bar or by bolts. Some of these bronze pins have been discovered in the tombs of Thebes; they were fastened to the wood with nails of the same metal, the round heads of which served also as ornaments. In the stone lintels and floors behind the thresholds of the tombs and temples are still frequently to be seen the holes in which the pivot-pins turned, as well as those of the

bolts and bars, and the recess for receiving the opened valves. The folding-doors had bolts in the centre, sometimes above as well as below; a bar was placed across from one wall to the other.

In many of the ancient Egyptian doors there were wooden locks fixed so as to fasten across the centre at the junction where the two folds of the door met. It is difficult, by mere inspection of the bas-reliefs and paintings, to decide whether these locks were opened by a key, or were merely drawn backwards and forwards like a bolt; but if they were really locks, it is probable that they were on the same principle as the Egyptian lock still in use. For greater security, these modern locks are occasionally sealed with a mass of clay; and there is satisfactory evidence that the same custom was frequently observed among the ancient inhabitants of that country. Sir J. G. Wilkinson gives a representation of an iron key, now in his possession, which he procured among the tombs at Thebes, and which looks very much like a modern burglar's picklock. In relation to keys generally, and after mentioning the use of bronze for their manufacture, he says: "'At a later period, when iron came into general use, keys were made of that metal, and consisted of a straight shank about five inches in length, and a bar at right angles with it, on which were three or more projecting teeth. The ring at the upper extremity was intended for the same purpose as that of our modern keys; but we are ignorant of the exact time when they were brought into use; and the first invention of locks distinct from both is equally uncertain; nor do I know of any positive mention of a key, which, like our own, could be taken out of the lock, previous to the year 1336 before our era; and this is stated to have been used to fasten the door of the summer parlour of Eglon, the king of Moab. The description here adverted to is that contained in Judges iii. 23-25: 'Ehud went forth through the porch, and shut the doors of the parlour upon him, and locked them . . . . his servants . . . . took a key, and opened them.'"

The curious and ingenious wooden lock of ancient Egypt is still in use in Egypt and Turkey. In Eton's *Survey of the Turkish Empire*, published towards the close of the last century, the locks then and there in use are thus described: "Nothing can be more clumsy than the door-locks in Turkey; but their mechanism to prevent picking is admirable. It is a curious thing to see wooden locks upon iron doors, particularly in Asia, and on their caravanserais and other great buildings, as well as upon house-doors. The key goes into the back part of the bolt, and is composed of a square stick with five or six iron or wooden pins, about half an inch long, towards the end of it, placed at irregular distances, and answering to holes in the upper part of the bolt, which is pierced with a square hole to receive the key. The key being put in as far as it will go, is then lifted up; and the pins, entering the corresponding holes, raise other pins which had dropped into these holes from the part of the lock immediately above, and which have heads to prevent them falling lower than is necessary. The bolt, being thus freed from the upper pins, is drawn back by means of the key; the key is then lowered, and may be drawn out of the bolt. To lock it again, the bolt is only pushed in, and the upper pins fall into the holes in the bolt by their own weight." Mr. Eton, probably seeing how well the tumbler-principle is here understood, says: "This idea might be improved on; but the Turks never think of improving." The locks on the doors of modern houses in Cairo seem to be of this long-established form, except where iron locks have been imported from Europe.

A letter was inserted in the *Journal of Design* for July 1850 from Mr. W. C. Trevelyan; in which, after adverting to the Egyptian lock, he says: "It is remarkable that the locks which have been in use in the Faroe Islands, probably for centuries, are identical in their construction with the Egyptian. They are, lock and key, in all their parts made of *wood;* of which material, if I mistake not, they have also

been found in Egyptian catacombs; and so identical with the Faröese in structure and appearance, that it would not be easy to distinguish one from the other."



fig. 1.



fig. 2.

fig. 3.

fig. 4.

The construction of this remarkable Egyptian or pin-lock will be understood from the accompanying engravings. The quadrangular portion, *a a* fig. 1, is the case of the lock, screwed or otherwise fastened to the door, having a wooden bolt, *b b*, passing horizontally through a cavity in it. In the part of the case above the bolt are several small cells containing headed pins, arranged in any desired form; and in the top of the bolt itself are an equal number of holes similarly arranged. The effect of this arrangement is such that, when brought into the right positions, the lower ends of the headed pins drop into the corresponding holes in the bolt, thereby fastening the bolt in the lock-case. A large hollow, or cavity, is made at the exposed end of the bolt, the cavity extending as far as and beyond the holes occupied by the pins. The key consists of a piece of wood (shewn in two positions, figs. 3 and 4,) having pins arranged like those in the lock, and projecting upwards just to a sufficient distance to reach the upper surface of the bolt. This being the arrangement, whenever the key is introduced and pressed upwards, its pins exactly fill the holes in the bolt, and by so doing dislodge those which had fallen

from the upper part of the case. The bolt may, under these circumstances, be withdrawn (as shewn in fig. 2), leaving the headed pins elevated in their cells, instead of occupying the position shewn by the dotted lines in fig. 1. The cavity in the bolt must of course be high enough to receive the thickness of the key, and also the length of the pins protruding from the key.

This primitive lock comprises many of the best features of the tumbler or lever-locks of later days, as will be seen in a future chapter. There will also be opportunities of shewing how the pin-action has been applied in other ways in some of the modern locks.

CHAPTER III.

LOCK CLASSIFICATION. THE PUZZLE-LOCK AND THE DIAL-LOCK.

In approaching the subject of modern locks it becomes necessary to decide upon some method of treating the widely-scattered and diverse materials which are presented to our notice. One plan would be to trace the subject chronologically, by describing, in the order of their invention, the most important locks which have been presented to public notice. But this would be attended with some disadvantages: the peculiar characters of the several locks would not be brought out with sufficient distinctness; and the result, so far as the reader is concerned, would rather tend to confusion than to a clear appreciation of the subject. There are more advantages belonging to a classification of locks under certain headings, according to some marked peculiarities in their modes of action. This is a convenient plan, but it is not an easy one to put in execution; for inventors have not sought to place their locks in any particular class, but rather to call attention to their merits. Moreover,

many locks embody two or three distinct principles so equally, that it will often be difficult to decide in which class to place them. This, nevertheless, may be done with an approach to correctness. It is necessary first, however, to explain certain technical terms by which locks are distinguished one from another.

Locks, in truth, admit of an immense variety, which, however important to be known to locksmiths, carpenters, and others employed on them, need only be glanced at very cursorily by the general reader. Some locks are named according to the purposes to which they are to be applied; others according to their shape, or the principles of their construction. In the first place, there is the distinction between *in-door* and *out-door* locks. Of in-door locks, one principal kind is the *draw-back* lock, for street-doors, in which the bolt is capable of maintaining any one of three positions: it may be locked by the key, or left half-way out by the pressure of a spring, or be drawn back by a handle. In the first position, it can only be withdrawn by the key; in the second, it closes the door, but can easily be withdrawn by the handle; and in the third, it leaves the door unfastened. If these locks are made of iron and carefully finished, they are further called *iron-rim*; but if made of wood, suitable for back-doors and inferior purposes, they are *spring-stock*. For the doors of rooms, there are the *iron-rim*, the *brass-case*, and the *mortise* lock; the second supplants the first, and the third the second, as we advance in the elegance of the door-fittings. Other designations for room-locks depend on the number of the bolts: thus, if there be only one bolt, it is a *dead lock* or *closet lock*; if there be a second bolt, urged by a spring and drawn back by a handle, it is a *two-bolt lock*; and if there be also a third, a private bolt acting only on one side of the door, it is a *three-bolt lock*. Again, according to the kind of handle employed, it may be a *knob lock* or a *ring lock*. According to which edge of the door it is to be fixed, it becomes a *right-hand* or a *left-hand* lock. If the wards of the lock are of somewhat superior quality, and

bend round nearly to a circle, the lock is *one-ward round*, *two-ward round*, and so forth. If the lock has no wards at all, it is *plain*; if the wards are of common character, they are often called *wheels*, and then the lock becomes *one-wheel*, *two-wheel*, &c. Sometimes the lock is named from certain fancied resemblances in the shape of the ward, as the L-*ward*, T-*ward*, or Z-*ward*. If the wards are cast in brass, instead of being made of slips of iron or copper, the lock is termed *solid ward*.

Of the numerous but smaller varieties known by the collective name of *cabinet locks*, there are the *cupboard*, the *book-case*, the *desk*, the *portable desk*, the *table*, the *drawer*, the *box*, the *caddy*, the *chest*, the *carpet-bag*, and many other locks. All these locks are further called *straight*, when the plate is to be screwed flat against the wood-work; *cut*, when the wood is to be so cut away as to let in the lock flush with the surface; and *mortise*, when a cavity is excavated in the edge of the door for the reception of the lock.

Out-door locks are usually *wooden stock locks*, for stables, gates, &c.; comprising many varieties of *Banbury*, *bastard*, *fine*, &c. There are D *locks* and P *locks*, for gates, designated from their shapes; and there are the numerous kinds of *padlocks*.

The above terms are employed chiefly between the makers of the locks and the persons who fix them in their places; but there are other terms and names, more familiarly known, which will come under notice in future pages.

It is scarcely worth while to descant upon the "middle age" of lock-making—to impart to the subject so much of dignity as to be susceptible of regular historical treatment. True, we know that *wards* were employed before *tumblers* (unless, indeed, the pins of the Egyptian lock be considered as tumblers—a character to which they present considerable claim), and that wards may be taken as the representative of the mediæval period of lock-making; but it may be more profitable to proceed in our notice of the different kinds of locks in an order which will in itself partake somewhat of the historical character.

Apart from all the warded and tumbler locks are the very curious *puzzle* or *letter-locks*; a construction which we propose to dismiss out of hand in the present chapter, before treating of those which have more commercial importance.

The puzzle-lock is generally in the form of a padlock, which is opened and closed without the use of a key, and which has certain difficulties thrown in the way of its being opened by any one who is not in the secret of the person who closed it. It is, in fact, one of the locks in which the doctrine of permutation is made to contribute to the means of security. The key to open it is a *mnemonic* or *mental* one, instead of one of steel or iron. Two centuries ago, the puzzle-lock attracted far more attention than any other. It has always certain movable parts, the movement of which constitutes the enigma. Some of these very curious and out-of-the-way locks are so formed as to receive the name of *dial-locks*; but the chief among them are *ring-locks*—a name the meaning of which will be presently understood.

The puzzle or letter-lock of the ring kind, then, consists essentially of a spindle; a barrel, encompassing the spindle; two end-pieces, to keep the spindle and barrel in their places; and the shackle, hinged to one of these end-pieces. To unfasten the lock, one of the end-pieces must be drawn out a little, to allow the shackle or horse-shoe to be turned on its hinge; and the question arises, therefore, how this end-piece is to be acted upon. This is effected in a very ingenious way: there are four studs or projections in a row on the spindle, and as the spindle fits pretty closely in the barrel, the former cannot be drawn out of the latter unless there be a groove in the interior of the barrel, as a counterpart to the studs on the exterior of the spindle; four rings fit on the barrel, on the interior of each of which there is a groove; and unless all these four grooves coincide in direction, and even lie in the same plane as the groove in the barrel, the studs will not be able to pass, and the spindle cannot be drawn out. Each ring may be easily made to work round the barrel by means of the

fingers, and to maintain any position which may be given to it. There are outer rings, one over each of the rings just described, with the letters of the alphabet (or a considerable number of them) inscribed on each; and these outer rings, by means of notches on the inside, govern the movements of the inner rings.

The action is, therefore, as follows: when the padlock is to be locked, the rings are so adjusted that all the grooves shall be in a right line; the spindle is thrust in, the end-piece is fixed on, and the shackle is shut down. The padlock is now fastened; but a reverse order of proceeding would as easily open it again, and therefore the "safety" or "puzzle" principle is brought into requisition. The outer rings are moved with the finger, so as to throw the various interior grooves out of a right line, and thus prevent the withdrawal of the spindle. As each ring may be turned round through a large or a small arc, and all turned in different degrees, the variations of relative position may be almost infinite. The letters on the outer rings are to assist the owner to remember the particular combination which he had adopted in the act of locking; for no other combination than this will suffice to open the lock. There may, for instance, be the four letters L O C K in a line, which line is brought to coincide with two notches or marks at the ends of the apparatus; and until all the four outer rings are again brought into such relative position as to place the letters in a line, the lock cannot be opened.

There are many allusions to locks, apparently belonging to the letter or puzzle principle, in authors who flourished two or three centuries ago. Thus, in Beaumont and Fletcher's play of the *Noble Gentleman*, written in the early part of the seventeenth century, one of the characters speaks of

> "A cap-case for your linen and your plate,
> With a strange lock that opens with A·M·E·N."

And in some verses by Carew, written about the same time, there is an analogy drawn, in which one of the things compared is—

"A lock
That goes with letters; for till every one be known,
The lock 's as fast as if you had found none."

In the *Memorabilia* of Vanhagen von Ense, written about the middle of the seventeenth century, a commendatory notice is given of a letter-lock, or combination-lock, invented by M. Regnier, Director of the *Musée d'Artillerie* at Paris. "Regnier," we are told, "was a man of some invention, and had taken out a patent for a sort of lock, which made some noise at the time. Every body praised his invention, and bought his locks. These consisted of broad steel rings, four, five, or eight deep, upon each of which the alphabet was engraved; these turned round on a cylinder of steel, and only separated when the letters forming a particular word were in a straight line with one another. The word was selected from among a thousand, and the choice was the secret of the purchaser. Any one not knowing the word might turn the ring round for years without succeeding in finding the right one. The workmanship was excellent, and Regnier was prouder of this than of the invention itself. The latter point might be contested. I had a vague recollection of having seen something of the sort before; but when I ventured to say so, my suspicions were treated with scorn and indignation, and I was not able to prove my assertion; but many years afterwards, when a book, which as a boy I had often diligently read, fell into my hands, Regnier's lock was suddenly displayed. The book was called *Silvestri a Petrasancta Symbola Heroica*, printed at Amsterdam in 1682. There was an explanation at p. 254, attached to a picture; these were the words:—*Honorius de Bellis, serulæ innexæ orbibus volubilibus ac literatis circumscripsit hoc lemma—Sorte aut labore.** However, neither luck nor labour would have done much more towards discovering the secret of opening Regnier's locks, from the variety of their combinations; and their security seemed so great, that

* "Honorius de Bellis wrote this inscription,—*By chance or by labour*, —round a lock composed of revolving rings graven with letters."

the couriers' despatch-boxes were generally fastened with them."

This curious extract, which was brought forward by Mr. Chubb, in a paper on locks and keys (read before the Institution of Civil Engineers in 1850), seems to take away the credit from one (Regnier) with whose name the letter-lock has been most intimately associated. We shall presently explain, however, what it was that Regnier effected towards perfecting the letter-lock. In the meantime it may be interesting to note that the British Museum contains a copy of the work mentioned by Vanhagen. At the page indicated there is an engraving (a fac-simile of which is given in fig. 5) containing a drawing of a veritable puzzle or letter-lock; the lock consists of a cylinder or barrel, on which seven rings work; each of these rings is ioscribed with letters, and the ends of the cylinder are grasped by a kind of shackle.



fig. 5. Puzzle-lock of the seventeenth century.

It was a natural result of the arrangement of the letter-lock, as invented (conjecturally) by Cardan, that only one particular word or cipher or key could be used in each lock; and it was to increase the puzzle-power of the lock that Reg-

nier doubled all the rings, making each pair concentric, and enabling the user to vary the cipher at pleasure.

The principle of the letter-lock, when applied to doors, requires that sort of modification which renders it what is termed a *dial-lock*. There are to such a lock one or more dials, with a series of letters or figures stamped on them; there is to each dial a hand or pointer connected by a spindle with a wheel inside the lock; on the wheel is a notch which has to be brought to a certain position before the bolt can be moved. There are false notches, to add to the difficulty of finding the true notch in each wheel. To adjust the notches to their proper position, a nut on the back of the wheel is loosened, and the pointer is set at any letter or figure chosen by the user. The pointers and the dials perform the part of the outer rings, the wheels that of the inner rings; and it is easy to see that the same leading features prevail in the two kinds of lock, however they may differ in detail.

These dial-locks have not been numerous; they require wheel and pinion work within the body of the lock, which gives delicacy and complication to the mechanism. The letter padlock, be its merits great or small, is strong and durable, not liable to get out of order; and in so far as it requires no key or key-hole, it occupies rather a special position among locks. One of our great "merchant-princes" has been a letter-lock inventor, as the following will shew.

Early in 1852, Mr. William Brown, the distinguished member for South Lancashire, read a paper before the Architectural and Archæological Society of Liverpool, of much interest in relation to our present subject. His object was to describe a letter-lock which he had invented, and which had up to that time given high satisfaction. We cannot do better than transcribe the paper, as reported in one of the Liverpool Journals, with a few abridgments.

"As your society are desirous of seeing any improvements or attempts at them, I send you a stock-lock for inspection. The idea for its construction I took from a letter-padlock.

I had a lock of this description made by Mr. Pooley twenty-five years ago, which has been in use ever since on Brown, Shipley, and Co.'s safe. . . . .

"Its advantages I conceive to be—First, it cannot be picked, for there is no key-hole. Second, it cannot be blown up by gunpowder, for the same reason. Third, you cannot drill through the door so as to reach the lock, for you are intercepted by a steel plate on which your tools will not act: thus you cannot introduce gunpowder that way to force the lock off. Fourth, you cannot bounce off the wheels in the interior with a muffled hammer, for vulcanised India-rubber springs resist this. Fifth, you cannot drill the spindles out, as their heads are case-hardened. Sixth, you cannot drive them in, for they are countersunk in the door about half-way through. . . . .

"Now let us set the lock to the word WOOD (any other four letters might be used). When you set the lock, make a private record of them, so that you may not forget them. If parties do not know your letters, nothing but violence, applied by some means or other, can enable them to get into your safe; for the lock will not open to any thing but its talisman. Take off all the large wheels and open the lock: you will see that the large wheels have a number of false chambers; if you get the spurs of the bolt into three real chambers and one false, you are as fast as ever, for all four must be right.

"Having placed your key and pointer outside the door to point to W on brass-plate No. 1, the small wheel inside obeys the same impulse; then maintain your small wheel steadily on this point, and the large wheel No. 1 will only fit on at the right place, the true opening compartment being opposite the spur of the bolt. It being necessary at the time you set your lock that it should be open, proceed with Nos. 2 and 3 in the same way, your pointer standing steadily at O. No. 4 is the same, the pointer being held steadily at D. You should then shoot your lock two or three times, to be sure you have

made no mistake. Every time you shoot your bolts out, turn your wheels away from the true chamber, and see when you again turn your pointers to WOOD that your lock opens freely; it is the proof that you have made no mistake, and you may now venture to lock your safe. When you unlock the door, and find it necessary to leave it open for a time, you should shoot the bolts as if locked, and turn the wheels, so that no one may find what your real letters are; and again adjust them to their proper places, in order that the bolt may go back and enable you to re-lock. Once having locked the door and turned the wheels from your real letters, you need not trouble yourself with carrying the key, but leave it in any place beside the lock.

"I believe two wheels would make a perfectly safe lock; three would be quite so. I adopted four to make security doubly sure, as it would be impossible in any given time to work the changes. On two wheels by chance the lock might open; you can, however, calculate the chances against this; and also three or four, the false compartment on the outer rim being taken into calculation. * * *

"If this lock is of any value, it should be known; if it has weak points, let them be pointed out, and they may admit of a remedy; for we ought not to be led to believe a lock is safe which is not so."

In relation to the "first advantage" which Mr. Brown not unreasonably supposed to be possessed by his lock—viz. that "it cannot be picked, because it has no keyhole"—we shall have something to say in a future page, where certain fallacies on this subject will be noticed. In the meantime we may remark, that it is not a little creditable that a leading Liverpool merchant should have invented a lock worthy of occupying a position on his own safe for a quarter of a century; for we may be quite certain that he would not have allowed the lock to maintain that post of honour unless it had really (so far as experience had then gone) served worthily as a safeguard to his treasures. And if it were possible to

collect all the by-gone specimens of lock-oddities, we should probably find among them many highly-ingenious letter-locks; for supposing a man to have a mechanical turn of mind, a lock is by no means an unworthy medium for displaying it; the pieces of metal are so small as to be easily manageable at a small work-bench in a small room. The fondness for this sort of employment evinced by the unfortunate Louis XVI. of France led to the common remark, "He is a capital locksmith, but a very bad king."

In an amusing article in the *Observer*, during the progress of the "lock controversy," was the following paragraph relating to combination-locks of the letter or puzzle kind: "The French, in their exposition of 1844, availing themselves of the permutation principle, produced some marvels in the art; but the principle has not been adopted in this country. The *Charivari* had an amusing quiz upon these locks when they first came out. It said the proprietor of such a lock must have an excellent memory: forget the letters, and you are clearly shut out from your own house. For instance, a gentleman gets to his door with his family, after a country excursion, at eleven o'clock at night, in the midst of a perfect deluge of rain. He hunts out his alphabetical key, and thrusts it into his alphabetical lock, and says AZBX. The lock remains as firm as ever. 'Plague take it!' says the worthy citizen, as the blinding rain drives in his eyes. He then recollects that that was his combination for the previous day. He scratches his head to facilitate the movement of his intellectual faculties, and makes a random guess BCLO; but he has no better success. In addition to his being well wet, his chances of hitting on the right combinations and permutations are but small, seeing that the number is somewhere about three millions five hundred and fifty-three thousand five hundred and seventy-eight. Accordingly, when he comes to the three-hundredth he loses all patience, and begins to kick and batter the door; but a patrol of the National Guard passes by, and the disturber of the streets is marched off to the watch-house."

CHAPTER IV.

WARDED LOCKS, WITH THEIR VARIED APPENDAGES.

THE more ordinary locks are of an oblong quadrangular shape. In nearly all of them, either a bolt shoots out from the lock, to catch into some kind of staple or box, or a staple enters a hole in the edge of the lock, and is there acted upon by the bolt. A common room-door lock will illustrate the first of these kinds, a tea-caddy lock the second. The key, as is well known, enters a receptacle made for it; and the shaft of the key generally serves as a pivot or axis around which the web or flat part of the key may move in a circular course. During this movement the web acts directly or indirectly on the bolt, driving it in or out according to the direction in which the key is turned; the key impels the bolt one way, certain springs act upon it in another, and the balance between these two forces determines the locking and unlocking of the bolt. *Wards*, or *wheels*, are contrivances for rendering the opening difficult without the proper key; and it is of warded locks that we shall chiefly treat in this chapter.



fig. 6. Interior of a back spring warded lock.

The annexed cut, fig. 6, represents the interior of an ordinary back-spring lock, without tumblers. Such a lock may

usually be known from a tumbler-lock by this simple circumstance, that it emits a smart snapping noise during the process of locking, occasioned by the pressure of the spring when the bolt is in a particular position. In the woodcut the bolt is represented half out, or half shot. At *a a* are two notches on the under side of the bolt connected by a curved part; *b* is the back spring, which becomes compressed by the passage of the curve through a limited aperture in the rim *c c* of the lock. When the bolt is wholly withdrawn, one of the notches *a* rests upon the rim *c c;* and the force with which the notch falls into this position, urged by the spring *b*, gives rise to the snapping or clicking noise. When the bolt is wholly shot, the other notch rests in like manner upon the edge of the aperture in the rim.

It must be obvious at a glance, that this hack-spring lock is objectionable on the score of security, on account of the facility with which the bolt may be forced back by any pressure applied to its end, a pressure which may often easily be brought to bear. At the centre of the lock is seen the end of the key acting on a notch in the bolt, and surrounded by wards.

It is not at a first glance that the relation between the clefts in a key and the wards of a lock can be duly appreciated; because the wards present themselves to view as portions of circles to which nothing in the key seems to correspond; but if it be borne in mind that the key has a rotary



fig. 7. Section to shew the action of wards.

motion within the key-hole around the pipe or barrel as an axis, the circular form of the wards will he accounted for, and their *section* will be regarded as exhibiting the looked-for relation to the wards of the key. In the annexed cut, for example (fig. 7), which represents a portion of the interior of a warded lock, the curved pieces of metal are the wards (two in this case); and there are two clefts in the hitt of the key to enable the latter to take its circular course without interruption from the wards. If the clefts were other than they are, either in number, position, or size, this freedom of the key's movement could not be obtained.

When once the opinion became estahlished that a lock is rendered secure hy virtus of its wards, (a theory which we shall have to discuss in a later page,) much ingenuity was displayed in varying the wards of the lock, the clefts of the key, and the shape of the keyhole. Even if the two former were unchanged, a change in the latter might add to the puzzlement of the arrangement. For instance, in the annexed cut

fig. 8. End sections of keys.

(fig. 8), all the six keys represented may have clefts or cuts exactly alike, all alike adapted to the wards of one particular lock; yet the differences in the *thickness* of the web are such, that if the keyholes were shaped in conformity therewith, each keyhole would be entered hy one of these keys; *b* and *c* differing from *a* in the relative thickness at different points, and *d*, *e*, and *f* having certain curvatures and cavities not to be found in the other three.

But without waiting for the detailed examination of the relative security and insecurity of locks, we may at once shew how simple is the principle which renders the warded system

fallacious. In fig. 9 we shall be able to illustrate this. Numbers 1, 2, and 3, all appear very different keys, and it is



fig. 9. Examples to shew the action of "master," or "skeleton keys."

quite true that neither one would open a lock adapted for either of the other two; and yet the very simple arrangement No. 4 would open all three. This No. 4 is called a *skeleton-key*; and the relation which it bears to the others may be expressed in the form of a proposition thus: at any point where there is solid metal in *all* the keys, there must (or may) be solid metal in the corresponding part of the skeleton-key; but at any point where there is a vacancy or cavity in *any* of the keys, there must be a cavity in the corresponding part of the skeleton-key. If Nos. 1, 2, 3, 4, be examined, this proposition will be found to be borne out; there is so much cavity in No 4 that it avoids the wards in all the three locks, nothing being required but the tongue of metal to move the bolt. Sometimes, to add to the safety, wards are attached to the front as well as the back plate of the lock; and then there may be a double series of notches required in the key, such as in No. 5; but if this be compared with Nos. 9, 10, 11, it will be found that although no one of the four would open a lock

adapted for either of the other three, yet the skeleton-key No. 12 would master them all, having cavities wherever any of the others have cavities. This is the theory of the *master-key*, by which one key may be made to command many locks. Nos. 6 and 7 have complicated wards; but the key is so much cut up as to be weakened more than is desirable. No. 8 enables us to point out the difference between two distinct classes of keys. Keys with pipes or barrels fitting on a pin or pipe-shaft can only open a lock on one side of the door or box; but a key with a solid stem, as No. 8, has the clefts so cut as to open the lock from either side, as in a street-door lock: it is, in fact, two warded keys fixed end to end, only half of which is employed at one time in opening the lock.



fig. 10. Wards of an old French lock.

Some of the warded locks of the last century are curious. While the idea prevailed that a complicated ward gave security, there was room for the exercise of ingenuity in varying the shape of the wards. Fig. 10 is copied from the great French work. It represents the cuts in the key, and also (seen perspectively) the complicated forms of the pieces of metal which constitute the wards corresponding with those cuts. The aperture in the key at 16 fits upon the metal surrounding the keyhole at 18; and the M-shaped cuts at 17 fit in like manner upon the similarly-shaped metal pieces at 19.

Another example of a similar kind is shewn in fig. 11, where an anchor appears to have been the favourite form. The

anchor cuts in the key are shewn at 26; while in the wards



fig. 11. Wards of an old French lock.

the bottom of the anchor is near the keyhole at 28, and the top at 29.

fig. 12. Wards of an old French lock.

A similar illustration occurs in fig. 12, where the star-like cuts at 34 on the key correspond with the star-like wards at 33.

From the fifteenth to the eighteenth centuries locks were made in France, on which a vast amount of care and expense was bestowed. They were, in an especial degree, decorative appendages as well as fastenings. They were of three kinds: room-locks, buffet-locks, and chest-locks; they were fixed on the outside of the door or lid, so as to be fully visible. The key had a multitude of perforations which bore no particular relation to the wards of the lock, but which were regarded as tests of the workman's skill. The honorary distinctions awarded to apprentices and aspirants in the art depended very much on the number and fine execution of these perforated keys. The locks, considered as fastenings, had slender merit; although usually throwing four bolts, they were not very secure. Fig. 13 represents the exterior of a lock made about the year 1730, by Bridou, a celebrated Parisian locksmith. It was a lock belonging to a coffer or strong

chest; all the works being sunk below the level of a carved architectural moulding or ornament. There is a secret opening near the part C, forming a portion of the ornamental de-

fig. 13. Exterior of an old secret lock.



fig. 14. The same, with a portion of the front let down, shewing the key-hole.

sign; it allows a bolt, shewn at D, fig. 14, acted on by the spring E, to be touched, by which a doorway opens upon the hinges at B B. A A are a sort of pilasters, which aid in forming a hold for the bolts. The little ornament at C is drawn down by the hand, opening the secret door and revealing the key-hole G. S S, O O, Z Z, are ornaments fastened on at *b c d*, fig. 14, by nuts and screws, intended to display the skill of the work-

man. The lock itself, access to the keyhole of which is obtained within the secret door, has nothing very remarkable about it.

Mr. Chubb, in his paper read before the Institute of Civil Engineers, illustrated the insecurity of the warded lock by the example of one which had actually been placed in the strong-room of a banking house, and which is represented in the



fig 15. Examples of true and false keys.

annexed cut (fig. 15). The wards are here shewn, surrounding the central key-pin; and from the appearance of the key, shewn at *a*, it is evident that these wards must have been rather complex. But the uselessness of the wards was proved by the result. A burglar employed an instrument, shaped like that at *b*, having on one of its faces, or sides, a layer of wax and yellow soap; this instrument, being introduced through the keyhole and turned a little way round, brought the soft composition in contact with the ends of the wards, and these ends thus left their impress on the composition. A false key was then made, as at *c*, which, however clumsy it may appear, has a cavity, or vacuity, where there is a cavity in the true key; and by such a surreptitious instrument was the lock opened. Even so rude an instrument as *d*, by passing round the wards, might open such a lock.

We are somewhat anticipating the full consideration of this

subject; but it is desirable at once to explain how and why an improvement on the warded lock was sought for.

In connexion with the fanciful eighteenth-century locks, lately adverted to, we may remark, that no less a man than Louis XVI. was an amateur workman in this department of mechanical art—or at least in smith's work, which in France is generally considered to include lock-making. Sir Archibald Alison says, in his *History of Europe:*—"He had an extraordinary fondness for athletic occupation and mechanical labour; insomuch that he frequently worked several hours a-day with a blacksmith of the name of Gamin, who taught him the art of wielding the hammer and managing the forge. He took the greatest interest in this occupation, and loaded his preceptor in the art with kindness; who returned it by betraying to the Convention a secret iron recess which they had together worked out in the walls of the cabinet in the Tuileries, wherein to deposit his secret papers during the storms of the Revolution." There are not wanting indications that the unfortunate monarch wrought upon locks, as well as upon safes and strong-rooms.

Besides wards, there have been numerous other contrivances for adding to the security of locks—including screws, escutcheons, spiral springs, wheel-and-pinion work, alarums, and multiple bolts. As these are not of sufficient importance to be treated in separate chapters, we shall here give just so much notice of them as will illustrate their general character. Some of them are found combined with the "tumbler" principle, presently to be described; but all of them, it is now well known, were employed in various ways when the tumbler lock was but little understood, and when the warded lock was held in esteem.

The Marquis of Worcester, whose curious *Century of Inventions*, written nearly two hundred years ago, contains so many suggestions which ingenuity has since developed into practical completeness, gives four of his inventions in the following words:—

69. "A way how a little triangle screwed key, not weighing a shilling, shall be capable and strong enough to bolt and unbolt, round about a great chest, an hundred bolts, through fifty staples, two in each, with a direct contrary motion; and as many more from both sides and ends; and, at the self-same time, shall fasten it to the place beyond a man's natural strength to take it away; and in one and the same turn both locketh and openeth it.

70. "A key with a rose-turning pipe and two roses pierced through endwise the hit thereof, with several handsomely contrived wards, which may likewise do the same effects.

71. "A key, perfectly square, with a screw turning within it, and more conceited than any of the rest, and no heavier than the triangle screwed key, and doth the same effects.

72. "An escutcheon, to be placed before any of these locks, with these properties: First, the owner, though a woman, may with her delicate hand vary the ways of causing to open the lock ten millions of times beyond the knowledge of the smith that made it, or of me that invented it. Second, if a stranger open it, it setteth an alarum a-going, which the stranger cannot stop from running out; and besides, though none shall be within hearing, yet it catcheth his hand as a trap doth a fox; and though far from maiming him, yet it leaveth such a mark behind it as will discover him if suspected; the escutcheon or lock plainly shewing what money he hath taken out of the box to a farthing, and how many times opened since the owner had been at it."

Mr. Partington, in his edition of the marquis's singular work, makes a few comments on these lock-and-key contrivances. He says that the lock is evidently intended to operate on the principle of applying a *screw* for the purpose of moving the bolt, instead of using a key as a lever for this purpose. That such a plan might be applied to locks generally, he observes, there can be no doubt; and by a similar contrivance the large keys at present in use for outer doors, iron chests, &c. might be advantageously reduced by this means. By

employing the escutcheon mentioned by the marquis, much additional security would be obtained. It must be confessed, however, that many of the marquis's statements are difficult to credit.

The escutcheon has been a favourite resource with lock-makers. Mr. Mordan's escutcheon, for instance, introduced before the Society of Arts in 1830, is a contrivance to be placed temporarily over the keyhole of a door, to prevent the picking of the lock during the owner's absence. The escutcheon, or "protector," has a short pipe which, after the door has been locked, is thrust into the keyhole; attached to the pipe is a small lock, on Bramah's or any other convenient principle, so contrived that, on turning its key, two lancet-shaped pieces fly out laterally and bury themselves in the wood. The escutcheon cannot be removed until the small key has reacted upon the small lock; and until this removal has taken place, the large key cannot reach the keyhole.

A curious application of the escutcheon principle attracted some attention among locksmiths about seventy years ago. One of the first premiums awarded by the Society of Arts, after the commencement of their "Transactions," was to Mr. Marshall, for a "secret escutcheon," in 1784. In his description of his new invention, he adverts to the marquis of Worcester's wonderful escutcheon, and to the many attempts which have since been made to produce an apparatus which should realise the marquis's description. He supposes that the letter padlock originated as one among many varieties of these imitative inventions; but this may be doubted. Mr. Marshall's contrivance, however, was in effect an endeavour to improve upon the letter-lock. He considered it an objection that, in ordinary locks of this kind, the letter-rings admit of no variation of place; and he sought to remedy this defect. It is not so much a new lock, as an escutcheon for a lock, which he produced. There is a studded bar passing through a barrel; there are five rings which work concentrically on this barrel; there are letters on the outer surfaces of the rings,

and notches on the inner surface; but when, by the usual puzzle-action of the rings, the notches in them have been brought into a right line with the studs of the bar, the result is, not that the hasp of a padlock is raised, but that the escutcheon is removed from the keyhole of an ordinary lock. Mr. Marshall's contrivance, therefore, is not so much a ring padlock, as a puzzle-ring security for the escutcheon of a fixed lock.

Some locks work by a screw and a spiral spring, instead of an ordinary key. Mr. W. Russell received a silver medal from the Society of Arts, about thirty years ago, for a new mode of locking the cocks of liquor-casks. Under ordinary circumstances, as is well known, the cock of a barrel or cask is in no way secure from the action of any one who can approach near enough to touch it; and different methods have been adopted of obtaining this security or secrecy. One plan is to employ a perforated cap, soft-soldered to the barrel of the cock, immediately over the grooved plug, the top of which plug is formed to the shape of the perforation, and a socket-key of the same form is introduced to turn the plug or open the lock. Another plan is to employ an iron saddle or staple, passing over the plug and below the bottom of the cock, through which a bolt is put, and a pendent padlock attached. The first method is very inefficient; the second is much superior, and has been largely adopted for locking the cocks of coppers, stills, vats, and other large vessels. But Mr. Russell thought some further improvement wanted. He caused a hole to be bored through the barrel, and to some depth into the plug when the latter is in the position for closing the cock. A stud works into this hole in such a way, that when the stud is driven home, the plug cannot be turned or the lock opened. The stud is attached at its other end to a spiral spring connected with a screw; a key is employed, the hollow pipe of which has an internal screw; and when this key is inserted in the cock-barrel and turned twice round, it draws back the stud, and allows the plug to be turned round in the proper way for opening the cock.

It is not often that wheel-and-pinion work is introduced into locks; the delicacy, the costliness, the weakness, and the tendency to get out of order, would all militate against the frequent adoption of such a course. It is, however, adopted occasionally. Mr. Friend's secret-lock, introduced to the notice of the Society of Arts in 1825, had a train of wheels which acted upon the bolt, driving it out whenever the circular arcs of three wheels moved against it, but allowing a spring to force it back again whenever a deep cleft in each of the wheels locked into a stud on the bolt. There were certain numbers on a guide-plate, and a power of combining these numbers in great variety; and a provision that the bolt could be unlocked only by the same combination of numbers which had locked it. The guide-plate was a separate piece of apparatus, carried in the pocket of the user as a companion to the key. The key was of no use without the guide-plate, nor the guide-plate without the key. The user 'set' the numbers on the guide-plate, then applied it to the face of the lock, then introduced the key into the key-hole, and turned the key partially round; the bolt was now shot, and the guide-plate removed. If the key were used without the guide-plate, the bolt might be locked, but it was always unlocked again by the time the key had made a complete circuit. There was considerable ingenuity in the idea of this lock; but we believe it never went further than a model. Indeed many of the locks elaborately described in books have never had an existence as acting working locks.

A very ingenious principle has been occasionally introduced, in which clock-work regulates the interval of time which must elapse before a lock can be opened, even with its proper key. The object is, to ensure the safety of the lock during a journey, or until a particular person be present, or until the locked article is conveyed to a particular room. A patent was taken out in 1831 for a lock on this principle by Mr. Rutherford, a bank agent at Jedburgh. Against the end of the bolt of the lock is placed a circular stop-plate, so

adjusted that the bolt cannot be withdrawn until a particular notch in the rim of the circular plate is opposite the end of the bolt. The plate is put in rotation by clock-work. As the notch can be set at pleasure to any required distance from the end of the bolt, the lock may be secured against being opened, either by its own or any other key, until any assigned number of minutes or hours after it has been locked; for the plate may be made to revolve either slowly or quickly, by varying the number of wheels in the clockwork. When the lock is used for boxes or portable packages, the clockwork must be moved and regulated by a spring; but when it is applied to closets or safes, a descending weight and a pendulum may be employed. It is manifest that this system is susceptible of being greatly varied in its mode of application; and it has many points of interest about it. That a man cannot open his own lock with his own proper key, until the lock gives permission by assuming a particular state or condition, certainly strikes one as being susceptible of many useful applications, where *time* is an element taken into the account.

A curious alarum-lock was invented by Mr. Meighan, in 1836, in which the bell or alarum is not placed behind a door, as in many alarum contrivances, but within the lock itself. Two or more studs are placed on the bolt, which press against the lower end of a small tumbler; the movement of the tumbler elevates a hammer; but as soon as the point of the tumbler becomes released from the stud, a spring presses the hammer down forcibly, and causes it to strike against a small bell placed near it. This sounding of the bell will be repeated, during the shutting of the bolt, as many times as there are studs to act upon the point of the tumbler.

Much of the ingenuity which has been displayed in locks depends on the employment of multiple bolts, there being all the additional strength which results from the use of two or more bolts instead of simply one. Ordinary doors seldom afford us examples of these double bolts; but they may be frequently seen in cabinets and desks, where two staples fixed to

the lid fall into two holes in tha lock, and are retained by two bolts. The most remarkable and complicated varieties, however, are those in which the bolts, instead of shooting parallel and nearly together, shoot in wholly different ways; one up, one down, one to the right, one to the left, and so on. It is on safes, strong boxes, and the doors of strong rooms containing valuable treasures, that such locks are usually placed. The mechanism is such that the key acts upon all the bolts at once, through the intervention of levers and springs of various kinds.



fig. 16. Multiple bolts of an old chest-lock.

The above woodcut represents a very curious specimen of these multiple-bolt locks. It is copied from the great French work; and the ponderous chest to which it is attached is, we are told by Réaumur, "known at Paris by the name of the strong German coffer." He further says, "nothing is wanting in these coffers on the score of solidity. They are made entirely of iron; or if of wood, they are banded both within and without with iron; and can only ba broken open by very

great violence. Their locks are almost as large as the top of the coffer, and close with a great number of holts. The one which we have engraved has twelve fastenings; they have been made with twenty-four, or more." His next remark on the subject is a sensible one: "Notwithstanding the large size of these locks, and all the apparatus with which they are provided, they correspond but ill with the solidity of the rest of the coffer. If we have given a representation of one, it is chiefly to shew how little confidence one could have in such a lock, and what are its defects, in order that we may avoid them." It is not difficult, by tracing the action of the several levers, to see how one movement of the key, in the centre of the lid, would act upon all the bolts. In the engraving (fig. 16) *a*, *f*, *h*, *c*, are the four corner bolts; six others, *a de*, *a de*, are on the long sides, three on each; and two, *b g*, on the short sides. Every bolt is provided with a spring, of which three or four are shewn at Z Z Z. There is no staple or box to receive each bolt; but all shoot or snap beneath the raised edge E running round the top of the box just within the exterior at A A. The keyhole in the front of the box at D is a deception or mask; the real keyhole is in the middle of the lid concealed by a secret door opened by a spring. When the key has moved the great central bolt, this acts upon the other bolts P Q R S T, &c.; V V are studs which act upon two of the bolts; Y Y are staples confining the great bolt; *k*, *l*, *c*, *p*, *x*, are small levers which transmit the action to the corner bolts; *q*, *r*, *s*, *t*, *n*, are the small levers which render a similar service to the side and end bolts; L L within the chest, and M M on the lid, are contrivances for limiting the movement of the latter; C H, H C are iron straps or bands by which the interior of the chest is strengthened. After all, this is not so much a lock as a series of spring latches.

If a lock can be picked, the picking is as effective whether the lock has one bolt or twelve bolts. This fact led Mr. Duce, in 1824, to construct, instead of a four-bolt lock, four distinct one-bolt locks, fixed in the same frame and opened by the

same key; the bolts to be moved in succession instead of simultaneously. It would require four times as long to pick this as a four-bolt lock of similar action.

There have been many other varieties of the multiple bolt, but we need not stop to describe them.

CHAPTER V.

ON TUMBLER, OR LEVER LOCKS.

SECURITY being the primary object in all locks, any considerations as to mechanical ingenuity and graceful decoration give place to those which relate to safety. A spring lock may be ingenious and even beautiful in its construction, but an imitative key will easily open it. Hence arose the invention of wheels or wards; and as wards failed in trustworthiness, they in their turn yielded to something better. We have already explained, how the insecurity of mere warded locks arises; and we shall have something more to say on the subject in a future chapter. It is sufficient here to remark, that wards, springs, screws, alarums, wheel-work, escutcheons,—all, however useful for particular purposes, are wanting in the degree of surety which we require in a lock. Hence the invention of *tumblers, levers*, or *latches*, which fall into the bolt and prevent it from being shot until they have been raised or released by the action of the key. We have been unable to ascertain at what time, or in what country, or by whom, tumbler-locks were invented. The invention has been claimed by or for persons subsequently to the year 1767, when the celebrated French treatise (*Art du Serrurier*) already referred to was published; and yet this treatise contains numerous examples of simple tumbler locks of ingenious construction, as will presently be shewn.

One of the most elementary forms of tumbler-lock is shewn in fig. 17. In this case the bolt, instead of having two notches in the bottom edge, like those in the back-spring lock, fig. 6,



fig. 17. Simple tumbler lock.

has two square notches or slots in the upper edge; and as the key acts upon the bolt, these notches must of course share in whatever movements the bolt is subjected to. Behind the bolt is a kind of latch or tumbler (the lower part of which is shewn by dotted lines), with a stump or projecting piece of metal at *a*; the tumbler moves freely on a pivot at the other end, and is made to rise through a small arc whenever the key acts upon the bolt. When the bolt is wholly shot, the stump falls into one notch and prevents the motion of the bolt; when wholly unshot or withdrawn, the stump falls into the other notch, and equally prevents the motion of the bolt. It is not, therefore, until the key, by elevating the tumbler, has raised the stump out of the notch, that the bolt has freedom of movement. If the shape of the key does not enable its web to effect this elevation to a sufficient degree, the bolt remains immovable; and to this extent a certain additional security is obtained by making the shape of the key significant as well as the wards.

The tumbler-principle, as we have said, is difficult to trace to its origin on account of the various aspects which it presents; but the great French treatise proves that the locksmiths of France were familiar with tumbler-locks a century ago. The plates of that work represent the details of numerous locks, on the upper edge of the bolts of which were notches called *encoches*, as at *o k* fig. 18; into these notches sank a

small iron stud or stump called the *arrêt du pêne*, or bolt-stop, shewn in fig. 19, attached to the upper portion of the *gâchette* or tumbler, which, for the sake of economy of metal, is made in the form of a triangular spring in front of the bolt *ki*; and not until the key, by its circular action, had raised this stud out of one or other of the notches, could the bolt move to the right or left. The stud was generally fixed to a spring which forced it down again into the notch as soon as the action of the key had ceased. Sometimes, however, the stud was fixed to the bolt, and the notches were in a separate tumbler or *gâchette* (see E E, fig. 21); and in other instances, again, the stump was fixed to the case of the lock and caught into notches in the bolt. It will be seen, when we come to treat of tumbler-locks of later date, that there was much in these early locks to point out the way. Fig. 19, copied from the French work, represents a lock of the box or casket kind. Two staples, fixed into the cover, fall into two cavities or receptacles at c d; and a short bolt in each receptacle catches into each staple, one near *g* and one near *h*. The small bolt *q* is attached to the upper extremity of the lever *q r s*, fig. 19, and shewn separately in fig. 20; and by the pressure of a spring *a* (fig. 19) upon this lever, the bolt



fig. 18.



fig. 19. Old French lock.

fig. 20.

q is kept locked in the staple. The vertical portion of this spring presses at its lower end on another spring *p* (fig. 19) of singular curvature; and attached to the horizontal part of this second spring is the stud, which falls into a notch in the top of the bolt. The action of these parts, then, is as follows: when the key is placed upon the key-pin at *z*, and turned round in the direction in which the hands of a watch move, the hitt presses against the tail *s* of the lever, moves it upon its centre *z*, fig. 19, *v*, fig. 20, to the left, and consequently moves the upper part *q* to the right, drawing it out of the receptacle and liberating the staple within C. Thus it will be seen that the lever *q r s*, held in one position by the spring *a*, forms in itself a simple kind of spring catch-lock, and was, in fact, formerly used as such, without any other appendages except the staple in the lever, into which the catch *q* fitted on shutting down the lid. So also we may regard the other portion, fig. 18, or *k i p h* (fig. 19), as forming a separate lock; for the key after having passed s comes in contact with the triangular spring, which it raises thereby, lifting the stud out of the bolt, and exerting pressure against the barbs of the bolt *n*. Fig. 18 shoots the bolt *k*, and also the short bolt *l*, which passes through the staple in the cavity *d*, fig. 19.

The lock represented in the four following figures is also

fig. 21. Details of an old French lock.

from M. de Réaumur's chapter on locks in the work referred to. In this lock the tumbler-principle is carried out in a very

elaborate manner, for not only is the stump or stud H (fig. 23) attached to a very strong spring (best shewn at H, fig. 22),



fig. 22. Another view of the same.

which holds it with considerable force in one of the three notches of the principal bolt RS (fig. 24); but there is also a second set of notches EE in the *gâchette* GO (fig. 21), and a pin



fig. 23. Another view of the same.

attached to one of the plates of the lock fits into one of these notches, thereby preventing the bolt from being moved until the *gâchette* is lowered by the revolution of the key; so that



fig. 24. The two bolts detached.

in attempting to pick this lock, not only must the spring H be raised so as to release the stud from the notches of the great bolt, but the *gâchette* must be lowered to disengage the fixed pin from the notches. There is yet a third source of security. Attached to the large bolt are short projecting pins F (fig. 21), against which an arm or detent, GF, of the *gâchette* projects, thus preventing the bolt from being shot back by any pressure applied to its extremity S.

There are a few details relating to this remarkable lock, which may as well be introduced here in order to complete the description. The principal bolt can be shot twice, or be *double-locked;* hence it is furnished with three barbs for the key to act against, and with three notches for the spring-stud. The lower bolt IK can be shot by the horizontal pressure of the button P (figs. 22, 23), which is situated on the inner side of the door to which this lock is attached, so that a person inside the room can secure the door against any one on the outside who is not furnished with the proper key, for it must be remarked that the small bolt as well as the large one is acted on by the key. Now supposing the small bolt to be shot or locked, it is kept so by the pressure of the coiled spring Q (figs. 21, 22). But this small bolt is connected with the large one by means of the bent lever ONM (figs. 21, 24), which turns on a pin N attached to the main bolt. Now, when both bolts are either fully shot or unshot, the arm ON lies flat against and parallel with the main bolt; but when the large bolt is unshot and the small one not moved, the arms ON, NM, fall into an inclined position, and the arm ON passing a little below the main bolt comes within the range of the web of the key, which in its revolution causes the bent lever to move upon its centre N, thereby restoring ON to its horizontal position, and at the same time causing the arm NM to move from right to left, or in the direction for unshooting the small bolt; the end of this arm thus catches into a mortise V (figs. 21, 24) in the small bolt, and immediately unlocks it.

But to return to the subject of tumbler-locks. About the

year 1778, Mr. Barron introduced that species of double-action (as it may perhaps be termed) which so greatly increases the security of the simple tumbler, fig. 17. In the tumbler-locks previously made, if the tumbler were raised sufficiently high, the lock could be opened: there was no such possibility as raising it *too* high; but Mr. Barron, by his invention, patented 31st October, 1778, rendered it absolutely necessary that a limit should be put to the height to which the tumbler should be raised, by rendering the bolt equally immovable whether the tumbler were too much or too little raised. Another important improvement was the introduction of two tumblers instead of one. The bolt has in its middle a slot or gating notched on both edges, the notches being fitted for the reception of studs fixed to the tumblers. Supposing the studs or stumps of the tumblers to be resting in the lower notches, they require to be elevated to the general level of the gating before the bolt can be moved; whereas, on the other hand, if the tumblers were raised ever so little too high, the studs will enter the upper notches, and prevent the shooting of the bolt. The lower edge, or belly, of each tumbler is acted on by the steps of the key during its circular movement; the leverage of the key being so exactly adjusted as to raise the tumbler to the desired height and no further. The tumblers are made unequally wide, so that steps or inequalities in the bit of the key are requisite to lift them both to the proper height. There are thus two improvements introduced: there are two tumblers instead of one, and each tumbler has a double instead of a single action.

This ingenious and very useful lock is represented, so far as regards its governing principle, in fig. 25. The bolt is here seen to have a peculiar slot or hole cut in it, consisting of a narrow horizontal passage or gating, with three notches above it and three below it. These double notches might be available even for one tumbler only; but Barron used two or more for the sake of additional security. In fig. 25 there are two tumblers shewn, expressed by dotted lines; both are hinged to



fig. 25. Action of Barron's tumbler-lock.

one pivot, both are raised by the same action of the key, but the stump on the one tumbler does not coincide in position with that on the other. It will be seen that if the studs of the tumblers rested in the lower notches, they would require to be elevated to the level of the gating before the bolt could be moved; while, on the other hand, if lifted too high, the stumps would be caught in the upper notches, and would equally prevent the passage of the bolt. The tumblers are unequally wide; and the bitt of the key is stepped or notched in a corresponding way, that there may be one step fitted to act upon each tumbler. Mr. Barron also adopted the reverse arrangement of having the stump on the bolt, and the openings in the tumblers; so that the principle of his patent may be concisely expressed as being "an arrangement to allow a stump on the tumbler to pass through an opening in the bolt, or a stump on the bolt to pass through an opening in the tumbler."

A very elaborate tumbler-lock, patented 23d February, 1790, by Mr. Rowntree, contrasts remarkably with the simplicity of Barron's lock. Mr. Rowntree's lock consisted of tumblers combined with revolving discs or wheels. Its mechanism may be understood from the following description and engravings. The same letters refer to the same parts in the several figures.

A A is the plate which encloses the whole mechanism of the lock, and fastens it to the door; B B is the bolt, guided in its motion by sliding under the bridges C D; E E are pillars

which support a plate covering the works; F are the circular wards surrounding the centre or key-pin; and *a* shews the position of the key, which, in turning round, acts in a notch *r* in the bolt, and propels it; G, the tumbler, is a plate situated beneath the bolt, and moving on a centre-pin at *d*; it has a catch or stump *e* projecting upwards, which enters the notches *f* or *g* in the bolt, and thereby retains the latter for backward



fig. 26.



fig. 27.



fig. 29.



fig. 28.

fig. 30.

Details of Rowntree's tumbler-lock.

or forward motion, as the case may be; H is a spring which presses the tumbler forward. The key *a*, in turning round, acts first against the part *c c* of the tumbler, and raises it so as to remove the stump from the notches; it can then enter the notch *r* in the bolt, and move it. So far there is no particular security; but Mr. Rowntree sought to obtain it by the following means. There is a piece of metal *h* fixed to the lower side of the tumbler, called the *pin*; when the tumbler is caught in either notch of the bolt, the pin applies itself to a cluster of

small wheels I, fitted on one centre-pin heneath the tumhler; the edges of these wheels stop the pin, and prevent the tumhler from heing raised. But each wheel has a notch cut in its circumference I; and it is only when the wheels are so placed that all their notches lie in a right line, that the pin can enter this compound notch and allow the tumhler to rise. Tha wheels must therefore he all adjusted to position; and this is effected hy a number of levers K centred on one pin at *k*; at the opposite end each lever has a tooth *m* entering a notch in the wheel belonging to it; so that when any lever is pressed outward, it turns its wheel round. Now this pressure of the levers is hrought about hy a spring *n* applied to each; and when so pressed, the levers rest against a pin *o* fixed in the plate. The key is so cut as to determine the extent to which tha levers shall act upon the wheels. The key first operates from the curved part *p p* of the levers K, and raising them, turns all the wheels I at once into the proper positions; in turning further round, it then operates on the part *c c* of the tumhler, causing the latter to rise and to release the holt; and in turning still further round, it (the key) seizes the notch *r* of the bolt, and shoots it. The key is cut into steps of different lengths, as shewn at V V; each step operates on its respective lever K in a different degree from the others; the notch at *s* acts upon the tumhler, and the plain part *t* moves the bolt.

We now proceed to notice the modern tumhler-lock. This was arranged hy Bird, whose patent, bearing date 29th October, 1790, was for a series of four double-acting tumhlers, differing in no respect from those patented by Barron, and closely resemhling those in use at the present time in the best tumhler-locks. We will describe the modern tumhler-lock more particularly when we have gone through a few historical details on the subject.

Messrs. Mitchell and Lawton ohtained a patent bearing date 7th March, 1815, for a lock in which were comhined with the holt and double-acting tumhlers, a series of movahle wards, and a revolving curtain for closing the key-hole. The

action of the wards was peculiar. On introducing any key or instrument, and passing it round, a number of movable wards or pieces were thrown out so as to prevent the key from being turned back or withdrawn. It was necessary therefore to pass round the key so as to unlock the lock, and if that were not possible, as in the case of a false key being used, it was held permanently, and could only be released by destroying the lock. When the bolt was once shot, the wards were carried up so as to leave a clear passage for the key. This lock does not appear ever to have come into use, on account of the violence required in case a wrong key should be used either by accident or design.

The detention of a wrong key in this lock appears to have suggested the contrivance of a *detector*. This was first made by Ruxton, whose patent is dated 14th May, 1816. His detectors were of various kinds, the object of each kind being to give information to the owner in case any one of the tumblers should be overlifted in an attempt to pick the lock, which fact would be discovered on the next application of the true key. This is precisely the object of the detector in tumbler-locks at the present day, and Ruxton accomplished it by somewhat similar means. He also had a contrivance for holding a false key, as in Mitchell and Lawton's lock; and he recommended this form of detector in the following words: "It is true that in this case the lock will have to be destroyed in order to open the door: the result is frightful; but we think the more terrible the result, the less likely would any one be to tamper with it."

We now come to Chubb's lock, patented 3d February, 1818, which consisted of double-acting tumblers and a peculiar kind of detector. This lock has been made the subject of various patents obtained in the years 1824, 1833, 1846, and 1847. This lock* consists of six separate and distinct double-acting

* The lock about to be described is the latest and most complete form of Chubb lock up to the date of the Great Exhibition. The various additions and alterations which have been made in the lock since that date will be noticed in a subsequent chapter.

tumblers, all of which must be raised to a particular height, neither more nor less, in order that the bolt may pass. It also comprises a *detector*, by which, should any one of the tumblers be lifted too high in an attempt to pick or open the lock by a false key, it would be immediately detected on the next application of the proper key. The tumblers are flat pieces of iron or steel, with the plane of the surface vertical, and pivoted at one end; and the following is the mode in which the key, the tumblers, and the bolt, are brought into mutual action.

The bolt shoots in and out of the lock in the usual way. It has a square stud or stump riveted on one surface; and it is to furnish obstructions to the passage of this stud that the tumblers are provided. All the six tumblers are pivoted to one pin at the end, giving to each of them a small leverage, each independent of the others. There are six springs which press these tumblers downwards, one to each tumbler. There is a longitudinal slot or gating in each tumbler, large enough to receive the stud of the bolt; and unless all the six slots (supposing there to be six tumblers) coincide in height or position, the stud will not have a clear passage for moving to and fro. Now the slots are purposely made nearer the upper edge in some of the tumblers than in others, all the six being different in this respect; so that if they are all lifted *equally*, the slots do not coincide, and the bolt and its stud will not pass. The tumblers must then be raised *unequally*, those to be most raised which have the slot nearest to the lower edge. To effect this, the bit of the key is cut into six steps or inequalities, each to act upon one particular tumbler, and each cut or stepped to the exact depth which will suffice for the proper raising of the tumbler. The key is inserted in the keyhole, and is turned; the six steps raise the six tumblers all to the proper height, to leave a clear passage along the slots; and the extreme end of the key then acts upon the bolt itself, and shoots it. To unlock it again, the same or a duplicate key must be used; for if another key be employed, differing by ever so little from the proper one, some one or more of the tumblers will be lifted either a

little too much or not quite enough; and in either case the stud of the bolt will catch above or below the slot, instead of having a clear line of movement along the slot itself. After both locking and unlocking, the springs force the tumblers down as far as they can go, burying the stud in the recesses above the slot; so that the tumblers must be raised by the key both for locking and unlocking.

The doctrine of chances has wide play in determining the relative position of the six tumblers. In Mr. Chubb's essay this part of the subject is treated in the following way: "The number of changes which may be effected on the keys of a three-inch drawer-lock is $1 \times 2 \times 3 \times 4 \times 5 \times 6 = 720$, the number of different combinations which may be made on the six steps of unequal lengths (on a six-tumbler lock), without altering the length of either step. The height of the shortest step is, however, capable of being reduced 20 times; and each time of being reduced, the 720 combinations may be repeated; therefore $720 \times 20 = 14{,}400$ changes. The same process, after reducing the shortest step as much as possible, may be gone through with each of the other five steps; therefore $14{,}400 \times 6 = 86{,}400$, which is the number of changes that can be produced on the six steps. If, however, the seventh step, which throws the bolt, be taken into account, the reduction of it only ten times would give $86{,}400 \times 10 = 864{,}000$, as the number of changes on locks with the keys all of one size (that is, with one key of definite size in all save the lengths of the steps). Moreover, the drill pins of the locks and the pipes of the keys may be easily made of three different sizes; and the number of changes will then be $864{,}000 \times 3 = 2{,}592{,}000$, as the whole series of changes which may be gone through with this key. In smaller keys, the steps of which are capable of being reduced only ten times, and the bolt-step only five times, the number of combinations will be $720 \times 10 \times 6 \times 5 \times 3 = 648{,}000$. On the other hand, in larger keys, the steps of which can be reduced thirty times, and the bolt-step twenty times, the total number of combinations will be $720 \times 30 \times 6 \times 20 \times 3 = 7{,}776{,}000$."

These enormous numbers have been the cause of much of the wunderment which the six-tumbler locks have excited; and, as we shall see further on, the Bramah lock presents still more of the marvellous in respect to this ringing of the changes.

The construction and action of the Chubb lock may be further illustrated by means of an engraving, fig. 31, in which *b* is the bolt of the lock, with a stump riveted to it marked *s*. The six tumblers are shewn perspectively, the front or anterior one being marked *t*; they all move on the centre-pin *a*, but are nevertheless perfectly distinct and separate, to allow of being elevated to different heights. At *d* is shewn one end of a divided spring, the divisions being equal



fig. 31. Chubb lock, with detector and six tumblers.

to the number of tumblers, one to each, and so bent that each spring may press upon its particular tumbler. At *e* is the detector-spring, so placed that a projecting piece in the hindmost tumbler shall be near it; this tumbler having also fixed into it a stud or pin *p*. This being the arrangement, especially in relation to the stump s and the tumblers, it follows that all the tumblers must be lifted to exact and regulated heights in order that the stump may pass through the longitudinal slits of the tumblers; unless it can do so, the bolt cannot be withdrawn. As there are gaps or notches in each tumbler both

above and below the proper line of passage, and as there are no ordinary means of ascertaining when any one tumbler is lifted too high or not high enough, the safety of the lock is greatly increased by this uncertainty; especially when it is considered that this uncertainty is multiplied sixfold by the different modes in which the six tumblers are slotted. If, through the insertion of a false key, or by any other cause, any one of the tumblers be raised above its proper position, the detector spring *e* will catch the hindmost tumbler, and retain it so as to prevent the bolt from passing; and thus, upon the next application of the true key, it will be instantly felt that some one of the tumblers has been overlifted, because the true key will not unlock it. To relieve the bolt from this temporary imprisonment, the key must be turned the reverse way, as for locking; all the tumblers will thus be brought to their proper position, and allow the stump to enter the notches *n n;* the bevelled part of the bolt will then lift up the detector-spring, and allow the hindmost tumbler to fall down into its proper place; and all this being effected, the lock may be opened and shut in the ordinary way. The pin *p* is so adjusted that if any one of the tumblers—front, back, or intermediate—be lifted too high, the pin will be lifted with it, and will catch into the detector-spring, thus producing the result just described.

The key is represented in fig. 32. It has six steps, besides a terminal step to act upon the bolt. The height of each step, or the distance to which it extends from the pipe of the key, depends of course on the height to which its corresponding tumbler is to be lifted; and it matters not whether the steps of the key are adjusted to the slots of the tumblers, or the slots to the steps, provided the agreement be brought about. It is simply a matter of manufacturing convenience that the key-steps are cut first and the tumbler-slots after-

fig. 32.
Key to Chubb's lock.

wards. We may here remark that *bit*, or *bitt*, is the name given, somewhat indefinitely, either to the whole flat part of a key, or to the small stepped portions of it. The flat part was formerly termed the *web* of the key, probably from the *webbed* appearance of the keys to complex warded locks.

After the reading of Mr. Chubb's paper before the Institution of Civil Engineers, Mr. Owen narrated one or two circumstances connected with the early history of Chubb's lock. A convict on board one of the prison-ships at Portsmouth dockyard, who was by profession a lock-maker, and who had been employed in London in making and repairing locks for several years, and subsequently had been notorious for picking locks, asserted that he had picked with ease one of the best of Bramah's locks, and that he could pick Chubb's locks with equal facility. One of the latter was secured by the seals of the late Sir George Grey, the Commissioner, and some of the principal officers of the dockyard, and given to the convict, together with files and all the tools which he stated were necessary for preparing false instruments for the purpose, as also blank keys to fit the pin of the lock. A lock exactly the same in principle was placed in his hands, that he might examine it and make himself master of its construction. If he succeeded in opening the lock, he was to receive a free pardon from the Government, and a reward of 100*l.* from Messrs. Chubb. After trying for two or three months to pick the sealed lock—during which time, by his repeated efforts, he frequently over-lifted the detector, which was as often re-adjusted for his subsequent trials—he gave up the attempt. He stated that Chubb's were the most secure locks he had ever met with, and that it was impossible for any man to pick or to open them with false instruments.

Mr. Owen further stated, that in order to compare the merits of Bramah's and Chubb's locks, he had suggested a mechanical contrivance, which was applied to one of Bramah's six-spring padlocks belonging to the Excise. It was hung

upon a nail, in a vertical position, secure from lateral oscillation. A self-acting apparatus was then applied, consisting of a pipe with hexagonal grooves, and a stud or bit corresponding with the division of the lock, and secured to it by a spring. In the grooves of this pipe small slides were inserted, which pressed against the spring keys of the lock; to these slides were attached levers, acted upon by eccentrics, moved by a combination of wheels, whose teeth differed in number so as to perform the permutation required for the different depths of the spring keys, corresponding with those of the proper key to the lock. The automaton machine was set in motion by a line working over a barrel, and acted upon by a weight; and was thus left acting upon the mechanism for a considerable time. At right angles to the pipe or false key was attached a rod and weight; and when the notches in the spring keys were brought in a line with the plane of the plate or diaphragm of the lock, the rod and weight turned the false key, opened the lock, and stopped the further motion of the automaton. In that state the slides indicated the exact depth of the grooves in the proper key, and gave the form of a matrix by which to make a key similar to the original one. The automaton worked during a period varying from half an hour to three hours, according to the state of permutation of the apparatus at the moment of being applied, compared with that of the slides in the lock. We confess that it is difficult to understand the action of this automaton from Mr. Owen's description. We imagine that the false notches would effectually prevent the operation of the instrument, and openings would be required on each slide to bring it back, so as to meet the motions of the machine.

Mr. Owen did not state whether his apparatus had been successful with one only of Bramah's locks or with several; nor did he describe any apparatus invented with the view to the picking of Chubb's locks. He stated, however, that in order to ascertain the effect of friction on one of these last-named locks, it was subjected to the alternate rectilinear motion of a steam-engine in Portsmouth dockyard, and was locked

and unlocked upwards of 460,000 times consecutively, without any appreciable wear being indicated by a gauge applied to the levers and the key, both before and after this alternate action. Mr. Owen concluded by expressing his individual opinion that Chubb's lock had never been picked. "The detector was the main feature of its excellence; and additional precaution, therefore, was only departing from its simplicity, and adding to the expense, without any commensurate advantage."

In a subsequent chapter the degree of security afforded by various descriptions of locks, and the obstacles which they present of being picked, will come under notice; we therefore now proceed to describe briefly a few other tumbler-locks, or application of the tumbler-principle.

In Mr. Somerford's lock, for which the Society of Arts gave a premium in 1818, an attempt was made to improve upon the ordinary action of tumblers. In most such locks, all the tumblers must ascend, although to different heights, before the stud of the bolt can pass through the slots; "which arrangement," says Mr. Somerford, "gives an opportunity of introducing a nail, or a piece of stout wire, into the lock, and thus raising the tumblers without the necessity of using the key." In his new lock, however, he made one lever to ascend while the other descended, by a somewhat complicated arrangement of slotted plates above and below the bolt. The key was so perforated as to be much endangered in respect to strength.

In Davis's lock there is a double chamber with wards on the side of the key-hole. The key is inserted into the first chamber and turned a quarter round; it is then pushed forward into the inner chamber, where there is a rotating plate containing a series of small pins or studs, which are laid hold of by the key. By turning the key, the plate is moved round, the tumbler is raised, and the bolt is shot backwards and forwards. This lock, which is somewhat expensive, is used to some extent on Cabinet despatch-boxes.

The lock invented by Mr. Nettlefold is so constructed,

that when the bolt is shot out by the key, two teeth or quadrants are projected from the sides of the bolt, which take a firm hold of the plate fixed on the door-post or edge. This construction is said to answer well for sliding-doors.

Mr. Alfred Ainger, in 1820, received a silver medal from the Society of Arts for a draw-back spring latch, in which the objects proposed were the two following—to render the lock more difficult of violation by a pick than those ordinarily in use; and to apply to it a key of which no ordinary person could take an impress, and which would be difficult of access even in a workman's hand. The key is very peculiar; its pipe consists of three divisions, the section of the upper and lower divisions being circular, and that of the middle division triangular; the triangular portion is intended to give motion to some part of the interior of the lock during the rotation of the key. There are collars fixed on the extremity of the key, to act each on one tumbler; and there are modes, by varying the arrangement of these collars on an octagonal stem, to give something like a permutation to the number of variations to which the action of the key may be subject. The notches or slots are rather in the bolt than in the tumblers; and there are many peculiarities in the general arrangement.

In a lock invented and patented by Mr. Parsons, the tumblers are of a particular form, being hinged on a pivot at their centres, and working into and out of two notches cut in the under side of the bolt. It must be obvious that many variations in the adjustment of the tumblers of locks might be made, without vitiating the principle on which the action depends.

Many inventors have tried the use of an expanding web to the key, so planned that if the step of the web be long enough to reach the tumbler, it would be too long to pass through the key-hole; and therefore a principle of safety would operate by enabling the key to adjust itself at one moment to the size of the key-hole, and at another to the height of the tumbler. Mr. Machin of Wolverhampton invented such a key in 1827. The web of the key is movable on a countersunk

pin, on which it can so far slide as to be drawn one-eighth of an inch from the barrel. The key-hole is of such a size as to admit the key only when the web is pressed close up to the barrel. When the key in this state is introduced, and is begun to be turned round, one of the notches in the web works into a raised circular edge of steel, placed eccentrically with regard to the lock-pin; so that as the key is turned, the web becomes drawn out, and is at its greatest elongation when it arrives at the tumblers: in the second half of its circular movement, the key becomes contracted to its original dimensions, and can then be removed from the lock.

Another mode of modifying the key has been introduced by Mr. Mackinnon, the object being to enable any person to change at will the pattern or arrangement of the movable parts of a lock and key; or to keep the key, when not actually in use, in such a state as to render it unavailing to any one but himself. It was a complex arrangement, which does not seem to have come much into use.

The lock invented by Mr. Williams, in 1839, may be designated a pin-lock, involving a principle analogous in many points to that of the Egyptian lock. This lock has a series of pins which reach through the cap, and are pressed to their places with a key like a comb or a rake-head. On the inner end of each pin is a flat piece of steel, in which is cut a notch for the passage of the bolt; but this passage is not clear until the notches in all the pieces of steel are in a right line. The pins are movable, and can be pushed either too far or not far enough to bring about the coincidence of position in the notches; and on this ground they are "double-acting." Now the teeth of the key are of irregular lengths, each having a length just suited for pushing the pin to the proper depth: any other lengths of teeth would fail to open the lock. There is a mechanism of springs and levers to shoot the bolt when the pins in the plate are rightly adjusted. The arrangements in respect to the key are singular and somewhat awkward. The teeth which lock the bolt are not the same as those

which unlock it, the user having to change ends and adjust the bit to a socket-handle. This is one among many examples in which a lock embodies several principles, the inventor having set himself the task of combining the excellences of many diverse locks.

In respect to the tumbler-locks generally, the simplicity of action, the strength of construction, and the non-liability of disarrangement, have given them a high place among safety-locks. The only danger seemed to be, that any person once obtaining possession of the key could take an impression from it, and thence form a key which would command the lock. Attempts have been occasionally made to obviate this danger, by supplying the key with movable bits which could be changed at pleasure, so as to constitute any number of effectively different bits in succession. But the locks being so constructed that the bolt could only be moved when the tumblers were in a certain position, the owner was placed in this predicament: that it was useless to alter the arrangement of the bits in the key, unless the tumblers were altered in a corresponding manner; and this would entail the removal of the lock from the door, and the re-arrangement of the interior mechanism.

One of the great defects of tumbler-locks made previously to the last ten years was, that the tumblers, when lying at rest in the lock, presented at their *bellies* or lower edges precisely the same arrangement as the steps of the key. Indeed, in many locks of the present day, a good idea of the form of the key may be gained by feeling the bellies of the tumblers. The bellies are in fact cut out so as to compensate for the circular motion of the key, to allow them to remain at rest while the stump is passing through the gating. Even in tumbler-locks of the best construction the tumblers will vibrate more or less during the motion of the key; a defect which must be provided against in adjusting the lock, or the stump will be caught in its passage through the gating. Mr. Hobbs provides a simple remedy by enlarging the back part of the

gating, the effect of which is as follows: when, in shooting back the bolt, as in unlocking, the key has got to its highest point, the stump enters the narrow end of the gating; but in shooting the bolt forward, as in locking, the stump enters the gating before the key has got to its highest point, and to allow for the slight vibratory motion of the tumblers during the passage of the stump, the gating is widened. The usual method of adjustment is to alter the forms of the bellies of the tumblers, thus greatly risking the security of the lock, a defect which was clearly perceived by Bramah [see pp. 67-70], and was one of the reasons which induced him to construct locks with slides instead of tumblers.

American locks on the tumbler-principle, and the relation which all such locks bear to the Bramah lock, will be better understood after the details of the following chapter.

CHAPTER VI.

THE BRAMAH LOCK.

The lock which was invented by the late Mr. Bramah deservedly occupies a high place among this class of contrivances. It differs very materially from all which has gone before it; its mechanical construction is accurate and beautiful; its key is remarkable for smallness of size; and the invention was introduced by the publication of an essay containing much sensible observation on locks generally. The full title of this essay runs thus: "A dissertation on the Construction of Locks. Containing, first, reasons and observations, demonstrating all locks which depend upon fixed wards to be erroneous in principle, and defective in point of security. Secondly, a specification of a lock, constructed on a new and infallible principle, which, possessing all the properties essential to security, will

prevent the most ruinous consequences of house-robberies, and be a certain protection against thieves of all descriptions." A second edition of this *Dissertation* was published in 1815; but the work is now extremely scarce, and hardly attainable.

It is remarkable to observe the boldness and self-relying confidence with which Mr. Bramah, some sixty years ago, declared that *all* locks were, up to that time, violable; he felt that this was strictly true, and he hesitated not to give expression to his conviction. The following is from his *Dissertation*:—

"It is observable that those who are taken in the desperate occupation of house-breaking are always furnished with a number and variety of keys or other instruments adapted to the purpose of picking or opening locks; and it needs no argument to prove that these implements must be essential to the execution of their intentions. For unless they can secure access to the portable and most valuable part of the effects, which in most families are deposited under the imaginary security of locks, the plunder would seldom recompense the difficulty and hazard of the enterprise; and till some method of security be adopted by which such keys and instruments may be rendered useless, no effectual check or opposition can be given to the excessive and alarming practice of house-breaking.

"Being confident that I have contrived a security which no instrument but its proper key can reach; and which may be so applied as not only to defy the art and ingenuity of the most skilful workman, but to render the utmost force ineffectual, and thereby to secure what is most valued as well from dishonest servants as from the midnight ruffian, I think myself at liberty to declare (what nothing but the discovery of an infallible remedy would justify my disclosing), that all dependence on the inviolable security of locks, even of those which are constructed on the best principle of any in general use, is fallacious. To demonstrate this bold and alarming proposition, I shall first state the common principles

which are applied in the art of lock-making; and by describing their operation in instruments differently constructed, prove to my intelligent readers that the best-constructed locks are liable to he secretly opened with great facility; and that the locks in common use are calculated only to induce a false confidence in their effect, and to throw temptation to dishonesty in the way of those who are acquainted with their imperfections, and know their inefficacy to the purpose of security" (p. 5).

Tumblers had been so little thought of and used at the time Bramah wrote, that his attention was almost exclusively directed to *warded* locks. The mysterious clefts in a key, connected with some kind of secret mechanism in the lock, had given the warded locks a great hold on the public mind, as models of puzzlement and security; and it was to shew that this confidence rested on a false basis, that he to a great extent laboured. The following is his exposition of the principle and the defects of the warded lock.

"Locks have been constructed, and are at present much used and held in great esteem, from which the picklock is effectually excluded; but the admission of false keys is an imperfection for which no locksmith has ever found a corrective; nor can this imperfection be remedied whilst the protection of the bolt is wholly confided to fixed wards. For if a lock of any given size be furnished with wards in as curious and complete a manner as it can be, those wards being necessarily expressed on what is termed hy locksmiths the bit or web of the key, do not admit of a greater number of variations than can be expressed on that bit or web; when, therefore, as many locks have been completed of the given size as will include all the variations which the surface of the bit will contain, every future lock must be the counterpart of some former one, and the same key which opens the one will of course unlock the other. It hence follows that every lock which shall be fabricated on this given scale, beyond the number at which the capability of variation ends, must be as subject to

the key of some other lock as to its own; and both become less secure as their counterparts become more numerous. This objection is confirmed by a reference to the locks commonly fixed on drawers and bureaus, in which the variations are few, and these so frequently repeated, from the infinite demand for such locks, that, even if it were formed to resist the picklock, they would be liable to be opened by ten thousand correspondent keys. And the same observation applies in a greater or less degree to every lock in which the variations are not endless.

"But if the variation of locks in which the bolt is guarded only by fixed wards could be multiplied to infinity, they would afford no security against the efforts of an ingenious locksmith; for though an artful and judicious arrangement of the wards, or other impediments, may render the passage to the bolt so intricate and perplexed as to exclude every instrument but its proper key, a skilful workman having access to the entrance will be at no loss to fabricate a key which shall tally as perfectly with the wards as if the lock had been open to his inspection. And this operation may not only be performed to the highest degree of certainty and exactness, but is conducted likewise with the utmost ease. For the block or bit, which is intended to receive the impression of the wards, being fitted to the keyhole, and the shank of the key bored to a sufficient depth to receive the pipe, nothing remains but to cover the bit with a preparation which, by a gentle pressure against the introductory ward, may receive its impression, and thus furnish a certain direction for the application of the file. The block or bit being thus prepared with a tally to the first ward, gains admission to the second; and a repetition of the means by which the first impression was obtained, enables the workman to proceed, till by the dexterous use of his file he has effected a free passage to the bolt. And in this operation he is directed by an infallible guide; for, the pipe being a fixed centre on which the key revolves without any variation, and the wards being fixed likewise, their position must be accu-

rately described on the surface of the bit which is prepared to receive their impression. The key therefore may be formed and perfectly fitted to the lock without any extraordinary degree of genius or mechanical skill. It is from hence evident that endless variations in the disposition of fixed wards are not alone sufficient to the purpose of perfect security. I do not mean to subtract from the merit of such inventions, nor to dispute their utility or importance. Every approach towards perfection in the art of lock-making may he productive of much good, and is at least deserving of commendation; for if no higher benefit were to result from it, than the rendering difficult or impossihle to many that which is still practicable and easy to a few, it furnishes a material security against those from whom the greatest mischiefs and dangers are to be apprehended."

There can he little doubt, in the present day, that Bramah did not over-rate the fallacies embodied in the system of wards for locks. He was sufficiently a machinist to detect the weak points in the ordinary locks; and, whatever may have heen his over-estimate of his own lock (presently to be described), he was certainly guilty of no injustice to those who had preceded him; for their locks were substantially as he has described them. To understand the true bearings of his Dissertation too, we mnst remember that housebreaking had risen to a most dering height in London at the time he wrote (ahout the middle of the reign of George III.); and men's minds were more than usually absorbed hy considerations relating to their doors and locks.

Mr. Bramah, after doing due justice to the ingenuity of Barron's lock, in which, if the tumhler he either *over* lifted or *under* lifted the lock cannot he opened, pointed out very clearly the defective principle which still governed the lock. "Greatly as the art is indehted to the ingenuity of Mr. Barron, he has not yet attained that point of excellence in the construction of his lock which is essential to perfect security. His improvement has greatly increased the difficulty hut not precluded the

possibility of opening his lock by a key made and obtained as above described (by a wax impression on a blank key); for an impression of the tumblers may be taken by the same method, and the key be made to act upon them as accurately as it may be made to tally with the wards. Nor will the practicability of obtaining such a key be prevented, however complicated the principle or construction of the lock may be, whilst the disposition of its parts may be ascertained and their impression correctly taken from without. I apprehend the use of additional tumblers to have been applied by Mr. Barron as a remedy for this imperfection." Mr. Bramah thought that Barron had a perception of a higher degree of security, but had failed to realise it; because, by giving a uniform motion to the tumblers, and presenting them with a face which tallies exactly with the key, they still partake in a very great degree of the nature of fixed wards, and the security of the lock is thereby rendered in a proportionate degree defective and liable to doubt.

To shew how this insecurity arises, Mr. Bramah illustrates the matter in the following way: "Suppose the key with which the workman is making his way to the bolt to have passed the wards, and to be in contact with the most prominent of the tumblers. The impression, which the slightest touch will leave on the key, will direct the application of the file till sufficient space is prepared to give it a free passage. This being accomplished, the key will of course bear upon the tumbler which is most remote; and being formed by this process to tally with the face which the tumblers present, will acquire as perfect a command of the lock as if it had been originally made for the purpose. And the key, being thus brought to a bearing on all the tumblers at once, the benefit arising from the increase of their number, if multiplied by fifty, must inevitably be lost; for, having but one motion, they act only with the effect of one instrument."

It is worthy of notice, that even while thus shewing the weak points of the Barron lock, Mr. Bramah seems to have

had in his mind some conception of infallibility or inviolability attainable by the lock in question. After speaking of the defect arising from the bad arrangement of the tumblers, he says: "But nothing is more easy than to remove this objection, and to obtain perfect security from the application of Mr. Barron's principle. If the tumblers, which project unequally and form a fixed tally to the key, were made to present a plane surface, it would require a separate and unequal motion to disengage them from the bolt; and consequently no impression could be obtained from without that would give any idea of their positions with respect to each other, or be of any use even to the most skilful and experienced workman in the formation of a false key. The correction of this defect would rescue the principle of Mr. Barron's lock, as far as I am capable of judging, from every imputation of error or imperfection; and, as long as it could be kept unimpaired, would be a perfect security. But the tumblers, on which its security depends, being of slight substance, exposed to perpetual friction—as well from the application of the key as from their own proper motion—and their office being such as to render the most trifling loss of metal fatal to their operation, they would need a further exertion of Mr. Barron's ingenuity to make them durable."

It may perhaps be doubted whether the principle of Bramah's lock is not more clearly shewn in the original constructed by him than in that of later date. In appearance it is totally different, but the same pervading principle is observable in both; and the cylinder lock can certainly be better understood when this original flat lock has been studied. The annexed woodcut is taken from the first and very scarce edition of Mr. Bramah's *Dissertation;* the description is somewhat more condensed, but perhaps sufficient for the purpose.

The lock is supposed to be lying flat, with the bolt B half-shot. Ranged somewhat diagonally are six levers, turning on a horizontal joint or pivot at A, each lever having a slight extent of vertical motion independent of the others. Each

lever rests on a separate spring of sufficient strength to sustain its weight, or, if depressed by a superior force, to restore it to its proper position when the force is withdrawn. F is a



fig. 33. Bramah's first model.

curved piece of metal, pierced with six grooves or passages; these grooves are exactly equal in width to the thickness of the levers, but are of sufficient depth to allow the levers a free motion in a perpendicular direction. The ends of the levers are inserted in these grooves, and have this freedom of motion, whether lifted by the elastic power of the springs or depressed by a weight from above. In the bolt B is a notch to receive a peculiarly-shaped lever, which shoots or withdraws the bolt according as it traverses to the right or the left. This lever, the six long levers, the springs beneath them, the bent piece F, and the pivot, all alike are fixed to a circular platform P, which turns on a centre; so that if any force can make this platform turn partially round, the bolt must be shot or unshot by the lever which works in the notch. The six long levers

are the contrivances whereby the platform shall *not* be allowed to turn until the proper moving agent (the key) shall have been applied, the plate *p* being one of the assistants in this obstruction. This plate, which is hollow underneath, has six notches in one of its edges; the points of the levers catch into these notches; and while so caught, the levers cannot move horizontally, and all the machinery is at a stand-still. To enable the key to set the mechanism in action, other contrivances are necessary. Each lever has a notch at its extreme end, and the six are notched very irregularly in respect one to another. These notches must be brought all into one plane, to enable the levers to pass horizontally out of the notches in the plate, in the same way as the two prongs of a fork might traverse one above and the other below the blade of a knife; and when the lever-notches are in this position, all in one plane and in the plane of the plate, the levers can be moved, and with it the stump which shoots the bolt. To ensure this due pressing down of the levers, a key is used such as is shewn in the cut, having six steps or bits to correspond with the six levers; this key, put upon the pin K, presses down all the levers to the exact distance necessary for bringing their notches into one plane, viz. the plane of the plate; the key then being turned round turns the movable platform F, and shoots the bolt. It is evident at a glance, that unless the various steps of the key are so cut, that each shall press down its own lever to the proper extent, the ends of the levers cannot pass the notches in the plate, and the bolt can neither be locked nor unlocked.

It may be well to give Bramah's own words in relation to this lock: "I may safely assert that it is not in art to produce a key or other instrument by which a lock constructed on this principle can be opened. It will be a task, indeed, of great difficulty, even to a skilful workman, to fit a key to this species of lock, though its interior face were open to his inspection; for the levers being raised by the subjacent springs to an equal height present a *plane* surface, and consequently

convey no direction that can be of any use in forming a tally to the *irregular* surface which they present when acting in subjection to the proper key. Unless, therefore, a method be contrived to bring the notches on the ends of the levers in a direct line with each other, and *to retain them in that position till an exact impression of the irregular surface which the levers will then exhibit can be taken*, the workman will in vain attempt to fit a key to the lock, or by any effort of art to move the bolt. And when it is considered that this process will be greatly impeded, and may perhaps be entirely frustrated, by the action of the springs, it must appear that great patience and perseverance, as well as great ingenuity, will be required to give any chance of succeeding in the attempt. I do not state this circumstance as a point essential or of any importance to the purpose of the lock, but to prove more clearly what I have before observed upon its principle and properties; for if such difficulties occur to a skilled workman, as to render it almost, if not altogether impracticable to form a key when the lock is open to his inspection and its parts accessible to his hand, it pretty clearly demonstrates the impossibility of accomplishing it when no part of the movement can be touched or seen."

It is evident that Mr. Bramah had his thoughts directed to that mode of picking locks which depends on taking impressions of the moving parts, rather than to the *mechanical* or *pressure* method which has been developed in later times. There can be little doubt that a lock was, to his mind, a beautiful and admirable machine, far elevated above the level of mere blacksmith's work; and his name will ever be associated with what may be termed the philosophy of lock-making.

After the model-lock, which has just been described, was constructed, and found to corroborate the idea which was working in Mr. Bramah's mind, he proceeded to the construction of his barrel or cylinder-lock, embracing similar elements placed in more convenient juxta-position. In his Essay he gives an engraving to illustrate the principle on which his lock

acts, rather in the manner of a diagram than as depicting any lock actually made; his main object being to impart a clear notion of the action of the slides which form such a distinguishing feature in his lock.



Fig. 34. Diagram to illustrate the Bramah lock.

Viewed in this sense, therefore, simply as an illustrative diagram, the annexed cut may represent the action of the safety slides. B is a sliding bar or holt, having a power of longitudinal motion in the frame F. This frame has six notches cut on each of its long sides, the two series being exactly opposite each other; and there are six similar notches cut in the bolt B. The concurrent effect of all these eighteen notches is, that the six slides *abcdef* can move freely up and down across the bolt. When the slides are thus placed, the bolt cannot move, and may in this case be considered to be locked. There are six clefts or notches in the six slides, one to each (1, 2, 3, 4, 5, 6); and until all these are brought in a right line, the holt cannot move through them. If a tally or key be prepared, as shewn at T in the lower part of the cut, with six projections, and if these projections thrust up the six slides till their clefts rise to the plane of the bolt, then can the bolt be withdrawn or the lock opened. This serves to illustrate the relation between the slides and the key, as carried out in the way now to be described.

One peculiarity of the Bramah lock is, that from the

essential part of the apparatus being a barrel or cylinder, much of the working can be conducted in the lathe; and this has given a beauty to the details generally and deservedly admired. Mr. Bramah, when he worked out the theory of his lock, resolved to discard altogether the use of fixed wards, and also the use of tumblers working on a pivot at one end; substituting in their stead a system of slides, working in a very novel way. The body of a Bramah lock may be considered as formed of two concentric brass barrels, the outer one fixed, and the inner rotating within it. The inner barrel has a projecting stud, which, while the barrel is rotating, comes in contact with the bolt in such a way as to shoot or lock it; and thus the stud serves the same purpose as the bit of an ordinary key, rendering the construction of a bit to the Bramah key unnecessary. If the barrel can be made to rotate to the right or left, the bolt can be locked or unlocked; and the problem is, therefore, how to ensure the rotation of the barrel. The key, which has a pipe or hollow shaft, is inserted in the keyhole upon the pin, and is then turned round; but there must be a very nice adjustment of the mechanism of the barrel before this turning round of the key and the barrel can be ensured. The barrel has an external circular groove at right angles to the axis, penetrating to a certain depth; and it has also several *internal* longitudinal grooves, from end to end. In these internal grooves thin pieces of steel are able to slide, in a direction parallel with the axis of the barrel. A thin plate of steel, called the locking-plate, is screwed in two portions to the outer barrel, concentric with the inner barrel; and at the same time occupying the external circular groove of the inner barrel; this plate has notches, fitted in number and size to receive the edges of the slides which work in the internal longitudinal grooves of the barrel. If this were all, the barrel could not revolve, because the slides are catching in the grooves of the locking-plate; but each slide has also a groove, corresponding in depth to the extent of this entanglement; and if this groove be brought to the plane of the locking-plate,

the barrel can be turned, so far as respects that individual slide. All the slides must, however, be so adjusted that their grooves shall come to the same plane; but as the notch is cut at different points in the lengths of the several slides, the slides have to be pushed in to different distances in the barrel, in order that this juxta-position of notches may be ensured. This is effected by the key, which has notches or clefts at the end of the pipe equal in number to the slides, and made to fit the ends of the slides when the key is inserted; the key presses each slide, and pushes it so far as the depth of its cleft will permit; and all these depths are such that all the slides are pushed to the exact position where their notches all lie in the same plane; this is the plane of the locking-plate, and the barrel can he then turned.

This is the principle which Mr. Bramah adopted; and we have now to trace it, step hy step, hy means of illustrative



fig. 35. Exterior of a Bramah lock.

details. Fig. 35 represents the exterior of a box or desk lock, one among many varieties which the Bramah lock presents. A A shews the bolt, formed something like two hooks rising out of a bar of metal, which bar has a backward and forward motion upon the plate B B. The upper edge of this plate is turned over at right angles, forming a small horizontal surface through which two openings are cut to receive the two hooked portions of the bolt. The movements of the bolt are otherwise guided by the edges of square holes through which it works;

the holes being made in the edge-pieces of the lock, riveted to the main plate. The bolt is further prevented from rising out of its place by means of a plate of metal C, which is secured to the edge-pieces by two screws 1, 1, and by two steadying pieces. This plate has on its surface a cylindrical projection D, which contains in effect all the working mechanism of the lock. The pins 4 4 are employed for securing a plate, which we shall have to describe presently. When such a lock is fixed upon a desk or box, the portion *D* projects to a small distance through a hole in the wood-work, forming in itself a very neat escutcheon, with a key-hole in the centre.



So much for the exterior. We must now proceed to examine the interior of the lock, especially the part contained within the cylinder. In fig. 36, for convenience of arrangement, the several parts are exhibited separately, and as if the plane of the lock were horizontal, with the key acting vertically. The essential part of the mechanism is a barrel or cylinder *E*, pierced or bored with a cylindrical hole down its centre. The inside of the bore has six narrow grooves, cut parallel with the axis, and in the direction of radii; the grooves are not cut through the thickness of the cylinder, but leave sufficient substance of metal for strength. In every groove is fitted a steel slida of peculiar form, such as is shewn at *a a* in fig. 37. Each slide is split in its thickness (seen in section), so that it may move up and down in its groove with a slight friction, and

fig 36. Details of the Bramah lock.

fig. 37. The slides.

thereby not fall simply by its own weight. Each slide has three small notches (3, 2, 3), the use of which will presently appear. Reverting to fig. 36, the lower part of the opening through the cylinder *E* is closed by a circular plate of metal, fixed to it by two screws; this plate is represented at *F*, in the lower part of the figure. This plate has a vertical pin rising from its centre (also seen at *b*, fig. 39), and serving as a key-pin on which the pipe of the key may work or slide; and it has also a short circular stud *c* projecting from its under side, and fitted to enter into a curved opening in the bolt presently to be described.

The point to be now borne in mind is this, that if the cylinder *E* turns round, the plate *F* will also turn round, and with it the stud *c*; and as this stud works into the peculiarly formed cavity *d* in a portion of the bolt (fig. 38), it causes the



fig. 38. The bolt.

bolt to be shot backwards or forwards. Now, in order to prevent this rotating of the cylinder unless the proper key be employed, the following mechanism is introduced: the cylinder has a groove cut round its circumference at *e e*, extending sufficiently near to the internal bore to produce the desired effect without too much weakening the metal. Into this notch is introduced the thin circular plate of metal *f f*, it being divided into two halves for this purpose; and when so placed, it occupies the position shewn by the dotted portion *e e*. When this plate is screwed to the case of the lock by the screws 4, 4, it cannot of course turn round; but the cylinder itself will or will not

turn round according to the position of the slides. The plate *ff* has six notches, 5, 5, 5, &c. in the inner edge or circle; so adjusted that, when the plate is in its place, the slides *a a* can move up and down. The cylinder cannot move round in a circle without carrying the slides with it; and these cannot so move unless they are all depressed to such exact distances in their respective grooves, that the deep notch of each slider (shewn at 2 in fig. 37) shall come into the plane of the circular plate: when all are so brought, the cylinder can be turned. If any one of the slides he pressed down either too low or not low enough, this turning of the cylinder cannot be effected, because the slides will be intersected by the edges of the notches 5, 5; and it is the office of the key, therefore, to press all the six slides down to the exact distances required. When the slides are not pressed upon hy the key, they are forced upwards to the top of the cylinder by a spiral spring 6, coiled loosely round the pin *b;* this pressure forces up a small collet, 7, on which the upper part of the slides rest by a sort of step.

The first locks were made with a separate and independent spring to each slide; hut it is a very great improvement, the introduction of one common spring to raise up the whole number; because if a person attempts to pick the lock hy depressing the slides separately hy means of any small pointed instruments, and hy chance brings two or more of tham to the proper depth for turning round, should he press any one too low, it is difficult to raise it again without relieving the spring 6, which immediately throws tha whole number of slides up to the top, and destroys all that had been done towards picking the lock. Another improvement of this lock, and one which very much increased the difficulty of picking, and its oonseqnent security, was the introduction of false and deceptive notches cut in the sliders, as seen at 3, 3. It was found that in the attempt to pick this lock, an instrument was introduced hy the keyhole to force the cylinder round. At the same time that the slides were depressed by separate instruments, those slides which were not at the proper level

for moving round were held fast by the notches 5, 5 in the plate *f f* bearing against their sides; but when pressed down to the proper level, or till the notch 2 came opposite *f f*, they were not held fast, but were relieved. This furnished the depredator with the means of ascertaining which slides were pressed low enough, or to the point for unlocking. The notches 3, 3 in the slides are sometimes cut above the true notch 2, sometimes below, and at other times one on each side (one above and one below); they are not of sufficient depth to allow the cylinder to turn round, but are intended to mislead any one who attempts to pick, by his not knowing whether it is the true notch or otherwise, or even whether the slider be higher or lower than the true notch.

We have not yet sufficiently described the key of the Bramah lock. One merit of the lock is the remarkable smallness of the key, which renders it so conveniently portable. The key, as shewn in the upper part of the figure, has six notches or clefts at the end of its pipe or barrel; these clefts are cut to different depths, to accord with the proper extent of movement in the slides. There is a small projection, 10, near the end of the pipe, fitted to enter the notch D in the cylinder; this forces the cylinder round when the parts are all properly adjusted. The bolt of the lock, when properly shot or locked, is prevented from being forced back by the stud *c* on the bottom, F, of the cylinder coming into a direct line with its centre of motion, as shewn in fig. 39; in this position no force, applied to drive the bolt back, would have any tendency to turn the cylinder round.

To facilitate the comprehension of this very curious and beautiful mechanism, the cylinder is shewn in section in the annexed fig. 39, the same letters and figures of reference being used as before. In the whole of this description we have spoken of six slides, and six only; but Bramah locks may be, and have been, constructed with a much larger number.

There have been several attempts made to modify the action of Bramah's lock, or to combine this action with that of



fig. 39. Section of the Bramah cylinder.

some other inventor. It will suffice to describe one of these. The lock invented by Mr. Kemp of Cork, and for which a patent was obtained in 1816, is called by him the *Union* lock, as combining the principles of Barron's and Bramah's locks. It contains two, three, or more sliders or tumblers, operated upon by two, three, or more concentric tubes. These concentric tubes are of different lengths, and are placed inside the barrel of the key; so that the barrel may, in fact, be conceived to consist of a series of concentric tubes. These tubes are made of such respective lengths as to push back the tumblers, sliders, or pins which detain the bolt; and this to the precise extent that will bring certain notches in all the sliders to the position which will allow the bolt to pass. The inventor gives this lock its distinctive appellation because it combines something of the pushing motion which Bramah gives to his key, with something of the tumbler-motion observable in Barron's locks. The principle of safety is considered here to rest chiefly on the extreme difficulty of imitating the key.

Mr. Bramah calculates the number of changes of position which the slides of his lock are capable of assuming before the right one would be attained. "Let us suppose the number of levers, slides, or other movables by which the lock is kept shut, to consist of twelve, all of which must receive a different and distinct change in their position or situation by the application of the key, and each of them likewise capable of receiving more or less than its due, either of which would be suffi-

cient to prevent the intended effect. It remains, therefore, to estimate the number producible, which may be thus attempted. Let the denomination of these slides be represented by twelve arithmetical progressionals; we find that the ultimate number of changes that may be made in their place or situation is 479,001,600; and by adding one more to that number of slides, they would then be capable of receiving a number of changes equal to 6,227,020,800; and so on progressively, by the addition of others in like manner to infinity. From this it appears that one lock, consisting of thirteen of the above-mentioned sliders, may (by changing their places only, without any difference in motion or size,) be made to require the said immense number of keys, by which the lock could only be opened under all its variations."

CHAPTER VII.

AMERICAN LOCKS.

The lock-manufacture in America has undergone some such changes as in England. The insufficiency of wards to the attainment of security has been for many years known; and the unfitness of even tumblers to attain this end, without auxiliary contrivances, has been fully recognised for a dozen years back. In this, and in other mechanical arts, the American machinists depended primarily on the invention of the artisans in the mother country, rather than on those of any continental European state. But the development of the art in the United States has not been wanting in originality; the varieties of locks have been very numerous, and many of them exceedingly ingenious. It is not necessary, however, to describe or depict any of those of simple form. The warded locks of different countries very much resemble each other; the intricate warded

locks made in France in the last century have long fallen into disuse, in consequence of the general conviction that no arrangement of wards, however intricate, can afford the degree of security required in a good lock. It will he more to the purpose, therefore, to proceed at once to a notice of those American locks which, during the last few years, have acquired some celebrity; first, however, noticing one of older date.

Stansbury's lock, invented in the United States about forty years ago, may be regarded as a modification of the Egyptian lock. It had a bolt, case, and key-hole somewhat similar to those of modern locks; but there were peculiarities of construction in other respects. There was a revolving plate, pierced with a series of holes, and having a bit or pin which moved the bolt. On the lock-case were a series of springs, each having a pin at one end; and the arrangement was such that, when the bolt was locked or unlocked, each pin would be pressed into some one of the holes. Like as in the Egyptian lock (figs. 1 to 4), each pin had to be pushed out, and all of them simultaneously, to allow the plate to turn and move the bolt. The key was made with a barrel and bit; and on the front end of the hit was a series of pins corresponding in position with the holes in the plate. The mode of locking or unlocking was as follows: the key was inserted in the key-hole, and turned to a certain position; it was then pressed in with some force, until the pins on the key met those in the plate; when the latter, yielding to the pressure, left the plate free to turn and move the bolt. Modifications of the Egyptian lock, more or less resembling this, have been brought out in some variety on both sides of the Atlantic; but scarcely any have equalled in simplicity the curious wooden relic of by-gone ingenuity in the art of lock-making.

A lock made a few years ago by Mr. Yale, in the United States, somewhat resembles the Bramah lock in having a cylinder or barrel, or rather two concentric cylinders, one working within the other. These cylinders are held together by pins which pass through them both into the key-hole. On the back

of the inner cylinder is a pin that fits into a slot in the holt, and moves it whenever the cylinder is turned. The pins that hold the cylinders together are each cut in two; the pieces of the various pins differing in lengths as irregularly as possihle. The key is so peculiarly formed, that, on inserting it in tha key-hole, it thrusts the pins radially outwards; each pin being pushed just so far that the joint of the pin shall coincide with the joint hetween the two cylinders. The inner cylinder can then be turned, by which the bolt is locked or unlocked. If, hy the use of a false key, any pin be pushed in too far, it will be as ineffectual in opening the lock as if it were not thrust in far enongh; and some of these locks having been made with as many as forty pins, the chances are very numerous against tha right comhination heing hit upon. There is a combination of something like the Egyptian with something like the Bramah lock, bere attempted.

One of the principal constructions adopted in America a few years hack for bank-locks is that of Dr. Andrews of Perth Amboy, in New Jersey. It was up to that time (1841) believed that the hest locks, both of England and America, were proof against any attempts at picking derived from knowledge ohtained by inspection through the key-hole; hut there still remained the danger that the sight of the true key, or the possession thereof, for only a few minutes, would enable a dishonest person to produce a duplicate. It was to contend against this difficulty that Dr. Andrews directed his attention; and he sought to ohtain the desired ohject hy constructing a lock, the interior mechanism of whicb could be changed at pleasure. The lock of his invention is furnished with a series of tumblers and a detector. The tumhlers are susceptible of being arranged in any desired order; and the key has movable bits which can be arranged so as to correspond with the tumhlers. When the lock is fixed in its place, no change can be made in the tumhlers, and cousequently only one arrangement of the bits of the key will suit for the sbooting and withdrawing of the bolt. The owner can, however, before the fixing of the bolt, adopt

any arrangement of tumblers and bits which he may choose. But though the tumblers cannot be actually re-arranged in any new order within the lock while the latter is fixed, yet by an ingenious contrivance the tumblers can be so acted upon as to render the lock practically different from its former self. The purchaser receives with his lock a series of small steel rings, each ring corresponds in thickness with the thickness of some one of the bits of the key; so that, by suitable adjustment, any one of the bits may be removed from the key, and a ring be substituted in its place. The effect of this substitution is, that the particular tumbler which corresponds with the ring is not raised by it; it is drawn out with the bolt, as if it were part of the bolt itself. Supposing the lock to be locked by this means, the original key would not now unlock it; for one of the tumblers has now been displaced, and can only be re-adjusted by the same ring which displaced it. If an attempt be made to open the lock by the original key, or by the key in its original adjustment, a detector is set in action, which indicates that a false key or other instrument has been put into the lock. One, or more than one, of the bits may be removed from the key, and rings be substituted, and consequently one or more of the tumblers may be disturbed in this peculiar way; so that the lock may change its character in all those permutating varieties which are so observable in most "safety-locks." The shape of the tumblers is, of course, such as to facilitate this action; they have each an elongated slot, and also two notches; when a tumbler is raised by one of the bits of the key, one of the notches closes around a stump fitted into the case of the lock, and prevents the tumbler from being moved onward with the bolt; but when a ring has been substituted for a bit on the key, the tumbler cannot be raised at all; it is carried onward by a stump on the bolt.

Dr. Andrews is also the inventor of a lock which he terms the *snail-wheel lock*. In this lock a series of revolving discs, or wheels, taking the place of the tumblers, are mounted on a central pin, on which the pipe of the key is inserted. Each

disc has a piece cut out of it, into which the bit of the key enters, and in turning round moves the discs according to the various lengths of the steps on the key. On the outer edge of each disc is a notch, and by the turning of the key all these notches are brought into a line, so that a moveable tongue, or *toggle*, attached to the bolt, falls into the notches; the key is then turned the reverse way, by which means the bolt is projected.

About the time when Dr. Andrews invented his first lock, Mr. Newell, of the firm of Day and Newell of New York, constructed a lock which possessed the same distinctive peculiarity as that of Andrews, viz. that the key might be altered any number of times without rendering it necessary to remove the lock or change its internal mechanism. This was brought about, however, in a different manner. Instead of having, as in the Andrews lock, a two-fold movement to every tumbler, Mr. Newell employed two sets of tumblers, the one set to receive motion from the other, and having different offices to fill, to be acted upon by the key in respect to the first series, and to act upon the bolt in respect to the second. Calling these two sets *primary* and *secondary*, the action of the lock may be briefly described as follows. A primary tumbler being raised to the proper height by the proper bit in the key, raises the corresponding secondary tumbler; the secondary tumbler is held up in a given position during the locking, while the primary becomes pressed by a spring into its original position. It results from this arrangement that the bolt cannot be unlocked until the primary tumbler has been raised to the same height as before, so as to receive the tongue of the secondary tumbler. And as this is the case in respect to any one primary and its accompanying secondary tumblers, so is it the case whether each set comprises four, five, or any other number. The key may be altered at pleasure, and will in any form equally well shoot the bolt; but the lock can only be unfastened by that arrangement of key which fastened it.

It is, however, desirable to trace the course of improve-

ments more in detail, because every successive change illustrates one or other of the several properties required in a good lock. Messrs. Day and Newell's lock was not finally brought to an efficient form without many attempts more or less abortive. Mr. Newell conceived the idea of applying a second series of tumblers, so placed as to be acted on by the first series. Each of these secondary tumblers had an elongated slot, such that a screw could pass through all of them; the screw having a clamp to overlap the tumblers on the inside of the lock. The head of the screw rested in a small round hole on the back of the lock, so placed as to form a secondary key-hole, to which a small key was fitted. There was thus a double system of locking, effected in the following way: when the large key had been applied, and had begun to act on the primary tumblers, the small key was used to operate on the clamp-screw, and thus bind all of the secondary tumblers together, ensuring their position at the exact heights or distances to which the primary key had caused them to be lifted. The bolt was then free to be shot, and the first series of tumblers reverted to their original position.

But such an arrangement has obvious inconveniences. Few persons would incur the trouble of using two keys; and besides this, there were not wanting certain defects in the action and reaction of the several parts; for if the clamp-screw were to be left unreleased, the first series of tumblers would be upheld by the second series in such a way that the exact impression of the lengths of the several bits of the key could be obtained through the key-hole while the lock was unlocked or the bolt unshot. To remedy one or both of these evils was the next object of Mr. Newell's attention. He made a series of notches or teeth in each of the secondary tumblers, corresponding in mutual distance with the steps or bits of the key; and opposite these notched edges he placed a dog, or lever, with a projecting tooth suitable to fall into the notches when adjusted properly in relation to each other. When the key was used, the primary tumblers were raised in the usual

way, and acted on the secondary tumblers; these latter were so thrown that the dog-tooth caught in the notches and held them fast, thereby rendering the same service as the clamp-screw and the small key in the former arrangement. No other relative position of the bits of the key could now unlock the lock.

Still, improvement as it was, this change was not enough; Mr. Newell found that his lock, like all the locks that had preceded it, was capable of being picked by a clever practitioner; and candidly admitting the fact, he sought to obtain some new means of security. He tried what a series of complicated wards would do, in aid of the former mechanism; but the result proved unsatisfactory. His next principle was to provide a number of false notches on the abutting parts of the primary and secondary tumblers, with alterations in other parts of the apparatus. The theory now depended upon was this, that if the bolt were subjected to pressure, the tumblers would be held fast by false notches, and could not be raised by any lock-picking instrument. To increase the security, a steel-curtain was so adjusted as to cover, or at least protect, the key-hole. Great anticipations were entertained of this lock, but they were destined to be negatived. A clever American machinist, Mr. Pettit, accepted Messrs. Day and Newell's challenge (500 dollars to any one who could pick this lock); he succeeded in picking the lock, and thus won the prize.

Once again disappointed, Mr. Newell re-examined the whole affair, and sought for some new principle of security that had not before occurred to him. He had found that, modify his lock how he might, the sharp-eyed and neat-fingered mechanician could still explore the interior of the lock in such a way as to find out the relative positions of the tumblers, and thus adapt their means to the desired end. How, therefore, to shut out this exploration altogether became the problem; how to make a lock, the works of which should be *parautoptic*—to coin a word from the Greek, which should signify *concealed from view*. The result of his labours was the production of

the American bank-lock now known by that name. The details of this lock may now conveniently be given.

In fig. 40 the lock is represented in its unlocked state, with the cover or top-plate removed; the auxiliary tumbler and the detector-plate are also removed. In fig. 41 it is represented as



fig. 40. The American Parautoptic lock; bolt unshot.

locked, with the cover and the detector-plate also removed, and the auxiliary tumbler in its place. In these two figures, the same letters of reference apply to the same parts, unless otherwise stated. AB is the bolt; T^1 are the first series of movable slides or tumblers; s shews the tumbler-springs; T^2 the secondary series of tumblers; and T^3 the third or intermediate series—these latter coming between the first and secondary series; PP are the separating plates between the several members of the first series of tumblers; s^1 are the springs for lifting the intermediate tumblers. On each of the secondary tumblers T^2 is a series of notches, corresponding in mutual distance with the difference in the lengths of the movable bits of the key. It thence happens that, when the key is turned in the lock to lock it, each bit raises its proper tumbler, so that some one of these notches shall present itself in front of the tooth *t* in

the dog or lever L L. When the bolt B is projected by the action of the key, it carries with it the secondary tumblers T^2, and presses the tooth *t* into the notches; in so doing, it withdraws the tongues *d* from between the jaws *jj* of the intermediate tumblers T^3, and allows the first and intermediate tumblers to fall to their original position. By the same movement, the secondary tumblers T^2 become held in the position given to them by the key, by means of the tooth *t* being pressed into the several notches, as shewn in the closed state of the lock (fig. 41). Now let us see what results if any attempt be made



fig. 41. The same with the bolt shot.

to open the lock with any arrangement of key but that by which it has been locked. In such case, the tongues *d* will abut against the jaws *jj*, preventing the bolt from being withdrawn; and should an attempt be made to ascertain which tumbler binds and requires to be moved, the intermediate tumbler T^3 (which receives the pressure), being behind the iron wall II, which is fixed completely across the lock, prevents the possibility of its being reached through the key-hole; and the first tumblers T are quite detached at the time, thereby making

it impossible to ascertain the position of the parts in the inner chamber behind the wall II. K is the drill-pin, on which the key fits; and C is a revolving ring or curtain, which turns round with the key, and prevents the possibility of inspecting the interior of the lock through the key-hole. Should, however, this ring be turned to bring the opening upwards, a detector-plate



fig. 42. The detector plate of the Parautoptic lock.

D, fig. 42, is immediately carried over the key-hole by the motion of a pin p^1 upon the auxiliary tumbler T^4, which is lifted by the revolution of the ring C, thereby effectually closing the key-hole. As an additional protection, the bolt is held from being unlocked by the stud or stump S bearing against the detector-plate; and, moreover, the lever ll holds the bolt, when locked, until it is released by the tail of the detector-plate pressing the pin p^1; l^1 is a lever which holds the bolt on the upper side, when locked, until it is lifted by the tumblers acting on the pin p^1; X are separating-plates between the intermediate tumblers T^2; $u\,u^1$ are the studs for preserving the parallel motion of the different tumblers.

Fig. 43 represents the key in two different forms, or with the bits differently arranged. Either form will lock the lock, but the other will not then unlock it. The end of the key is represented in fig. 44, shewing the screw which fixes the bits

fig. 43. Key of the Parautoptic lock.

fig. 44. End view of the key.

in their places. The bits for a six-bitted key are shewn separately in fig. 45.

fig. 45. Separate bits of the key.

In 1847 the parautoptic lock was exhibited at Vienna before the National Mechanics' Institute of Lower Austria; and towards the close of the year Mr. Belmont, consul-general of Austria at New York, placed in the hands of Messrs. Day and Newell a letter, a diploma, and a gold medal, forwarded by the Institute. The letter was from the president of the Institute to Mr. Newell, and was couched in the following terms:

"The Institute of Lower Austria, at its last monthly session, has passed the unanimous resolution to award to you its gold medal, as an acknowledgment of the uncommon superiority of the combination-lock of your invention; and this resolution was ratified in its general convention held on the 10th instant.

"Whilst I, as president of this Institute, rejoice in seeing the services which by this invention you have rendered to the locksmith's art thus appreciated and recognised, I transmit to you, enclosed, the said medal, together with the documents re-

lating to it; at the same time availing myself of this opportunity to assure you of my esteem.

"COLLOREDO MANNSFELD.

"Vienna, May 31st, 1847."

The diploma and the medal were similar to other honorary distinctions of the same class, and need not be described here; but the report of the special committee may be given, as it expresses the opinions of the Viennese machinists on the relative principles by which safety is sought to be obtained in different kinds of locks.

REPORT

Of a Special Committee on the new Parautoptic Permutation Lock of the American Newell, made known to the Lower Austrian Institute by the Councillor, Professor Reuter, and on the motions relating to it made by the same and accepted by the Institute. Presented at the monthly meeting, April 6th, 1847, by Mr. Paul Sprenger, Aulic Councillor on Public Works, &c. &c.

GENTLEMEN:—At our last monthly meeting, Mr. Reuter, Aulic Councillor and Secretary of the Institute, directed your attention to a newly invented lock of Mr. Newell, of North America, which was represented as excelling all other changeable combination locks hitherto known, and as being without a rival.

The Special Committee which was intrusted with the examination of this lock, and of the motions made by the said Secretary, and accepted by the Institute, has conferred on me the honour of making you acquainted with the results of its investigations.

The attention of your committee was chiefly occupied with the three questions proposed by the said Aulic Councillor in relation to the lock in question:

First: Whether the idea of Mr. Newell was of any practical value for already existing and still-to-be-invented combination-locks;

Secondly: Whether the idea was of sufficient importance to be published and minutely described in the transactions of the said Institute; and

Thirdly: Whether the merits of the inventor were of sufficient importance to entitle him to a distinction from the said Institute.

The deliberations on the first question, viz. the newness of the idea, and of its practical value, would of necessity enlist the particular attention of your committee, especially since by far the greater number of its members are by their avocation called upon to be interested in the execution of all kinds of locks.

It is therefore the unanimous opinion of your committee, that the idea

of the American Parautoptic Combination-Lock is entirely new and without example.

The combination-locks with keys have, with few exceptions, such an arrangement that a determinate number of movable parts (the so called combination-parts) must by the turning of the key be raised or lifted into a certain position, if it is desired to project the bolt, or, what is the same thing, to lock it out; consequently these parts, or, as they are technically termed, tumblers, could not be transposed or changed, from the circumstance that the key-bit was one solid piece, with various steps or notches adapted to the several tumblers, and one impression from it destroyed the security of the lock.

In order, however, to add more security to such a combination-lock, and to make the key, in case it should be lost, or any counterfeit made from a wax impression, useless for an unlawful opening of the lock, another step was taken: the key-bit was made to consist of several bits or movable parts, in such a manner that the owner of the lock was enabled to change the bits, and to form, *as it were*, new keys different from the former. But since the bolt of the lock can only be projected whilst the combination parts or tumblers are in a certain position, which position depends upon the order of the bits in the key, it is evident that the owner, when changing the key, must at the same time make a corresponding change in the position of the tumblers in the lock itself, before the lock can be of any use for the newly changed shape of the key, which rendered it troublesome, and impracticable for the purpose designed, from the fact that no positive change could be made in the lock, without taking it from the door, and then taking the tumblers out of the case, to change them in a suitable form for the key.

This principle of changing the lock is rarely adhered to, as few men understand the machinery of a lock sufficiently to undertake the task; and this circumstance rendered the lock quite as insecure as the former one described.

Another step toward the perfection of combination-locks consisted in this, that the key remains unaltered whilst the combination parts of the lock can, before it is locked, be brought into different positions by means of moveble plates on the frame of the lock. These plates were arranged by hand to certain figures, and depended on the memory for adjustment at each time the bolt was to be locked out or in, the key operating only on the bolt, to move it back and forth when the plates were set in proper positions for the purpose, and should the owner forget the arrangement of the plates, after projecting the bolt, his key is of no use to him, and he must resort to the skill of the locksmith to gain access.

The same case may occur in the far less perfect ring-lock of Reynier, which is operated without keys, and is opened by means of the rings being turned in a particular position; on these rings are usually stamped letters, which, by introducing some word readily suggested to the memory, thus point out the relative position of the rings.

But although in case of these ring-locks the owner is enabled to produce

a change in the rings in such a manner that the opening of the lock can, as it were, only become possible by rightly arranging the altered position of the letters, still this lock of Reynier's does not possess that safety and perfection which could have insured it universal application.

M. Crivelli, formerly professor at Milan, has given a minute description of the imperfection of ring-locks generally, in the annals of the Imperial Royal Polytechnic Institute.

It is the unanimous conviction of your committee that the American Lock of Newell surpasses, in the ingenuity displayed in its construction, all other locks heretofore known, and more especially in this, that the owner can, with the greatest facility, change at pleasure the interior arrangement of his lock to a new and more complex one, at every moment of his life, simply by altering the arrangement of the bits in the key, and this is accomplished without removing the lock or any part of it from its position on the door.

Its operation is as follows :—At the closing or locking of the lock, whilst the bolt is projecting, the movable combination parts assume precisely the position prescribed to them by the key, according to the particular arrangement of its bits at the time the key is turned.

The combination parts do not consist in one set of tumblers only, such as are found in all other locks, but there are three distinct sets or component parts fitting into each other. When the bolt is projected, it dissolves the mutual connexion of the constituent pieces, and carries along with it such as are designedly attached to it, and which assume the particular positions given them by the key in its revolution. These parts are rendered permanent in their given form by means of a lever adapted for the purpose, while the parts not united with the bolt are pressed down by their springs to their original places.

If now the bolt is to be returned again, *i. e.* if the lock is to be unlocked, then the constituent pieces or tumblers which are in the original state must, by means of the key, be again raised into that position in which they were when the lock was closed, as otherwise the constituent parts attached to the bolt would not lock in with the former, and the bolt could not be returned. Nothing, therefore, but the precise key which had locked the lock can effect the object.

This idea in itself, considered by your committee, is as ingenious as it is new, and is accompanied by a perfection in its execution which reflects the highest honour on Mr. Newell, the inventor and manufacturer of the lock.

The lock is built strong and solid, and the several parts are admirably adapted to the functions which they are designed to perform. The walls of steel or iron which separate the security parts from the tumblers, and the cylinder which revolves with the key, present formidable barriers to all descriptions of pick-locks, and render the lock a most positive and reliable security. The tumblers consist of rolled very smooth steel plates, in which the fire-crust has not been filed away, partly in order that the lock might not need oiling, as all these parts are very smooth, and partly that the

combination pieces might not easily rust, a thing to which the adhering fire-crust is not favourable. The springs, which by the turning of the key must be raised together with the tumblers, are attached to levers, and press upon the latter at their centre of gravity, in consequence of which all crowding towards either side is prevented, and the key can be turned with facility, in spite of the many combination parts which it has to raise; and the springs themselves are by their positions so little called into action, that their strength can never be impaired by use.

The lock has also another very complete arrangement in the detector-tumbler, which is attached to the cop or covering of the lock. This tumbler, on turning the key either way, closes the key-hole, and not only prevents the use of false instruments in the lock, but detects all attempts at mutilating its interior parts.

This lock is especially useful for locking bank-vaults, magazines, counting-houses, and iron-safes, in which valuable effects, money, or goods are to be deposited for safe keeping. When it is considered that the bits of the key belonging to this lock can be transferred into every possible form within its limits, and since the construction of the lock admits of every combination of the slides resulting from the changes of the key, therefore the lock in question is, in every respect, deserving of the appellation given to it by the Secretary of the Institute, namely, the Universal Combination Lock; and justly so, when we consider that the ten bits attached to the key admit of three millions of permutations, and upward; consequently forming that number of different kinds of keys and locks.

If we consider further, that we need not be limited to the given bit, but that others can be applied, differing in their dimensions from the former; and again, if we consider that from every system arising from a difference in their relative dimensions, a large number of new keys differing from each other will result, and that this can be effected in a space scarcely occupying a square inch,—then we cannot refrain from confessing that the human mind, within this small space, has shewn itself to be infinitely great.

After this preliminary and general exposition, your committee can answer the three questions propounded to them the more briefly, as the locks heretofore known have all been noticed.

To question first —On the practical value of the invention of Mr. Newell, your committee were unanimous and positive that the principle on which it is based should be preserved.

To question second.—For this reason the committee deemed it desirable that a drawing and description of the American lock in question should be published in the Transactions of the Institute of Lower Austria.

To question third.—With regard to the claims of the inventor, Mr. Newell, to an honorary distinction from the Institute of Lower Austria, the committee recommend that he be presented with a Diploma of honourable mention and a Gold Medal.

The members of your committee, consisting mostly of fellow-tradesmen of Mr. Newell, experience great satisfaction in the fact that it has fallen to

their lot to vote to their colleague on the other side of the ocean an acknowledgment of his successful ingenuity, and they close the Report with the request that the Institute will transmit to Mr. Newell of New York, in North America, the Diploma and Gold Medal, together with a copy of this Report, according to the motion of the Aulic Councillor and Professor Reuter.

[An exact copy of the original Report as preserved in the archives of the National Mechanics' Institute of Lower Austria.]

DR. SCHWARTZ,
Assistant Secretary of the Institute.

There are other circumstances connected with the American bank-lock, in relation to events both in the United States and in England, to which attention will be directed in a subsequent chapter.

The English patent for Messrs. Day and Newell's lock, dated April 15, 1851, runs as follows: "The object of the present improvements is the constructing of locks in such manner that the interior arrangements, or the combination of the internal movable parts, may be changed at pleasure according to the form given to, or change made in, the key, without the necessity of arranging the movable parts of the lock by hand, or removing the lock or any part thereof from the door. In locks constructed on this plan the key may be altered at pleasure; and the act of locking, or throwing out the bolt of the lock, produces the particular arrangement of the internal parts which corresponds to that of the key for the time being. While the same is locked, this form is retained until the lock is unlocked or the bolt withdrawn, upon which the internal movable parts return to their original position with reference to each other; but these parts cannot be made to assume or be brought back to their original position, except by a key of the precise form and dimensions as the key by which they were made to assume such arrangement in the act of locking. The key is changeable at pleasure, and the lock receives a special form in the act of locking according to the key employed, and retains that form until in the act of unlocking by the same key it resumes its original or unlocked state. The lock is

again changeable at pleasure, simply by altering the arrangement of the movable bits of the key; and the key may be changed to any one of the forms within the number of permutations of which the parts are susceptible."

The "claims" put forth under this patent are the following:—

"1. The constructing, by means of a first and secondary series of slides or tumblers, of a changeable lock, in which the particular form or arrangement of parts of the lock, imparted by the key to the first and secondary series of slides or tumblers, is retained by a cramp-plate.

"2. The constructing, by means of a first and secondary series of slides or tumblers, of a changeable lock, in which the peculiar form or arrangement of parts of the lock, imparted by the key, is retained by means of a tooth or teeth, and notches on the secondary series of slides or tumblers.

"3. The application to locks of a third or intermediate series of slides or tumblers.

"4. The application of a dog with a pin over-lapping the slide or tumblers, for the purpose of holding-in the bolt when the lock is locked or unlocked.

"5. The application of a dog operated on by the cap or detector-tumbler for holding the bolt.

"6. The application of a dog for the purpose of holding the internal slide or tumbler.

"7. The application to locks of curtains or rings, turning and working eccentrically to the motion of the key, for preventing access to the internal parts of the lock.

"8. The application to locks of a safety-plug or yielding-plate, at the back of the chamber formed by such eccentric revolving curtain or ring.

"9. The application to locks of a strong metallic wall or plate, for the purpose of separating the safety and other parts of the lock from each other, and preventing access to such parts by means of the key-hole.

"10. The application to locks of a cap or detective tum-

hler, for the purpose of closing the key-hole as the key is turned.

" 11. The constructing a key hy a combination of bits or movable pieces, with tongues fitted into a groove and held by a screw.

" 12. The constructing a key having a groova in its shank to receive the detector tumhler."

When the American locks became known in England, Mr. Hobbs undertook the superintendence of their manufacture, and their introduction into the commercial world. Such a lock as that just described must necessarily be a complex piece of mechanism; it is intended for use in the doors of receptacles containing property of great value; and the aim has been to baffle all the methods at present known of picking locks, by a combination of mechanism necessarily elaborate. Such a lock must of necessity be costly; but in order to supply the demand for a small lock at moderate price, Mr. Hobbs has introduced what he calls a *protector lock*. This is a modification of the ordinary six-tumbler lock. It bears an affinity to the lock of Messrs. Day and Newell, inasmuch as it is an attempt to introduce the same principle of security against picking, while avoiding the complexity of the changeahle lock. The distinction which Mr. Hobbs has made between secure and insecure locks will be understood from the following proposition, viz. " that whenever the parts of a lock which come in contact with the key are so affected by any pressure applied to the holt, or to that portion of the lock by which the bolt is withdrawn, as to indicate the points of resistance to the withdrawal of the holt, such a lock can be picked." Fig. 47 exhihits the internal mechanism of this new patent lock. It contains the usual contrivances of tumblers and springs, with a key cut into steps to suit the different heights to which the tumblers must he raised. The key is shewn separately in fig. 48. But there is a small additional piece of mechanism, in which the *tumbler stump* shewn at s in

fig. 46. Movable stump.



fig. 47. Hobbs's Protector Lock.

figs. 46 and 47 is attached; which piece is intended to work under or behind the bolt of the lock. In fig. 47, *b* is the bolt; *t t* is the front or foremost of the range of six tumblers, each of which has the usual slot and notches. In other tumbler-locks the stump or stud which moves along these slots is riveted to the bolt, in such manner that, if any pressure be applied in an attempt to withdraw the bolt, the stump becomes pressed against the edges of the tumblers, and bites or binds against them. How far their biting facilitates the picking of a lock will be shewn further on; but it will suffice here to say, that the movable action given to the stump in the Hobbs lock transfers the pressure to another quarter. The stump *s* is riveted to a peculiarly-shaped piece of metal *h p* (fig. 46), the hole in the centre of which fits upon a centre or pin in a recess formed at the back of the bolt; the piece moves easily on its centre, but is prevented from so doing spontaneously by a small binding spring. The mode in which this small movable piece takes part in the action of the lock is as follows: when the proper key is applied in the usual way, the tumblers are all raised to the proper heights for allowing the stump to pass horizontally through the gating; but should there be an attempt made, either by a false key or by any other instrument, to withdraw the bolt before the tumblers are properly raised, the stump becomes an obstacle. Meeting

fig. 48. The key.

with an obstruction to its passage, the stump turns the piece to which it is attached on its centre, and moves the arm of the piece *p* so that it shall come into contact with a stud riveted into the case of the lock; and in this position there is a firm resistance against the withdrawal of the bolt. The tumblers are at the same moment released from the pressure of the stump. There is a dog or lever *d*, which catches into the top of the bolt, and thereby serves as an additional security against its being forced back. At *k* is the drill-pin on which the pipe of the key works; and *r* is a metal piece on which the tumblers rest when the key is not operating upon them.

Another lock, patented by Mr. Hobbs in 1852, has for its object the absolute closing of the key-hole during the process of locking. The key does not work or turn on its own centre, but occupies a small cell or chamber in a revolving cylinder, which is turned by a fixed handle. The bit of the movable key is entirely separable from the shaft or stem, into which it is screwed, and may be detached by turning round a small milled headed thumb-screw. The key is placed in the key-hole in the usual way, but it cannot turn; its circular movement round the stem as an axis is prevented by the internal mechanism of the lock; it is left in the key-hole, and the stem is detached from it by unscrewing. By turning the handle, the key-bit, which is left in the chamber of the cylinder, is brought into contact with the works of the lock, so as to shoot and withdraw the bolt. This revolution may take place whether the bit of the movable key occupy its little cell in the plate or not; only with this difference—that if the bit be *not* in the lock, the plate revolves without acting upon any of the tumblers; but if the bit be in its place, it raises the tumblers in the proper way for shooting or withdrawing the bolt. It will be understood that there is only one key-hole, namely, that through which the divisible key is inserted; the other handle or fixed key working through a hole in the cover of the lock only just large enough to receive it, and not being removable from the lock. As soon as the plate

turns round so far as to enable the key-bit to act upon the tumblers, the key-hole becomes entirely closed by the plate itself, so that the actual locking is effected at the very time when all access to the interior through the key-hole is cut off. When the bolt has been shot, the plate comes round to its original position, it uncovers the key-hole, and exhibits the key-bit occupying the little cell into which it had been dropped; the stem is then to be screwed into the bit, and the latter withdrawn. It is one consequence of this arrangement, that the key has to be screwed and unscrewed when used; but through this arrangement the key-hole becomes a sealed book to one who has not the right key. Nothing can be moved, provided the bit and stem of the key be both left in; but by leaving in the lock the former without the latter, the plate can rotate, the tumblers can be lifted, and the bolt can be shot.

CHAPTER VIII.

THE LOCK CONTROVERSY: PREVIOUS TO THE DATE OF THE GREAT EXHIBITION.

It must be evident, even on a cursory glance at the past history of the lock-manufacture, that the prime motive for the introduction of novelties and improvements in construction is the desirability of producing a lock which no one can open without the proper key. From the earliest and simplest lock, down to the latest and most complex, this object has been constantly held in view; and every clear proof or evidence that this object has not been attained has led to the invention of some new contrivance. It has been a succession of struggles —to attain security—to shew that this security has not been attained—to make a further and more ingenious attempt—to detect the weak point in this renewed attempt—and so on. We need not repeat here, what was stated in an early chapter,

that benefit must ultimately result from a candid discussion of this question. When M. Réaumur proposed to explain how the locks of his day could be picked or opened without the true key, his object was to shew to persons who were not locksmiths how far they could depend upon the principle of security offered by locks. But before proceeding on his inquiry, the illustrious naturalist asks, "Ne craindra-t-on pas que nous ne donnions en même tems des leçons aux voleurs?" And he replies, "Il n'y a pas grande apparence qu'ils viennent les chercher ici, et qu'ils en aient besoin; ils sont plus grands maîtres que nous dans l'art d'ouvrir les portes. Apprenons donc l'art d'ouvrir les portes fermées, afin d'apprendre celui de les fermer d'une manière qui ne laisse rien ou qui laisse peu à craindre."*

Before treating of lock controversies and lock violability in England, it will be desirable first to refer to America, where this subject attracted much attention some years earlier than the Great Exhibition—an Exhibition which will always be associated in a remarkable manner with the history of locks.

Soon after the inventions by Dr. Andrews and Mr. Newell, in 1841 (described in a former chapter), the rivalry between the two locks ran high; each lock being 'unpickable,' according to the estimate of its inventor. Mr. Newell thought the best mode of shewing the superiority of his own lock would be by picking that of his competitor: and after several trials, he succeeded in bringing into practical application that system of picking which we may designate the *mechanical*, as contradistinguished from the *arithmetical*. Mr. Newell not only picked Dr. Andrews' lock, but he wound up the enterprise by picking his own! He was probably the first person who honestly confessed to having picked his own unpickable lock. This dis-

* "But is there not this danger, that at the same time we shall be giving lessons to the thieves? It is not very probable that they will seek instruction of us, or that they have any need of it; they are greater masters in the art of opening doors than we can pretend to be. Let us then learn the art of opening locked doors, in order that we may acquire that of securing them in such a way as to leave little or nothing to be feared on account of their security."

covery led Mr. Newell, as has been noticed in a former page, to the invention of the triple-action or parautoptic lock.

The mechanical principle, as applied to the picking of a tumbler lock, is nearly the same whatever form of construction be made the medium of experiment. When a pressure is applied to the bolt sufficient to unlock it if the tumbler-obstructions were removed, the edges of the tumbler bite or bind against the stump of the bolt, so as not to move up and down with such facility as under ordinary circumstances. By carefully trying with a small instrument each tumbler, and moving it until the bite ceases, the gating of that particular tumbler may be brought to the exact position for allowing the stump of the bolt to pass through it. (See page 118.)

This violability is observable in the tumbler-locks under very varied forms of construction. Mr. Newell, after he had picked his own lock, devised a series of complicated wards, to add to the difficulty of reaching the tumblers; but he could not thereby ged rid of the importance of this fact, that wherever a key can go, instruments of a suitable size and form could follow: his wards did not render his lock inviolable. His next contrivance was to notch the abutting parts of the primary and secondary tumblers, or the face of the stump and the ends of the tumblers; but this failed also. Mr. H. C. Jones, of Newark, N. J., added to all this a revolving pipe and curtain, to close as much of the key-hole as possible. But so far were all these precautions from being successful, that a lock provided with all these appendages, and affixed to the door of the United States Treasury at Washington, was picked. The makers of locks have, each one for himself, contended against such difficulties as were known to them at the time of inventing their locks; and, mortifying as failure may be, it would be cowardly to yield up the enterprise whenever any new difficulty presented itself. Difficulties, in locks as in other matters, are made to be conquered.

To shew how numerous are the sources of insecurity which have to be guarded against, to meet the skill often

brought to bear upon this lock, we may adduce the reasons which led Mr. Newell to apply a curtain to the key-hole of his lock. Supposing the interior arrangement of the triple set of tumblers, and the metallic shielding wall, to be perfect, still, *if the first set of tumblers can be seen through the key-hole*, the following plan may be put in operation. The under-side of the tumblers may be *smoked*, by inserting a flame through the key-hole; and the key will then leave a distinct mark upon each tumbler the next time it is used, shewing where it began to touch each tumbler in lifting it. This may be seen by inserting a small mirror hinged into the lock through the key-hole. There may even be an electric light used from a small portable battery, to illumine the interior of the lock. By these and other means the exact length of each bit of the key may be determined; and from these data a false key may be made. It is to prevent this inspection of the works, or any other examination of an analogous kind, that the revolving curtain was applied; but, as stated in the last paragraph, even this did not suffice: ingenuity devised a mode of baffling the contrivance of curtains as well as that of the wards and false notches in the tumblers.

When the parautoptic lock was completed, it was keenly criticised in America, owing to the long discussions respecting the merits of previous locks. In a matter of this kind, where a commercial motive would lead bankers and companies to apply a very severe test to the security of locks and similar fastenings to strong-rooms and receptacles, any experiments made with their sanction became important. Mere letters or certificates emanating from individuals, expressive of opinions concerning a particular lock, would be out of place in a volume relating to locks generally; but it is quite within the limits of the subject, and has indeed become part of the history of locks, to notice experiments and attempts of a more public character. We may therefore introduce a few paragraphs of this description, relating to the career of the American lock in America itself.

The principal bankers at Boston (U.S.) held a meeting to

take into consideration measures for testing the security of hank locks. Consequent on this meeting, Messrs. Day and Newell deposited five hundred dollars with the cashier of the State Bank at Boston, to be by him paid to any one who could pick the parantoptic lock: the trial was to be conducted under the auspices of the bank. One of the locks was brought to the bank, and was minutely examined by two machinists on two afternoons, after which it was secured to an iron chest, and locked by a committee appointed by the bank. The key was to remain in the hands of the committee during the trial; and it was to be used at their discretion, in unlocking and locking the door, without the knowledge of either of the other parties—provided that in so doing no alteration was made in the combination-parts of the key. Ten days were allowed to the operators for the examination and the trial; if they succeeded they were to have five hundred dollars; but if they injured the lock they agreed to forfeit two hundred, as a purchase price. At the end of the period the lock remained unopened and uninjured; and the two deposited sums were accordingly returned to the respective parties.

Messrs. Page and Bacon, of St. Louis, had a strong-room lock made by one of the chief locksmiths of that city. To test its security, the proprietors requested Mr. Hobbs to attempt to pick it; he did so, and succeeded. Whereupon the proprietors, having purchased one of the parautoptic locks, deemed it no more than fair play to subject this lock to a similar ordeal, an additional zest being given by a reward of five hundred dollars offered by Day and Newell to the successful picker. The maker of the former lock accepted the challenge; he was allowed to examine the new lock piecemeal, and was then allowed thirty days for his operations in picking. He failed in the enterprise. Of course, in this, as in all similar cases, the operator had not access to the true key.

It follows from the nature of this lock, as noticed in a former chapter, that when the bolt has been shot, if the bits of the key be re-arranged in any other form, the lock becomes

to all intents and purposes a new lock, so far as that key is concerned, and cannot be unlocked unless the key revert to its original arrangement. To test this principle, a box with a parautoptic lock was placed in the room of the American Institute in 1845; it was locked; the bits of the key (12 in number) were then re-arranged, and the key was placed in the hands of any one who chose to try to open the lock — with the offer of a reward of five hundred dollars in the event of the lock being opened. Here, instead of the operator being called upon to devise new pick-lock implements, he had the actual key placed in his hands, modified however in such a way that, though the modifier could restore the original arrangement (provided he had kept some kind of record), the operator had numerous chances against his success. The lock remained unopened notwithstanding this challenge.

We shall have occasion to shew presently, that if the number of tumblers (and consequently the number of bits in the key) be small—not exceeding six, for instance—the possession of the *true* key gives any one the power of opening the lock, provided he has time and patience to go through a few hundred changes of the bits of the key; for, as some one arrangement must have been that by which the lock was locked, it must again occur if the user takes care to make *all* the arrangements in turn, and tries the lock after each. Whether this constitutes picking a lock, each lock-owner will decide for himself. All that it is at present meant to state is, that *without* access to the true key, the parautoptic lock has not hitherto been opened; and that *with* the true but altered key the process of opening is possible, but is slow and tedious.

In 1846 the American Institute appointed a committee to examine into the merits of the parautoptic lock. On the 18th of September in that year the Committee made their report, signed by Professor Renwick and Mr. T. W. Harvey, as follows:—

"The Committee of the American Institute, to whom was referred the examination of NEWELL'S PARAUTOPTIC BANK

Lock, report that they have given the subject referred to them a careful and attentive examination, and have received full and complete explanations from the inventor. They have remarked in the lock a number of important advantages, and, in particular, very great improvements upon the permutation-lock formerly submitted by him to the American Institute. Thus, while it retains the advantages of the permutation principle, combined with the property that the act of locking sets the slides to the particular arrangement of the bits in the skeleton key, the parts thus set are completely screened from observation, from being reached by false instruments, or from being injured by any violence not sufficient to break the lock to pieces.

"Having in the course of their inquiries examined the different existing modes in which locks may be picked, forced, or opened by false keys, the Committee have come to the conclusion that the parautoptic lock cannot be opened by any of the methods now practised, unless by a person in possession of the key by which it was locked, in the exact form of combination in which it was used for the purpose, or in the almost impossible case of the bits being adjusted to the skeleton key by accident in that very form. As the chances of such accidental combination range according to the number of movable bits, from several thousands to several millions to one, the Committee do not conceive that so small a chance of success would ever lead to an attempt to profit by it.

"In conclusion, the Committee feel warranted in expressing the opinion, that unless methods hitherto unknown or imagined should be contrived for the specific object, the lock in question may be considered as affording entire and absolute security."

The latest form which Messrs. Day and Newell have given to their challenge, after the experience of the last few years, is the following:

"First, a Committee of five gentlemen shall be appointed in the following manner: viz. two by the parties proposing to

operate, and two by ourselves; and hy the four thus appointed a fifth shall be selected.

"In the hands of this Committee shall be placed Two Thousand Dollars, as a reward to the operator if successful in picking the lock hy fair means.

"We will place upon the ifside of an iron door one of our best bank locks. The operator shall then have the privilege of taking the lock from the door, and have it in his possession for examination; it shall then be returned to the Committee for our inspection, so that we may be assured that it has not been mutilated or injured. The operator shall then, in the presence of ourselves and the Committee, place the lock upon the door in its original position; after which the Committee shall place upon it their seals, so that it cannot be removed or altered without their knowledge. The lock being thus secured to the door, we shall then be allowed to lock it up ourselves, upon any change of which it is susceptihle.

"The time for operation to continne thirty days; and if at the end of that time he shall consider that he hes made any progress towards picking the said lock, he shall have thirty days more in which to continue operations."

The Austrian report concerning the American lock was given in a former page, to which we may here refer; and then direct attention to England, and to the discussions which have lately been carried on respecting the safety of locks.

It is of course natural that each inventor of a new look should, while describing the product of his ingenuity, point out what he conceives to be the imperfections of locks which have preceded: use has sanctioned the custom not only with regard to locks, hut also in other important matters. Hence there have been many "lock controversies" in England during the last seventy years. We have seen how freely and justly the late Mr. Bramah criticised all the locks that preceded his own; and he was certainly not the man to shrink from criticism in his own case. Twenty years ago the Bramah lock was itself made the subject of criticism.

Mr. Ainger, in his lecture on the subject delivered at the Royal Institution, London, and afterwards in his article "Lock" in the *Encyclopædia Britannica*, thus narrates the circumstances which led to the adoption of the false notches in the Bramah lock as a means of security: "At length (after the original lock had acquired much celebrity,) an advertisement appeared in the public papers, requesting those who had lost keys of Bramah's locks, not, as had hitherto been done, to break open their doors or drawers, but to apply to the advertiser, who would undertake to save this destructive process by picking. And it appeared that an individual of great dexterity could perform this operation almost with certainty. The effect of this discovery on the demand for the locks may easily be imagined; but the effect it had in stimulating ingenuity to provide a remedy is one of the best illustrations of the proverb, that necessity is the mother of invention. Within a few days or weeks, Mr. Russell, who was at that time employed in Mr. Bramah's establishment, devised an alteration which at once, and without any expense, entirely overcame the difficulty, and converted the lock into one of perfect security. This contrivance is the most simple and extraordinary that ever effected so important an object; but before we describe it, we will endeavour to explain what has been called the *tentative* process of lock-picking, and which had been so successfully applied to Bramah's locks."

Mr. Ainger illustrates the subject by an engraving—not of an actual lock, but of an hypothetical arrangement of bolts and notches; and he then makes his reasoning apply to the actual process adopted by the picker of the real lock. "A tendency to revolve was given with some force to the barrel; then, by means of a pair of small forceps, the tumblers (sliders) were tried, and it was ascertained which one was most detained by the pressure against the locking-plate. That which offered most resistance was gradually depressed till its notch was felt to hang itself upon the locking-plate; and so on till the whole were depressed in succession, exactly as they would

Digitized by Google

bave been depressed simultaneously by the key." Mr. Ainger then describes the contrivance which, in bis jndgment, seemed to render any further attempts to pick the Bramah lock hopeless. This consisted in cutting false notches in the sliders; so as to render it impossible for the picker to tell when he has brought a notch to tbe plane of the locking-plate, whether it is a true notch, or one of sballower depth, unfitted to admit the movement of tbe plate."

This is a very interesting statement, for it sbews that the mecbanical or tentative method of opening was known in England long ago, although very little attention has been since paid to it. In a complex Bramah lock, and in locks on the combination principle, the difficulty of picking is almost insuperable, so long as wbat may be termed the arithmetical method is adopted. It is perfectly true, as has been so often stated, that the varied combinations in tbe arrangement of the slides amount to millions and even billions, when the slides are in any degree numerous; and if a person attempt to pick the lock by ringing the changes on all these combinations, it would very likely require the lives of a dozen Methuselahs to bring the enterprise to an end. But by tbe mecbanical method, sketched so clearly by Mr. Ainger, tbe exploit puts on a different aspect. The experimenter passes through the keyhole an instrument so arranged as to give a *tendency* in the bolt to withdraw in the wisbed-for direction; and a pressure produced in the slides by this tendency gives information concerning the state of the slides; and then comes the tentative process on tbe slides themselves. Mr. Ainger was quite right in describing the false notcbes as an admirable addition to the safety of the Bramah lock; bnt he was not correct in stating that these notches rendered any further attempts on the lock bopeless. The false notches are not so deep as the true; they will permit the barrel to turn partially but not wholly round. Bnt even supposing that the false notch had been hit upon in nearly every slide instead of the true, and that the barrel had been partially turned to the extent wbich these notches per-

mitted, there would then be a binding action at the false notches different from that in the true, and this would guide the operator in his search for the true notches. It would not add a new principle different from the one before in action, but it would add to the time during which the search would have to be carried on.

We make these remarks in connection with Mr. Ainger's article, which was probably written twenty years ago. We now come to the year 1850.

At the meeting of the Institution of Civil Engineers, when Mr. Chubb's paper was read, many challenges and counter-challenges were made, as to the possibility of picking certain locks. Mr. Chubb described, among others, a lock on the patent of Mr. Davies, which, ingenious though it be, he considers not safe. Captain D. O'Brien differed from Mr. Chubb in this matter; he had had occasion to open from ten to twenty of Davies's cabinet-locks daily, during a period of two years, and he never once observed the locks to be out of order; in fact, they always appeared to afford great security. Mr. Chubb thereupon rejoined, that he was prepared to produce a workman who would pick any number of Davies' cabinet-locks, of different combinations, which he had never seen before, taking only half an hour for each lock.

As another instance, Captain O'Brien stated that, in his capacity as Inspector of Government Prisons, his attention had been much directed to the subject of secure locks; and he produced, among others, specimens of those in use at the Pentonville Prison; though not of first-rate workmanship, he characterised them as being safe, strong, and cheap. They were on Thomas's principle. The locks had been in use eight years, during which period not one had required to be replaced; and any trifling derangements had been made good whilst the prisoners were at exercise. Mr. Chubb, after making his offer concerning Davies's lock, stated that "he was willing to make the same offer with respect to the locks from the Pentonville Prison; and he might state that, in point of

security, he considered them absolutely worthless;" in proof of which he exhibited one of them, and a common burglar's tool, by which the lock could be opened with the greatest ease.

In respect to Bramah's lock, there was no particular challenge associated with the proceedings of the evening; but incidental observations were made as to the degree of security pertaining to it. Mr. Farey, after passing a high eulogium on the ingenuity of the principle and the beauty of the workmanship, considered it nevertheless objectionable that the sliders should be so completely exposed to view. He then proceeded to make the following observations: "It had been suggested, that a universal false key for Bramah's locks might be made, with the bottoms of its several notches formed by as many small steel sliders, extending beyond the handle of the key, so as to receive pressure from the fingers, for moving each one of the sliders within the lock, with a sliding motion in its own groove, independently of the other. During such sliding motion, a gentle force could be exerted, tending to turn the barrel round. Under such circumstances, supposing that the motion of the barrel was prevented by any one slider only; that one, having to resist all the turning force, would be felt to slide more stiffly endways in its groove, and therefore it could be felt when its unlocking notch arrived opposite the steel plate, and left some other slider to begin to resist the turning force. Such a circumstance (continues Mr. Farey) presumes a palpable inaccuracy in the radiating correspondence between the notches in the steel plate and the grooves for the sliders in the barrel, which could not happen with Bramah's workmanship."* He further remarked: "Unfortunately, if a Bramah's key fell into dishonest hands, even for a short time, an impression could be easily taken, and a false key as easily made. A turkey-quill, notched into the form of a key, had sufficed to open a Bramah's lock; and an efficient false key could be formed out of a pocket pencil-case. Such facility of fabrication was an invitation to dishonesty; and as an

* See also Mr. Owen's suggestion, p. 59, *ante*.

abortive attempt left no trace, the impunity was an encouragement to repeat the attempt until success is attained."

With respect to Chubb's locks, a discussion arose out of a statement made by Mr. Hodge. Mr. Chubb had himself stated it to be a general opinion that a skilful workman, furnished with impressions taken from the true key, in wax or soap, could make a false key to open any lock; and he considered that, in common locks, with the most elaborate wards, but with only one tumbler, as also in Bramah's locks, there was much truth in the notion. In respect to his own lock, however, with six double-acting tumblers, "a false key made ever so carefully from impressions would not be likely to open the lock, for want of exactitude in the lengths of the several steps; and if the key could not be made exact from the impressions, there would be no chance of rectifying it by trial in the lock, on account of the total uncertainty as to which part required alteration." Mr. Hodge stated that, in America, he had repeatedly seen impressions taken of locks having twelve or fourteen tumblers, in consequence of the bellies of the tumblers, when at rest, coinciding with the form of the key (see page 63). He also suggested a method of taking an impression of the bellies of the tumblers; but Mr. Chubb, Mr. Farey, Mr. Stephenson, and Mr. Whitworth, all expressed a disbelief that a Chubb's lock could be opened by the means indicated by Mr. Hodge. Mr. Hodge admitted that he was not aware of any lock actually made by Messrs. Chubb having been picked in America; but that the locks to which he had adverted were such exact imitations, that he had no doubt of the Chubb lock yielding to similar treatment. He further stated that there were persons in New York who would undertake to pick a real Chubb lock.

CHAPTER IX.

THE LOCK CONTROVERSY: DURING AND SINCE THE TIME OF THE GREAT EXHIBITION.

We next come to the remarkable year 1851, which produced so many unexpected results in connection with the industrial display in Hyde Park, and conferred a lasting benefit on the useful arts and manufactures of the United Kingdom, by bringing their products into contrast and competition with those of other nations. It was to be expected that such a trial as this would afford evidences of national failure as well as of success; but probably no one suspected before the trial, that English locks, so celebrated over the greater part of the world for skilful mechanical design, beauty of workmanship, and perfect inviolability, would readily yield to a well-arranged system of lock-picking. Such, however, was the case; and we are bound to admit that Mr. Hobbs, the author of this system, is a mechanician of great skill, and with a profound knowledge of the art of the locksmith.

The first step in the celebrated *lock controversy* of 1851 was taken by Mr. Hobbs himself, who declared to a party of scientific men in the Crystal Palace, that all the locks made in this country up to that date admitted of being very easily picked; and in order to explain to these gentlemen the principle upon which this was to be done, Mr. Hobbs picked one of Chubb's patent detector-locks in their presence in a few minutes.

The fairness of this experiment having been called in question by certain persons who were not present at the time when it was made, Mr. Hobbs, on July 21st, 1851, wrote a letter from the American department of the Great Exhibition, to Messrs. Chubb, simply announcing that an attempt would be made, on the next following day, to pick a lock manufactured by

them, and which was at that time on the door of a strong room in a house named by Mr. Hobbs. Messrs. Chubb were invited to be present at the operation; but no member of the firm attended. What occurred on the day specified may best be given in the words of a letter written by those who witnessed the operation.

"London, July 22, 1851.

"We the undersigned hereby certify, that we attended, with the permission of Mr. Bell, of No. 34 Great George-street, Westminster, an invitation sent to us by A. C. Hobbs, of the City of New York, to witness an attempt to open a lock throwing three bolts and having six tumblers, affixed to the iron door of a strong-room or vault, built for the depository of valuable papers, and formerly occupied by the agents of the South-Eastern Railway; that we severally witnessed the operation, which Mr. Hobbs commenced at 35 minutes past 11 o'clock A.M., and opened the lock within 25 minutes. Mr. Hobbs having been requested to lock it again with his instruments, accomplished it in the short space of 7 minutes, without the slightest injury to the lock or door. We minutely examined the lock and door (having previously had the assurance of Mr. Bell that the keys had never been accessible to Mr. Hobbs, he having had permission to examine the key-hole only). We found a plate at the back of the door with the following inscription: 'Chubb's New Patent (No. 261,461), St. Paul's Churchyard, London, Maker to Her Majesty.'"

This letter was signed with the names and addresses of the following gentlemen:—

Mr. Handley.
" William Marshall.
" W. Armstead.
" G. R. Porter.*
" F. W. Wenham.
" A. Shanks.
Mr. T. Shanks.
Colonel W. Clifton.
Mr. Elijah Galloway.
" Paul R. Hodge.
" Charles H. Peabody.

Several of these names are well and publicly known in England and the United States.

* Late Secretary to the Board of Trade.

This event gave rise to much newspaper controversy; and attempts were made to shew that, as this was not a *test* lock, prepared expressly for challenge, the picking proved nothing as regards the finest of the manufacturers' locks. Two circumstances, however, have to be noticed—that the lock was of sufficient commercial importance to be placed on a door enclosing valuable papers, and that the makers had an opportunity to attend and witness, and comment on the trial, if they so chose. We may here remark, that one of the ingenious contrivances of the Chubb lock, the *detector*, excited some doubt no less than fifteen years ago, as will be seen from the following. The writer of the article "Lock" in Hebert's *Engineers' and Mechanics' Encyclopædia*, while speaking with much commendation of Chubb's locks, points out a curious feature, which seems to him to render somewhat doubtful the surety of the *detector* apparatus. "In Barron's and Bramah's locks," he observes, "the picker has no means of knowing whether the tumblers are lifted too high or not; but in Chubb's he has only to put the detector *hors de combat* in the first instance, by a correct thrust from the outside of the door (which might be accurately measured), so as to *fix* it fast in its place; the detector then becomes a stopper to the undue ascent of the tumblers, and the extent of their range is thereby correctly ascertained. Thus, it appears to us, the *detector* might be converted into a *director* of the means for opening the lock."

Much will depend on the view which is taken of the circumstance just noted. The object of the detector is, not to prevent the lock from being picked, but to shew that an attempt has been made to pick it; or, at least, to attain a given purpose by an indirect instead of a direct method. But if there be really any truth in the surmise, that the detector actually guides a skilful hand in determining how high the tumblers should be raised, the supposed advantage will be purchased at rather a dear rate. As we are here, however, speaking of facts and not of mere opinions, it is proper to say,

Google

that the lock opened by Mr. Hobbs had the detector apparatus, but that it was not disturbed by him in picking the lock.

But instead of reiterating opinions, we will state the method by which most of the tumbler-locks made in England, up to the date of the Great Exhibition, can be opened or picked.

Bearing in mind the principle on which the picking of locks is said to depend, namely, that "whenever the parts of a lock which come in contact with the key are affected by any pressure applied to the bolt, or to that portion of the lock by which the bolt is withdrawn, in such a manner as to indicate the points of resistance to the withdrawal of the bolt, such a lock can be picked," the first step is to produce the requisite pressure.

If the end of the bolt were exposed, this pressure might be applied by some force tending to shoot back the bolt; but as the bolt, whenever it is shot, is buried in the jamb of the door, or otherwise concealed from view, the pressure can in general only be applied through the key-hole. In order, therefore, to apply this pressure, the operator provides himself with an instrument capable of reaching the talon of the bolt, which in the case of the Chubb lock was a pipe-key of the form shewn at *a b*, fig. 49, furnished at the pipe-end with that portion of



fig. 49.

the bit of the key *b c* which moves the bolt (see fig. 32, page 57, where the step which acts on the bolt is called the terminal step). The other end of the pipe-key is made square, as at *a*, for the purpose of receiving the square eye *e* of the lever *e f*, fig. 50, to the further end of which *f* a weight *w* is attached by means of a string *s*. Now it is evident that if this pipe be introduced into the lock as far as it will go, and be turned

round as in the act of unlocking, and the lever and weight be attached to the end *a*, the bit *b c* of the pipe-key will maintain a permanent pressure on the bolt, which, if the weight he sufficient, will throw hack the holt as soon as the tumhlers are raised to the proper height to allow the stump to pass.



fig. 50.

The next step in the operation is to raise the tumblers to the proper height. For this purpose a second pipe *m n* is made to slide upon the first with an easy motion, and hy means of the cross handle *h h* can be turned round or slid backwards and forwards on the tuhe *a b*. This tube *m n* is also furnished with a single projecting hit or step *n o*, corresponding with one of the six steps of the key, fig. 32, and made of the proper length for entering the key-hole.

Now for the operation of opening a tumhler-lock with this simple apparatus. Referring to fig. 31, page 56, it will he evident that if the pipe *a b*, fig. 49, be passed over the pin of the lock and turned round towards the left, and the weight be attached, there will be a tendency in the bolt to shoot hack, which tendency will hring the stump *s*, fig. 31, up against the inner angle or shoulder of one or other of the tumhlers, whichever happens to project, however slightly; or, as Mr. Hohhs expresses it, "one or more of the tumblers will hind." By moving forward the pipe *m n* and turning round the bit *n o* in the lock, it is easy to ascertain, hy delicate touch, which of the tumhlers it is that hinds. It may be found that all are free to move except one or two against which the stump is pressing with the force of the weight *w*, fig. 50. The hit *n o* is therefore hrought gently under the bellies of the tumblers which hind, and they are moved slightly upwards until they cease to bind. As soon as they are set free another tumhler

will bind; that is, the bolt will move through a small space, so as to bring the stump into contact with that particular tumbler which now projects; this in its turn is relieved, another tumbler binds and is relieved, and so on until the tumblers are, one by one, raised to the proper height for the stump to pass. When the last binding tumbler is raised to the proper height, the weight *w* being no longer resisted, shoots the bolt back, and the work is done.

Now it must be evident that in this operation the detector apparatus need not come into operation. But if, as has been proposed, a detector-spring be added to each tumbler, it may be converted into a friend or a foe according to the use that is made of it. If the tumblers are lifted *too high*, they will be detained or detected in that position, and the operator will have to release them by turning the bit round in the opposite direction before he can begin his work again. The same force, however, which detains the tumblers when they are lifted too high will obviously detain them when they are lifted only just high enough, and thus the detector-springs would really be of great assistance to the operator in picking such a tumbler-lock.

The apparatus which we have described for picking the tumbler-lock must be varied to suit the form of key employed in opening the lock; but it is not difficult, in the case of most locks, to ascertain this form through the key-hole, without examining the key itself.

It is but fair to state in this place, that since the above method of picking tumbler-locks was made known,* Mr. Chubb

* We believe the method was first made publicly known at a special general meeting of the members of the Institution of Mechanical Engineers, held at the rooms of the Society of Arts, London, on the 30th June, 1851, when a paper was read by Mr. Paul R. Hodge "On the progress of improvements in locks in the United States of America." A report of this paper, together with the discussion thereon, was published by Waterlow and Sons, London Wall, 1851. Plate 34 (figs. 9 and 10) of this report contains representations of the lock-picking apparatus, from which we have copied our figures.

has added a series of teeth and notches to the stump and tumblers; the effect of which would evidently prevent the application of the above method of picking, because any permanent pressure applied to the bolt would send a tooth of the stump into a notch of the tumbler, and prevent all further motion. But recurring to the principle, that whenever the parts of a lock which come in contact with the key indicate the points of resistance when any pressure (*whether permanent or temporary*) is applied in attempting to withdraw the bolt, that lock can be picked, it follows, if this principle be admitted, that although the notches prevent the application of the form of instrument described, yet there is sufficient indication afforded by the pressure to enable a skilful operator, with proper instruments, to form a false key, as was done in the case of the lock referred to at page 104. We now proceed to the second stage in the lock controversy of 1851.

Soon after the picking of the Chubb lock in Great George-street, and consequent on the excitement and discussion to which that operation led, a committee, consisting of Mr. G. Rennie, Professor Cowper,* and Dr. Black, agreed to superintend the arrangements for a more severe testing of Mr. Hobbs's power to open locks. There had been for many years exhibited in the window of Messrs. Bramah's shop, in Piccadilly, a padlock of great complexity and beauty; to which an announcement was affixed, that a reward of two hundred guineas would be given to any person who should succeed in picking that lock. This challenge was accepted by Mr. Hobbs; and the committee managed all the arrangements, as arbitrators between Mr. Hobbs on the one side and Messrs. Bramah on the other. The lock was removed to an upper room in Messrs. Bramah's establishment; where it was placed between two boards, and so fixed and sealed, that no access could be

* In mentioning the name of the late Professor Edward Cowper, we cannot refrain from deploring the loss which mechanical science has suffered by his too early death. The application of mechanical principles to manufactures was treated by him in his lectures and illustrations with a felicity which has been rarely equalled.

obtained to any part of it except through the key-hole. The room was to be given up to Mr. Hobbs; he was not to be interrupted by the presence or entrance of any other persons; and he was allowed a period of thirty days for opening the lock. If the lock was not picked at the expiration of that period, Mr. Hobbs was to be considered as having failed in his attempt.

There was much negotiation and correspondence before and during Mr. Hobbs's operation on this lock. On July 2, he, with a view to this enterprise, applied for permission to take wax impressions of the key-hole. This permission being given, and the parties having met to discuss the necessary arrangements, an agreement was signed on the 19th, reciting the terms of the challenge, and providing that thirty days should be allowed to Mr. Hobbs to effect his enterprise; that the lock should be secured in a certain specified way; and that the key should remain in the possession of Messrs. Bramah, who were to retain the right of using it in the lock when Mr. Hobbs was not at work. Messrs. Bramah subsequently relinquished this last-mentioned privilege, in order that the trial might be perfectly fair; and it was agreed that the key should be sealed up during the whole period, beyond the reach either of Mr. Hobbs or Messrs. Bramah; and that the key-hole should be secured by an iron band, sealed, when Mr. Hobbs was not at work. These and other conditions were embodied in the agreement noticed in the last paragraph.

Mr. Hobbs commenced his labours on July 24th. After a few visits to the lock, Messrs. Bramah wished to have the privilege of inspecting it, or else that such an inspection should be made by the arbitrators; and, during a correspondence which arose out of this request, the operations were suspended. Mr. Hobbs resumed his work on August 16. On the 23d, Messrs. Bramah drew the attention of the arbitrators to the challenge, that the reward of two hundred guineas was offered to the artist who should make an instrument that would pick or open the lock; that he was to be paid the money on the production of the instrument; and that, unless some person were present, it

was impossible that any one could know that the lock had been opened by the instrument which might be produced. This letter was not allowed by the arbitrators to affect the arrangements made. We may now consistently give the "Report of the Arbitrators."

"Whereas for many years past a padlock has been exhibited in the window of Messrs. Bramah's shop, in Piccadilly, to which was appended a label with these words: 'The artist who can make an instrument that will pick or open this lock shall receive two hundred guineas the moment it is produced;' and Mr. Hobbs, of America, having obtained permission of Messrs. Bramah to make trial of his skill in opening the said lock, Messrs. Bramah and Mr. Hobbs severally agreed that George Rennie, Esq., F.R.S., of London; and Professor Cowper, of King's College, London; and Dr. Black, of Kentucky; should act as arbitrators between the said parties.

"That the trial should be conducted according to the rules laid down by the arbitrators, and the reward of two hundred guineas be decided by them; in fine, that they should see fair play between the parties.

"On July 23 it was agreed that the lock should be enclosed in a block of wood, and screwed to a door, and the screws sealed, the key-hole and the hasp only being accessible to Mr. Hobbs; and, when he was not operating, the key-hole was to be covered with a band of iron and sealed by Mr. Hobbs, that no other person should have access to the key-hole. The key was also sealed up, and was not to be used until Mr. Hobbs had finished his operations. If Mr. Hobbs succeeded in picking or opening the lock, the key was to be tried; and if it locked and unlocked the padlock, it should be considered as a proof that Mr. Hobbs had not injured the lock, but had fairly picked or opened it, and was entitled to the two hundred guineas.

"On the same day, July 23, Messrs. Bramah gave notice to Mr. Hobbs that the lock was ready for his operations.

"On July 24 Mr. Hobbs commenced his operations; and

on August 23 Mr. Hobbs exhibited the *lock opened* to Dr. Black and Professor Cowper (Mr. Rennie being out of town). Dr. Black and Mr. Cowper then called in Mr. Edward Bramah and Mr. Bazalgette, and shewed them the lock opened; they [the last-named two gentlemen are of course meant] then withdrew, and Mr. Hobbs locked and unlocked the padlock in presence of Dr. Black and Mr. Cowper.

"Between July 24 and Aug. 23 Mr. Hobbs's operations were for a time suspended; so that the number of days occupied by Mr. Hobbs was sixteen, and the number of hours he was actually in the room with the lock was fifty-one.

"On Friday, Aug. 29, Mr. Hobbs again locked and unlocked the padlock in presence of Mr. G. Rennie, Professor Cowper, Dr. Black, Mr. Edward Bramah, Mr. Bazalgette, and Mr. Abrahart.

"On Saturday, Aug. 30, the key was tried, and the padlock was locked and unlocked with the key, by Professor Cowper, Mr Rennie, and Mr. Gilbertson; thus proving that Mr. Hobbs had fairly picked the lock without injuring it. Mr. Hobbs then formally produced the instruments with which he had opened the lock.

"We are, therefore, unanimously of opinion, that Messrs. Bramah have given Mr. Hobbs a fair opportunity of trying his skill, and that Mr. Hobbs has fairly picked or opened the lock; and we award that Messrs. Bramah and Co. do now pay to Mr. Hobbs the two hundred guineas.

GEORGE RENNIE, *Chairman.*
EDWARD COWPER.
J. R. BLACK.

Holland Street, Blackfriars,
Sept. 2, 1851."

It may be here stated, in reference to the space of time during which the operations were being conducted, that the actual opening of the lock occurred much earlier, so far as concerned the principle involved, though not in a way to meet the terms of the challenge. On his fifth visit, Mr. Hobbs suc-

ceeded in adjusting the slides and moving the barrel, preparatory to withdrawing the bolt; but the instrument with which the barrel was to be turned round, being too slight, slipped, and defeated the operation. Mr. Hobbs had then to readjust the barrel, and to make a new instrument to aid him; this new instrument, when completed, enabled him to open the lock in the space of an hour or two.

On the same day Messrs. Bramah addressed a letter to the arbitrators, stating the reasons which induced them to think that, though Mr. Hobbs had succeeded in opening the lock, the manner of doing so did not come within the meaning of the challenge originally made by them. The arbitrators, however, were unanimous in their award, and Messrs. Bramah bowed to it.

In an article written in one of the daily newspapers immediately after the opening of the lock, the following notice was given of the lock and its production: "We were surprised to find that the lock which has made so much noise in the world is a padlock of but 4 inches in width, the body of it $1\frac{1}{4}$ inches thick, and its thickness over the boss $2\frac{3}{4}$ inches. Upon opening the outer case of the lock, the actual barrel enclosing the mechanism was found to be $2\frac{1}{4}$ inches in length and $1\frac{1}{2}$ inches in diameter. The small space in which the works were confined, and its snug, compact appearance was matter of astonishment to all present. The lock and key were made forty years since by the present head of the eminent firm of Messrs. Maudslay and Co., Mr. Maudslay being at that time a workman in the employ of Mr. Bramah."

We may here remark, as indeed has been remarked in former pages, that the Bramah lock is, and will probably continue to be, deservedly celebrated for the amount of mechanism contained in a small space, as adverted to in the last paragraph. The cylindrical form is well calculated for this concentration of power within narrow limits; and the smallness of the key is a great merit.

The objections made by Messrs. Bramah to the award of

the committee were embodied in the following letter to Mr. Rennie, dated 9th September:

"Dear Sir,—We beg to acknowledge your letter of yesterday's date, and will not trouble you to attend here to-morrow, but beg to hand you the 210*l.* awarded by the arbitrators to Mr. Hobbs. We need scarcely repeat that the decision at which the arbitrators have arrived has surprised us much; and we owe it to ourselves and the public to protest against it. We do so for the following reasons:

"1. Because the arbitrators, having been appointed to see fair-play, and that the lock was fairly operated upon, did not, although repeatedly requested in writing to do so, once inspect or allow any one to witness Mr. Hobbs's operations during the sixteen days he had the sole custody of the lock and was engaged in the work.

"2. Because the arbitrators did not once exercise their right of using the key, although repeatedly requested in writing to do so, till after Mr. Hobbs had completed his operations; and then, instead of applying at once to prove that no damage had been done to the lock, allowed him twenty-four hours to repair any that might have occurred.

3. "Because the lock being opened by means of a fixed apparatus screwed to the wood-work in which the lock was enclosed for the purpose of experiment (which it is obvious could not have been applied to an iron door without discovery), and the addition of three or four other instruments, the spirit of the challenge has evidently not been complied with.

"4. Because from the course adopted an opportunity of some good scientific results has been taken from us; as neither arbitrators nor any one else saw the whole or even the most important instruments, by which it is said the lock was picked, actually applied in operation, either before or after the lock was presented open to the arbitrators.

"5. Because during the progress of Mr. Hobbs's operations, and several days before their completion, we called the atten-

Digitized by Google

tion of the arbitrators to what we considered the interpretation of the challenge, begging at the same time that they would apply the key and appoint some one to be present during the residue of the experiment; feeling that whatever might be the result in a scientific point of view, the reward could not be awarded.

"We would add, that we think that several points which appear in your minutes should not have been mentioned in your award; more especially that Mr. Hobbs on the 2d of June took a wax-impression of the lock, and had made, as far as he could, instruments therefrom between that date and the commencement of his operations.

"We are, dear sir,

"Your obedient servants,

"BRAMAH AND CO."

In order that the opinions of Messrs. Bramah and others may be given with as much fairness as possible, on a matter which they could not feel but otherwise than important to them, we may state, that among the letters to which the picking of the Bramah lock gave rise in the public journals, was the following addressed to the *Observer* newspaper on 10th October:

"SIR,—This controversy having excited an unusual degree of public attention for some time past, perhaps you will be good enough to allow us to state in your journal, that the lock on which Mr. Hobbs operated had not been taken to pieces for many years, and it was only on examining it (after the award of the committee) that we discovered the startling fact, that in no less than three particulars it is inferior to those we have made for years past. The lock had remained so long in its resting-place in our window that the proposal of Mr. Hobbs somewhat surprised us. After his appearance, however, no alteration could of course be made without our incurring the risk of being charged with preparing a test-lock for the occasion; we were therefore bound in honour to let the lock re-

main as Mr. Hobbs found it when he accepted the challenge. No one inspected his operations during the sixteen days he had the sole custody of the lock and was engaged at the work. We are therefore compelled to advertise another 200 guineas, in order that we may see the lock operated upon and opened, if it be possible; and thus gain such information as would enable us to use means that would defy even the acknowledged skill of our American friends. We believe the Bramah lock to be impregnable; and we cannot open it ourselves, with the knowledge Mr. Hobbs has given us. We have fitted up the same lock with such improvements as we now use, and some trifling change suggested by the recent trial, and restored it with its challenge to our window. We have not done this in a vain, boasting spirit; on the contrary, we feel it rather hard that, from the way in which the former trial was conducted, we are driven to adopt this course. Had any one inspected Mr. Hobbs's operations during that trial, it would not have been necessary.

"We are, sir, &c.,

"BRAMAH AND CO."

Messrs. Bramah are well entitled to offer any explanation concerning the relative perfection of the lock in question, and of one that they could now produce with certain improvements in some parts of the working mechanism; but if these improvements do not involve any new invention, patented or otherwise, —that is, if the lock be really a carrying out of the contrivances already made public,—it is difficult to see why it should not yield to the same treatment as the other. It is true that, shortly after the decision of the arbitrators, Messrs. Bramah exhibited a new lock in their window, and repeated their challenge in the same terms as before, with the single addition, that applications were to be made in writing only. We have reason to know that an application was made, and that the consequence was the withdrawal of the challenge. In respect to the actual contest, however, the character and position of

the arbitrators ought surely to hold Mr. Hobbs justified in his proceedings. They were not all Americans (supposing nationality to give a bias in the matter); two were Englishmen, both of distinguished rank in respect to mechanical knowledge; and as Mr. Hobbs was as much bound by their decision as Messrs. Bramah, he was entitled to claim any advantage resulting from a favourable decision.

The following is a description, so far as can be given in words, of the mode in which Mr. Hobbs operated on the Bramah lock. The first point to be attained was to free the sliders from the pressure of the spiral spring; the spring was very powerful, pressing with a force of between 30 and 40 lbs.; and until this was counteracted, the sliders could not be readily moved in their grooves. A thin steel rod, drilled at one end, and having two long projecting teeth, was introduced into the key-hole and pressed against the circular disc between the heads of the sliders; the disc and spring were pressed as far as they would go. In order to retain them in this position, a curved stanchion was screwed into the side of the boards surrounding the lock, and the end brought to press upon the steel rod, a thumb-screw passing through the drilled portion of the instrument and keeping it in its place. The sliders being thus freed from the action of the spring, operations commenced for ascertaining their proper relative positions. A plain steel needle, with a moderately fine point, was used for pushing in the sliders; while another with a small hook at the end, something like a crochet-needle, was used for drawing them back when pushed too far. By gently feeling along the edge of the slider, the notch was found and adjusted, and its exact position was then accurately measured by means of a thin and narrow plate of brass, the measurements being recorded on the brass for future reference. The operator was thus enabled, by this record, to commence each morning's work at the point where he left off on the previous day. The lock having eighteen sliders, the process of finding the exact position of the notch in each was necessarily slow. Mr. Hobbs employed a small

bent instrument to perform the part of the small lever or bit of the key; with this he kept constantly pressing on the cylinder which moved the bolt. He thus knew that if ever he got the slide-notches into the right place, the cylinder would rotate and the lock open. He could feel the varying resistance to which the sliders were subjected by this tendency of the cylinder to rotate; and he adjusted them one by one until the notch came opposite the steel plate. The false notches added, of course, much to his difficulty; for when he had *partially* rotated the cylinder by means of the false notches, he had to begin again to find out the true ones.

This description accords pretty nearly with that given in a former page; but we reproduce it here to shew not merely what *might* be the process adopted, but what really *has been* done. One circumstance ought at least to be noted in these transactions—there is no mystery; the method adopted is the result of a process of reasoning candidly and openly explained.

In justice to Messrs. Bramah we thought it our duty to give them an opportunity of stating what improvements they had made in their locks since the date of the Great Exhibition; and accordingly, on the 28th April, 1853, our publisher addressed to Messrs. Bramah a note, stating that a *Rudimentary Treatise on the Construction of Locks* was being prepared, and inviting them to contribute thereto. The following is a copy of their reply:

"124 Piccadilly, May 2d, 1853.

"Sir,—Pressure of business has prevented our sending an earlier reply to your favour of the 28th ult.

"The lock on which Mr. Hobbs operated during the Great Exhibition had been made nearly forty years, and when taken to pieces the sliders were found to be in iron, instead of steel; and the key-hole of the lock being three times larger than it ought to have been, enabled the operator to fix down the spring of the lock, and yet leave himself ample space to turn and bend the sliders (being in iron) at pleasure. The barrel of the lock in which the sliders act, instead of being whole length from

front to back of padlock, was not quite half its proper length; a serious oversight in the workman who put the lock together, as the barrel being short, the sliders were necessarily so, which diminished the number of notches in the sliders full one-half, and to that extent diminished the security of the lock, and increased the facility of the operator.

"We send for your inspection a box of guards, which will shew you the barrel and sliders of our Bramah lock. You will observe several notches in each slider, only one of which will turn on the locking-plate, the others being what are termed false, or security ones. These notches being cut only the exact width of the locking-plate, require the most perfect accuracy to carry each down to its proper distance. In the lock on which Mr. Hobbs operated, in addition to the sliders being so short, and only half the number of security-notches in each, the notch which passed round the locking-plate was found to be cut twice the width it ought to have been. The whole of these defects have been corrected since the Exhibition.

"We are, Sir, yours respectfully,

"Bramah and Co.

"per J. Smyth.

"To John Weale, Esq., 59 High Holborn."

In the Jury Report of the Great Exhibition, Class XXII., are the following remarks: "On the comparative security afforded by the various locks which have come before the jury, they are not prepared to offer an opinion. They would merely express a doubt whether the circumstance that a lock has been picked under conditions which ordinarily could scarcely ever, if at all be obtained, can be assumed as a test of its insecurity." [page 500]. The conditions here alluded to probably refer to the free access which Messrs. Bramah allowed Mr. Hobbs to have to their lock during a period of thirty days, and we are hence led to infer that the burglar is denied any such facilities. On this point we would refer to the opinion of a high authority. In a paper "on the History and Con-

struction of Latches and Locks," by Mr. Chubb, read before the Society of Arts, 22d January, 1851, the following graphic passage occurs :

"In order to shew the absolute necessity of secure locks and safe depositories for property, especially in banking establishments, it may not be out of place to trace the systematic care and great sagacity with which the large burglaries are planned. You will bear in mind that an unsuccessful attempt is seldom made where the booty is of any magnitude. The first-rate 'cracksmen' always know beforehand where to go, when to go, and what they are going for. When a 'plant,' as it is termed, is made upon a house or a bank, precise information is gained, if possible, as to the depository of the valuables ; and if it is found that the safeguards are too strong in themselves, and that the locks are invulnerable, the affair is quietly dropped. But if otherwise, then no expenditure of time or misapplied ingenuity is spared to gain the desired end. The house is constantly watched, the habits of its inmates are observed, their ordinary times of going out and coming in are noted ; the confidential servants are bribed or cajoled, and induced to leave the premises when their employers are absent, so that impressions may be taken from the locks, and false keys made. When all the keys required are made, one or two men who have not been previously initiated are generally called in, and receive their instructions to be ready at a certain hour on the following day to enter the house. A plan of the premises is put into their hands, they are cautioned to step over a certain creaking stair or plank, and the keys of the different doors are given them. The day or evening is chosen when it is known that the inmates will be from home—the servant, taking advantage of their absence, fulfils a long-standing engagement with his new and liberal friends—a signal is given—the two confederates enter—the so-called safe is swept of its contents, all the doors are carefully re-locked, and not until the bank is opened for business next morning is the robbery discovered."

In an article in *Frazer's Magazine* for November 1852 the following observations were made on the Exhibition Jury Report on Locks: "This jury seems to have consisted of the only persons in England who did not hear of the famous 'lock controversy' of last year; for one can hardly imagine that, if they had heard of a matter of so much consequence to the subject they were appointed to investigate, they would have altogether abstained from saying any thing about it. They may be excused for not knowing, because very few people did know, fortunately for our safes and strong boxes, that the mode of picking Bramah's and Chubb's locks, by which the transatlantic Hobbs gained so much glory, was suggested and explained in the *Encyclopædia Britannica* nearly twenty years ago. But it does seem very strange that they, or at least their reporter, should not have known, long before the Report finally left his hands, that Hobbs had picked both of those locks, and taught every lock-picker in England how to do it, if he possesses the requisite tools and fingers. Of course, however, the reporter did not know it, as nobody could read any newspaper last autumn without knowing it. And this jury did exercise their judgment to the extent of declaring that Hobbs's own lock (under the name of Day and Newell) 'seems to be impregnable.' Notwithstanding all which, they express their inability to 'offer any opinion on the comparative security afforded by the various locks that have come before them.' The only discrimination which they venture to make is, that the keys of Bramah's and Chubb's locks are of convenient size, while Hobbs's is ponderous and bulky, and his lock complicated; and they might have added (without any very painful amount of investigation), enormously expensive, in consequence of its complication, and probably also more likely, on the same account, to get out of order and stick fast, and so become rather inconveniently impregnable—on the money door of a bank, for instance,—than the other two locks, especially Bramah's."

In relation to the opinion just given, it may be remarked that the American lock has shewn no tendencies to get out of

order; if well constructed (and good construction is a *sine qua non* in such mechanism), the parts work into and upon each other with very little friction. In respect to expense, and to the size of the key, a *bank*-lock is not one in which economy would be much studied, security being the great desideratum. No attempt is made to produce a parautoptic lock of small size or for cheap purposes. The lock, therefore, must he jndged of with reference to what it undertakes to perform. And this brings us to notice the attempts made in England to pick the parautoptic or American hank-lock.

The following were the circumstances connected with Mr. Garhutt's attempt to pick the American lock. It is of course known that a challenge was affixed to the American lock in the Great Exhibition, and it was this challenge which Mr. Garhutt accepted. Mr. Garhutt, it may be here observed, was a working locksmith and engineer; he had heen entrusted by Messrs. Fox and Henderson with the care and adjustment of the metal check-tahles at the pay-places of the Crystal Palace; he had at a previous period heen in the employ of Messrs. Bramah. We mention these facts only on account of an erroneous rumour at the time that he was an agent of Messrs. Bramah in respect to the acceptance of the American challenge; whereas we believe he acted independently, hy and for himself.

On Sept. 10th, 1851, Mr. A. H. Renton, Mr. E. H. Thomson, and Mr. W. F. Shattuck,—the first an engineer, and the other two American exhibitors,—were appointed arhitrators to superintend the arrangements, and they met Mr. Garhntt and Mr. Hohbs at the house No. 20 Knightsbridge. The following conditions were agreed to:—That a Newell lock should he selected, and should be screwed to a wooden hox; that Mr. Garbutt should have access only to the key-hole of the lock, through which key-hole all his operations for picking the lock should be condnoted; that Mr. Garhutt should have uninterrupted and exclusive access to the box, between the hours of nine in the morning and nine in the evening, for thirty days, heginning on the 11th of September, he having

during that time the privilege of introducing one associate, and the arbitrators reserving to themselves the right of inspecting the seals placed by them on the box; that, in order to afford every information concerning the internal arrangement of the lock, the trial-lock should be taken to pieces in presence of all the parties; that it should be examined by Mr. Garbutt; that it should be locked and unlocked with the proper key by him and by Mr. Hobbs; that it should be fastened to a box, and the fastenings sealed by the arbitrators; that the key, when the lock was finally locked, should be sealed up by the arbitrators and delivered to Mr. Hobbs, who would retain it until required by the arbitrators to hand it over to them. That at the expiration of the thirty days, or earlier in case either of the success or the abandonment of the attempt, the arbitrators should examine the lock. And, finally, that if Mr. Garbutt should have succeeded in picking the lock (that is, in withdrawing the bolt without injuring the lock), the sum of 200*l.* should be paid to him by Mr. Hobbs.

In accordance with the above agreement, Mr. Hobbs produced a parautoptic lock, with ten tumblers, marked No. 8560. The key and the lock were examined by Mr. Garbutt. The lock was again put together, affixed to a box, and sealed. Mr. Hobbs set the bits of the key (ten in number) to an arrangement chosen by himself, and the lock was then locked by all parties in succession; the key, after the final locking, being sealed up and returned to Mr. Hobbs. Mr. Hobbs at the same time delivered to Mr. Garbutt a similar but smaller lock, which he was to be allowed to retain during the whole period of the trial, to assist in rendering him familiar with the construction of both locks.

On the 11th of October, the day on which the prescribed period expired, the arbitrators met at the house in question, when Mr. Garbutt delivered up to them the lock uninjured, but *unopened*. The award of the arbitrators was thereupon given in the following terms: "We therefore hereby certify that Mr. Garbutt having had uninterrupted and exclusive ac-

cess to the lock during the period of thirty days, and, availing himself of the conditions of the agreement, had every facility for opening the lock that could he obtained without possession of the true key, has delivered up the same into our hands unopened and uninjured; and the said lock has been delivered hy us to Mr. Hobbs."

It will of course be understood that it was one condition of this enterprise, that the particular combination of bits in the key wherewith the lock was finally locked should not be seen by Mr. Garbutt. The key was in the first instance tried by Mr. Garbutt and by the members of the committee, and was found to turn readily in the lock; Mr. Hobbs then left the room, and re-arranged the bits of the key so as to produce a new combination; he then returned to the room, and locked the lock with the key in its altered form; he allowed all present to feel the key turn freely, and then, without allowing any one to see the combination, wrapped the key up in paper, in which it was sealed as above described. Whether Mr. Garbutt, or any one, could have succeeded better by a momentary glance at the arrangement of the key, was not at that moment the question: the terms of the challenge were that he should *not* see it. What are the circumstances likely to occur if the operator really has access to the key (provided the bits are not very numerous) we may shortly explain.

It is necessary to draw a distinction between *picking of a lock* and *ringing the changes on a permutating key;* otherwise some of the late occurrences connected with locks can hardly be understood. After the reading of a paper by Mr. Hobbs before the Society of Arts, a discussion arose, in which it was stated that the Newell lock had heen picked in London. Mr. Hobbs deemed it necessary to refute this statement. The report was circulated in many of the London newspapers; and Mr. Jeremiah Smith, the operator in question, supported it by his own statement. Under these circumstances Mr. Hobbs, on April 2, 1852, addressed a letter to the editor of the *Observer;* of which the following paragraph was intended to

point out the distinction above mentioned between "picking" and "ringing the changes:"

"Early last autumn I lent to Mr. Potter, of South Molton Street, one of my locks, for the purpose of giving him an opportunity to make himself acquainted with its principle and construction. After he had had the lock in his possession several weeks, a report reached me that one of Mr. Potter's workmen had picked my lock. I immediately called on Mr. Potter to ascertain the fact. Mr. Potter informed me that for the purpose of testing the possibility of opening the lock by means of an impression taken, or a copy being made of the true key, Mr. Smith had made a copy of the key by means of a transfer instrument, which instrument he shewed me at the time. After the key was made, it was tried, and found to lock and unlock the lock as readily as the original key. Mr. Potter then sealed the screws of the lock, changed the combination of the key, and locked it. Mr. Smith then took the lock, and with the key that he had made by copying the original, hit the combination, and unlocked it. The lock was of the smallest size, having but six tumblers; the number of changes that could possibly be made were 720. The time occupied by Mr. Smith, according to his own statement, was six hours and fifty-five minutes; this, allowing one minute for each change, would give him time to have made 415 out of the 720 changes before hitting the right one. I asked Mr. Smith why he did not use the original key instead of making a copy? His answer was, that 'he could change the one he made faster, as he did not have to screw the bits in.' Any person will readily understand the difference between ringing the combination of a key and picking a lock."

In other words, the process was this: the operator had the true key, and might have used either this or one which he made from it. This would have sufficed for opening almost any lock ever constructed instantly; but in the American lock he had to find out which of 720 combinations was the right one, and he was employed almost seven hours in doing this.

The exploit shewed patience, but had little bearing on the practical subject of lock-picking.

In March 1852 Mr. Smith put forth an offer to accept the challenge made by Mr. Hobbs in respect to the Exhibition lock. Mr. Hobbs agreed to the offer, and chose, as arbitrators on his part, Mr. Hensman, Engineer to the Bank of England, and Mr. Appold, inventor of the centrifugal pump which attracted so much attention at the Great Exhibition. Mr. Hobbs requested Mr. Smith to appoint arbitrators on his side also; but this was not done. Mr. Smith, at a meeting held by the four persons named, expressed a wish that an ordinary commercial lock should be the one experimented on, instead of the more complicated test-lock which had been at the Great Exhibition. This was a departure from the terms of the original challenge; but Mr. Hobbs waived his objection on this point, and offered to substitute a bank-lock with ten tumblers for the Exhibition lock with fifteen, the former being similar in construction but less complex. Another meeting was agreed upon, but Mr. Smith did not attend; and the matter was, by himself, brought to a sudden termination.

To shew the effect of difference in the number of tumblers and key-bits, we may state that, while, at a minute per change, it would take twelve hours to go through all the combinations with a six-bitted key, it would require seven years with a ten-bitted, and 2,500,000 years with a fifteen-bitted key! So much for power of combination, in the arithmetical mode of picking.

We now proceed to notice the violability of sundry minor locks. It might at first appear that the *letter-lock* is exceedingly difficult to pick; and so it unquestionably is, as long as we merely attend to the chance-medley trials by turning the rings round and round until we happen to hit upon the right combination. But there is another mode of solving the riddle, mechanical rather than arithmetical. A piece of common wire, bent in the form of the shackle, is put in between the ends of the lock; the spring or elasticity of the wire tends to force

Digitized by Google

the ends apart; this causes the pins or studs on the rod to press against the inner edges of the rings. By trying all the rings in succession, some one of them will be found to bind or cling more than the others; this is turned round until the cessation of the bind shews that the notch in the ring has been brought into its right position relatively to the pin on the rod. Then another ring which binds more than the rest is treated in a similar way; until at length all the rings seem to be so far liberated as to indicate that the notches are in the right positions. In the dial-lock, similarly, when a pressure has been brought to bear upon the bolt in the right direction, a trial of the pointers will soon bring the notch in each wheel to the required position.

Some short time after the events in London connected with the lock controversy, Mr. William Brown of Liverpool described the letter-lock noticed in a former page, characterising it as a lock which he believed no one could pick. An incident in the history of this lock was thus narrated in one of the Liverpool newspapers. "Mr. Hobbs was taken by Mr. Milner to the office of Messrs. Brown, Shipley, and Co., and shewn this lock. The safe-door was closed and locked by the cashier at Mr. Brown's request; and then Mr. Hobbs began to illustrate his views of the construction of the lock by manipulation and explanation, with which the subject of them appeared to sympathise so entirely and promptly that the door opened in a few minutes."

In respect to the picking of the Egyptian lock, the main difficulty would be in obtaining any false key that would correspond with the pins of the lock; but this might be accomplished in a way analogous to that which is practised in many other cases. If a small piece of wax be laid on a blank key, the key inserted into the lock, and the blank pressed upwards against the pin-holes, there would be left an impression of those holes on the wax; this impression would furnish a guide to the fabrication of a false key. There is also very little difficulty in picking this lock by one of the ordinary instruments.

For the Yale lock, combining something like the pin-action of the Egyptian with the cylinder-action of the Bramah locks, the picking requires the use of an instrument that will fit between two of the pins, and to the outer end of which is attached a lever and weight; by this means a pressure is exerted upon the cylinder in the right direction for it to turn, and the pins are made to bind. Then, with another instrument, the pins are felt, and each one moved until it seems to be relieved from the bind: this indicates that the joint in the pin coincides with the joint between the two cylinders; and when all have been similarly treated, the weight acting on the inner cylinder will turn it. It is evident that this method is the same in principle as the one applicable to the Bramah lock.

CHAPTER X.

EFFECTS OF THE GREAT EXHIBITION OF 1851 IN IMPROVING ENGLISH LOCKS.

We have now to refer to the effects of the lock controversy. It was no doubt annoying to be told, on good authority, that the machines on which we so much prided ourselves were wrong in principle; and that our locks, in order to afford the degree of security which are expected of such contrivances, must be re-constructed. The grumbling with which the first part of this proposition was received would alone have sufficed to lead to a suspicion of its truth, if the large number of new locks that have actually appeared had not confirmed it. Whether the second part of the proposition has been fairly carried out, is a point which must now be considered.

One of the first locks produced during or immediately after the lock controversy was Mr. Parnell's, to which the bold term

of *patent defiance lock* is attached. This lock is said to depend for its security on a mode of arrangement which may best be described in the inventor's own words: "Viewing the lock from its exterior, it presents nothing remarkable; but, upon removing the plate, it will be seen that all possible access to the mechanism with false or surreptitious keys is effectually prevented by a solid cylinder of *hardened* [?] brass, with protecting wards extending the whole depth of the lock, and having in the centre the aperture for the key, which fits to a mathematical nicety so exact as to preclude the possibility of any second instrument being used to open it. . . . . This protecting cylinder must revolve with the key to get to the works; and the moment it passes from the key-hole in going round to lock or unlock, the solid portion moves into its place, and so completely closes that aperture that the point of a pin, or a fine steel-pen, has failed to be inserted between it and the onter plate or cap, to say nothing of the utter hopelessness of perforating the metal."

The cylinder or protecting cap, though it revolves by the action of the key somewhat in the same way as the cylinder of the Bramah lock, appears to be intended rather for closing or protecting the key-hole than for governing the movements of the bolt. The internal arrangements of the lock are as follow: Supposing the bolt to be shot, and to be about to be unlocked, the key, by the time it has made about one-third of a rotation, meets with a forcible resistance in the shape of an upright spring-bolt or detector of strong steel acting on the revolving cylinder. The key passes this detector, and arrives at the levers or tumblers. In the bolt-stud which works in the slot of these tumblers there is a small deep serrated notch on one side, corresponding to similar notches on each of the tumblers; if, therefore, the bolt be forced, these notches would lock into each other in a similar manner to the catch on a ship's windlass or a hoisting crane. There is also a double-action tumbler-bolt, so adjusted, that if any of the tumblers be overlifted, this little appendage becomes thrust down at one end into the bolt of the lock, where it

wedges all fast until the tumblers become properly re-adjusted. The double-action tumbler-bolt also falls into the lock-bolt when the latter is locked or shut, thereby imparting an additional strength to the lock. The key has a power of expansion or enlargement while turning in the lock; it meets with an eccentric plate which draws out the bits somewhat; so that, at the moment of acting on the tumblers, they protrude farther from the pipe of the key than when the key entered the key-hole. The key is, in fact, larger when in than when out of the lock. There is connected with the works of the lock a 'detention-cap,' so formed that, in the event of a false key being used, a powerful bolt instantly locks into the revolving cylinder, and holds fast the surreptitious instrument." Such is, in substance, the account which Mr. Parnell has given of his own lock. It must, however, be stated, that the points of security or novelty claimed by Mr. Parnell for his lock were patented by previous inventors. The revolving cylinder or curtain was claimed by Mitchell and Lawton in the patent of 7th March, 1815, as noticed at page 52 *ante*. The expanding key-bit was claimed by Mr. Machin of Wolverhampton in 1827, as noticed at page 61, and by Mr. Mackinnon (page 62); while the serrated notches in the tumbler were used by many lock-makers long before the date of Mr. Parnell's patent. The detention-cap for catching and holding a false key when put into the lock was also patented by Mitchell and Lawton, as noticed at page 53 *ante*.

We come now to notice a lock lately invented by Mr. E. B. Denison (the author of the *Rudimentary Treatise on Clocks* in this series), which has the merit of combining considerable novelty in construction with security. After the details given in the two preceding chapters, it will certainly be no small praise when we express our conviction that in the present state of the art of lock-picking, this lock may be considered as secure. Mr. Denison has furnished us with a description of his lock, which we insert almost in his own words. Mr. Denison claims for this lock the following advantages:—

1. That a very large and strong lock on this construction only requires a very small key. 2. That no key is required to lock it, although it is free from the inconvenience pertaining to spring-locks, viz. that the door cannot be shut without locking itself. Moreover this lock is more secure than any spring-lock can be. 3. That it cannot get out of order from the usual causes of the tumblers sticking together or their springs breaking, inasmuch as the action of the tumblers does not depend on any thing but the key and the handle, and there are no tumbler-springs. 4. That for the same reason, the parts of this lock do not require any polishing or delicacy of execution. 5. That the key-hole being completely closed by a curtain, except when the key is in, the lock is protected from the effects of the atmosphere and dust entering at the key-hole. 6. That this lock is secure against any known mode of picking; the smallness of the key-hole prevents the insertion of any instrument strong enough to open the lock by violence. 7. That this lock, from the simplicity of its construction, admits of being made at small cost.

These objects are accomplished as follows:—In the large-sized locks, such as would be used for safes and large doors, the tumblers T, fig. 51, are made of pieces of hoop-iron, 6 or 7 inches long and 1½ inch wide: these tumblers are supported by and turn on a pin *a*, placed at about the middle of their length; so that being balanced on the pin, or nearly so, and having their separating plates P between them, which cannot turn, the tumblers will stand in any position indifferently; and in order to secure sufficient friction to keep them steady, one or more of the separating plates P is bent a little, so as to act as a spring when the cap of the lock is screwed down. The lock is shewn in fig. 51 as locked, the bolt B having been shot by the fan-tailed piece *f* on the handle, and the tumblers sent down, so that the stump *s* cannot enter their jaws by the other piece of the handle; and it is evident that the handle cannot draw the bolt back again until the tumblers have all been raised by the key to the proper position to allow the stump *s* to enter their

jaws. It will be observed that in the position shewn in the figure, the stump does not touch the tumblers; and consequently, so long as the bolt is kept in the position represented, no pressure of the stump against the tumblers can be felt, although by means of a false key or pick-lock the tumblers be raised to any height. No implement, however, can be pushed into the key-hole without first pressing in the curtain K, which is held up against the cap of the lock by the two spiral springs *c c* on each side of the key-hole; and at the back of the curtain there is a square plug *p*, which goes through a hole in the back of the lock, and has a notch in it through which the bolt can pass when the curtain is up, closing the key-hole, but at no other time. In other words, the act of pushing in the key sends down the curtain plug, the effect of which is to hold the bolt fast in the position in which the stump cannot be made to touch the tumblers. If the proper key be used and turned about half round to the right, it will bring the tumblers to the proper height for the stump to pass. The key is then taken



fig. 51. Mr. Denison's large lock.

out; for so long as it is in the lock, the bolt cannot be moved; and then turning the handle to the right, the bolt is drawn and the door opened.

The handle H should be so made, that as soon as the fan-

tailed piece *f* has sent the bolt just clear of the tumblers, the other arm to the right of H may begin to move the tumblers; but the fantail need not send the stump above one-sixteenth of an inch beyond the tumblers; and the curtain-plug and bolt must be so adjusted that the curtain cannot be pushed in until the bolt is so far out that the stump is this one-sixteenth of an inch beyond the tumblers. The curtain K need only be a thin piece of steel, and the bolt B must be thick enough for the curtain to go down just to the level of the thin plate P between the bolt and the first tumbler T. The curtain-plug *p* is made as long as the key-hole and rather broader, and of the shape represented, partly for the sake of steadiness in pushing in the curtain, and also for more completely protecting the key-hole; for if an attempt be made to pick the lock by drilling into the key-hole, the drill will pass into the inside of the door and not into the inside of the lock.*

It is true that iron safes have been made for some years in which any number of large bolts are shot by a handle and then locked by a very small key. But in such locks the key must be used in locking, and this leads to certain objections, viz. the key must occasionally at least be confided to some person whose duty it is to lock up the safe after the owner has left the place; there is also the temptation to leave the key in the lock, since it will be wanted in locking up; and thus there is the danger of some dishonest person taking an impression of the key. Besides this, the real strength and security of such safes is only that due to the small lock which locks into the main bolt; whereas in Mr. Denison's lock the security and strength are those due to the lock itself, with its large and

* Mr. Denison informs us that there is a further contrivance, which he will explain privately to any persons who wish to manufacture these locks, of which the object is, not to add any thing to the security of the lock under ordinary circumstances, but to provide against the unusual case of a very dexterous thief having occasional access to the lock when open; in which case (but for some such further provision) he might manage to construct a false key capable of opening the lock at any other time, by a method which, for obvious reasons, it is not advisable to publish.

strong tumblers, and other provisions peculiar to its construction; and the key for a lock of the largest size, which was lately exhibited at the Society of Arts by Messrs. S. Mordan and Co., the makers, only weighs a little more than a quarter of an ounce. It may be mentioned that for large locks the key may be solid, although in the small ones it is more convenient to have a pipe-key, on account of the different construction of the curtain.

The arrangement of the small lock for drawers, &c. is somewhat different from that of the large ones, and will be understood by referring to fig. 52. The action of the handle



fig. 52. Mr. Denison's small lock.

H on the bolt B and on the tumblers T is sufficiently clear from the figure. The curtain in this case has no plug, but is only a flat plate held up by a thin spring behind it, and moving up and down on the drill-pin of the key, and kept from turning by having one edge against the side of the lock. The bolt has a kind of second stump, only coming up so high as to be able just to pass under the corner of the curtain when it is up, but not able to pass when the curtain is at all pressed down by any thing inserted in the key-hole. In a drawer lock the key has only to be turned a quarter round in order to raise the tumblers. In small locks, the friction of the tumbler-plates is

quite enough to keep them in any position, without putting the pin in the middle so as to balance them, as in large locks with heavy tumblers.

In the making of these locks the key must be made first, with proper provisions to prevent the repetition of the same pattern; a kind of pattern or model for locks of each size should be made; the tumblers put on the pin with plates of the intended thickness between, and when raised by the key to the proper height they should be clamped down; and the jaws for the stump of the bolt may then be cut by a circular saw moving in a slit in the model corresponding to the place of the stump. The tumblers for large locks may be cut off from a strip of hoop-iron to the proper lengths by a stamping cutter, giving them the proper circular end, and a punch might at the same time make the pin-hole in the middle. The tumblers for small locks should be stamped out of sheet brass or iron.

It will thus be evident that from the general simplicity of construction, and the small amount of finish required in the working parts, this lock can be made at small cost. We may also add that this lock is as creditable to the public spirit as to the mechanical skill of the inventor; for the lock is not patented, patents being, in Mr. Denison's estimation, obstructions to the progress of science.

The next result of the "lock controversy" which we have to notice is the production of not less than three improved locks by Messrs. Chubb. We thought it our duty to invite the attention of this celebrated firm to the preparation of this *Rudimentary Treatise*, and in answer to the application of our publisher we received the following communication from Messrs. Chubb, which we insert verbatim:—

"It will not be necessary to describe the lock as originally made, as a description of it will be found in Mr. Chubb's paper read before the Institution of Civil Engineers.

"Lock No. 1.—The first of the improvements introduced consists of a barrel, to which a circular curtain is attached, revolving round the drill-pin in the lock; so that if any instru-

ment is introduced to attempt to pick it, the curtain immediately closes up the key-hole, and prevents the introduction of any auxiliary instruments, there being several required in action at once to produce any effect.

"If by any means these several instruments can be introduced simultaneously, the barrel keeps them all confined in a very small space, preventing their expansion, and renders it impossible to work them independently of each other; therefore they are of no avail, being incapable of acting as more than a single pick, which is perfectly useless. The barrel and curtain have each been previously used *separately* in locks, but until patented by Mr. De la Fons in 1846 they had not been used *in combination*. Neither of them, used separately, is of much use, but when combined they afford a very great security. Locks have been, and still are shewn, containing either the barrel or curtain *singly*, and as these have been picked, it has been asserted that the improvement now introduced in Chubb's lock is equally insecure; but a slight examination of the difference in their construction will prove the contrary. Mr. Chubb has purchased the patent-right of this part of Mr. De la Fons' invention, and applies it to all his locks.

"Lock No. 2.—The next improvement, recently patented by Mr. Chubb, is based upon the assumption that there may be a possibility of overcoming the security of the barrel and curtain as already described (although this assumption is not in the slightest degree admitted), and consists in applying what is called a 'tumbler-bolt,' working on a hinge connected with the main bolt. The web of the key does not in any case touch the main bolt in unlocking, but acts only on the tumbler-bolt. All the tumblers must first be lifted, each to its proper position, before the tumbler-bolt will act. Should any pressure be applied to either bolt before the tumblers are all at their exact position, the effect would be to throw the bolts out of gear, and thus effectually to stop the stump of the main bolt from passing through the racks of the tumblers. None of the many plans of picking which have been suggested, such as smoked key-blanks,

thin key-bits, &c., would be of the least avail against a lock made on this principle. Different kinds of detectors may he applied to these locks. It is submitted that this lock, retaining all the simplicity and durability which have distinguished Chubb's lock for so many years, and combining with them these important improvements, affords a complete security against all surreptitious attempts of any nature. Locks on the same principle are being made on the permutation plan, with any number of tumblers, and any number of changes in combination that may he desired.

"It has been suggested that the 'detector,' instead of giving additional security to Chubb's lock, affords a partial guidance to a person attempting to pick it. This objection holds good to a certain extent in these locks as originally made, in which all the tumblers had an *equal* bearing against the detector-stump; hut in the locks as now constructed this objection is entirely obviated, by giving the tumblers an *unequal* bearing, whereby, if an operator feels the obstruction of the detector-stump, he cannot tell whether the tumbler which he is lifting is raised too high, or not high enough.

"Lock No. 3.—For banks, Mr. Chubb has introduced what he particularly calls his 'bank lock.' It contains a barrel with a series of curtains. While the key-hole is open, all access to the tumblers from the key-hole is completely cut off by two sliding pieces of solid metal, which fit closely on either side of the barrel. These pieces are acted upon by an eccentric motion, so that when the key is applied to the lock, and turned in it, the key-hole is shut up by the revolution of the curtains, and then only do the sliding pieces of metal move aside to allow the key to act upon the tumblers. These pieces return to their position when the key has passed; therefore, while the key is lifting the tumblers, all communication is cut off from the exterior of the lock by these sliding pieces and the series of curtains. The bolt is made in two pieces, the main bolt never being in contact with the key, which acts only on the talon-bolt, and by it transmits the motion to the main bolt. After

the action of locking, the talon-bolt is partly repelled, and a lever or 'dog' connected with it locks into a series of combinations arranged upon the front parts of the tumblers, and holds them securely down, so that none of them can be lifted in the least degree until the talon-bolt is thrown forward to release them If, therefore, any pressure be applied to this talon-bolt, to endeavour by its help to ascertain the combinations of the tumblers, it will only the more tightly lock them down, and render the attempt ineffectual. By another contrivance it is rendered impracticable to move a pick or picks round in the lock more than a small distance, unless the tumblers could previously be all lifted to their right positions, which can only be done by the right key. Should one or more of the tumblers be surreptitiously raised by any possible means, they cannot be detained in this uplifted position, for the action of turning back the pick to try to raise another tumbler sets in motion a lever which allows the tumblers already raised to drop to their former position, leaving the operator just as far from the attainment of his object as at the outset."

Such is the statement with which Messrs. Chubb have favoured us respecting their three new locks. We are willing to admit the enterprising spirit which has led to their production, and the ingenuity which has been bestowed on their construction; but whether they mark a step in advance in the art of lock-making may perhaps admit of doubt. With respect to the lock No. 1, we would remark, that locks with the barrel and curtain combined were made by Mr. Aubin of Wolverhampton in 1833, and that a specimen of such a lock was exhibited on his stand of locks in the Great Exhibition. Locks with the combined barrel and curtain were also made and sold by Mr. Jones of Newark, N.J., as stated at p. 104.

With respect to the lock No. 2, the object of the *tumbler-bolt* is evidently intended to produce the same effect as the *movable stump* in Mr. Hobbs's protector-lock, fig. 47, page 100; but with greater complexity in the construction, there is less efficiency in the action of this part of Mr. Chubb's lock as

compared with that of Mr. Hobbs, inasmuch as a pressure of the stump against the tumblers, corresponding with the strength of the spring which holds the bolt in its place, can always be produced, thereby giving friction, and affording indication as to which tumbler it is that is in tight contact with the stump.

With respect to the barrel and curtains of lock No. 3, and all similar contrivances, the object of which is said to be to prevent the entrance into the key-hole of all instruments except the proper key, we would offer the self-evident remark, that the same aperture which admits the key will also admit some other instrument. In the case of Mr. Chubb's "bank-lock," it may be questioned whether the revolving curtain, &c. give it any advantage over the other locks already referred to which are furnished with similar contrivances. The effect of the *talon-bolt* in this lock appears to be the same as that of the false notches, namely, to hold the tumblers in the position in which they were placed when the pressure was applied. Hence, a pressure applied to the talon-bolt affects the parts which come in contact with the key in the act of locking and unlocking; and this circumstance brings the lock under the application of the principle stated at page 99, and thus, if this principle be admitted, may render the security of the lock somewhat questionable.

Various other locks have been brought out since the date of the "lock controversy" in the year 1851. We would gladly notice them all, did they shew novelty of design and mark an advance in the art of the locksmith. We must, however, admire the ingenuity with which Mr. Hobbs's movable stump has been more or less adopted; but in the attempts to imitate it the objection has not been removed, that it is possible to produce on the tumblers a pressure or friction equal to the strength of the spring which holds the tumblers down.

There is, however, a lock which has lately been introduced to the public, which calls for special notice, on account of the high honours which have been bestowed upon it. We refer to

the prize lock of the Society of Arts, London, the invention of Mr. H. J. Saxby of Sheerness, who has received the Society's medal and the sum of ten guineas as the reward of his ingenuity. The interior of this lock consists of a cylinder with four pins or slides radiating from the centre, and pressed into the key-hole by means of spiral springs. The pins project beyond the periphery of the wheel or cylinder, and into slots in a ring which is affixed to the case of the lock, thereby preventing the cylinder from being turned. On each pin is a notch, so placed that when the proper key is inserted into the key-hole, the notches on the several pins will be brought into a position such as will allow the cylinder to turn. The turning of the cylinder in this, as in the Bramah lock, shoots the bolt.

A lock on precisely the same principle, but more secure in its construction, was described by Mr. Hobbs in a paper read by him before the Society of Arts in January 1852, when diagrams illustrative of the same were exhibited. This paper was not reported at any length in the journal of the Society's proceedings; but the same paper was read by Mr. Hobbs, March 1, 1852, before the Liverpool Polytechnic Society, and a full report thereof, and a description of the lock in question, is given in the "Transactions" of that Society, from September 1849 to December 1852 (8vo, Liverpool, 1853). This lock is no other than the Yale lock already noticed at page 83, and is thus described at page 196 of the "Transactions:"

"Another description of cylinder-lock was invented, a few years since, by a Mr. Yale of the State of New York, U.S.A.

"The Yale lock has two cylinders, one working within the other; and they are held together by a series of pins reaching through the cylinders into the key-hole, which is in the centre. On the back of the inner cylinder is a pin that fits into a slot in the bolt, and moves it as the cylinder is turned. The pins that hold the cylinders together and prevent the inner one from turning, are cut in two at different lengths. The key is so made, that by inserting it into the key-hole the pins are moved, so that the joint in the pins meets the joint be-

tween the cylinders, and allows the inner one to be turned. But, as with the slides of the Bramah lock, should any one of the pins be pushed too far, the cylinder is held quite as firmly as though it had not been touched. Some of these locks have been made with as many as forty pins; and to a person unacquainted with the principles on which locks are picked, they would seem to present an insurmountable barrier.

"Figure 1* represents the case of the lock containing the bolt A, having a groove B, to receive the pin C on the cylinder. Figure 2 shews the cap or top-plate of the lock, and the cylinders; D D is the outer cylinder, that is stationary, being fastened to the plate; E E the inner or moving cylinder; F F the four rows of pins, being cut in two at different lengths, and reaching through the cylinders into the key-hole; G G are the springs that press the pins to their places; C the pin that fits into the groove and moves the bolt. Figure 3 is an end view of the key, shewing four grooves. Figure 4 is a side view, shewing the irregular surface of the grooves by which the pins are adjusted.

"For the purpose of picking the lock, an instrument is made that will fit between two of the pins; to that is attached a lever and weight, thereby getting a pressure on the cylinder and causing the pins to bind; then with another instrument the pins are felt, and as they are found to bind, they are pressed in until they are relieved (as they will be when the joint comes to the right place), thereby easily opening the lock. There is a great similarity in the operation and security of this and the lock manufactured by Mr. Cotterill of Birmingham."

In the *Society of Arts Journal* for the 24th June, 1853, is a letter from Mr. Hobbs on the subject of the prize lock, which, it appears, he picked, "in the presence of parties connected with the Society, in the short space of three minutes."

* This and the following figures refer to the diagrams exhibited by Mr. Hobbs.

CHAPTER XI.

THE LOCK AND KEY MANUFACTURE.

The manufacture of locks and keys, considered as a department of working in iron, is one that requires, and indeed admits of, very little description. The hammer, the file, the drill, the fly-press, are the chief instruments employed; the iron itself being brought to something like the desired state and form by rolling or casting, or both. But the manufacture is interesting in its social features—in its relation to the persons employed and the buildings occupied. One by one, several departments of industry have progressed from the *handicraft* to the *factory* system—from that system in which a man and a few apprentices work in a small shop in the lockmaker's garret or kitchen, to that in which organisation is maintained among twenty or fifty or a hundred men. Locks have scarcely yet passed out of the first stage, but there is no good reason whatever why they should so remain; there are as many reasons for progress in this as in other arts, and indications are not wanting that some such progress will be made.

So far as England is concerned, the neighbourhood of Wolverhampton is the great storehouse whence locks are obtained. Eminent lock-makers reside in London and in other principal towns; but Wolverhampton is regarded by all as the centre of the trade. This is not a modern localisation, for we have information respecting the locks of Wolverhampton a century and a quarter ago. Among the Harleian Manuscripts is an account of "The Voyage of Don Manuel Gonzales (late merchant), of the City of Lisbon in Portugal, to Great Britain: containing an Historical, Geographical, Topographical, Political, and Ecclesiastical Account of England and Scotland; with a Curious Collection of things particularly rare, both in Nature and Antiquity." This Ms. appears to have been writ-

ten about 1732; it was translated from the Portuguese, and printed in Pinkerton's Collection of Voyages and Travels. With reference to Wolverhampton, Gonzales says: "The chief manufacturers of this town are locksmiths, who are reckoned the most expert of that trade in England. They are so curious in this art, that they can contrive a lock so that if a servant be sent into the closet with the master-key, or their own, it will shew how many times that servant hath gone in at any distance of time, and how many times the lock has been shot for a whole year; some of them being made to discover five hundred or a thousand times. We are informed also that a very fine lock was made in this town, sold for 20*l.*, which had a set of chimes in it that would go at any hour the owner should think fit." If Gonzales were correct in these descriptions, they indicate an exercise of considerable ingenuity in lock-construction, especially in reference to the lock which keeps a registry of the number of times it has been opened. There is abundant evidence that the old lock-makers were very fond of these knick-knack locks, which would do all sorts of strange and unexpected things; and this may in part account for the great favour in which locks have been held by amateur machinists.

The lock-manufacture in South Staffordshire is of a remarkable character, comprised as it is within so small an area. Although Wolverhampton is known commercially as the chief depôt of the English lock trade, yet it is at Willenhall, three or four miles eastward of that town, that the actual manufacture is chiefly carried on. When the Commission was appointed a few years ago to inquire into the condition of children employed in trades and manufactures, Mr. R. H. Horne was deputed to examine the Wolverhampton district; and his report is too curious, and too closely connected with our present subject, to be passed unnoticed. We here give an abstract of such parts of his report as bear reference to the lock-makers of Willenhall.

Almost the entire industry of Willenhall is in the three

articles of currycombs, locks and keys, and articles connected incidentally with locks, such as bolts and latches. At the time Mr. Horne wrote, in 1841, there were among the master manufacturers 268 locksmiths, 76 key-makers, 14 bolt-makers, and 13 latch-makers; besides many small masters living in such out-of-the-way corners that they escaped enumeration. In the *Post-Office Directory* of that district, of later date, there are entries of rather a curious character. In the first place it is observable that different kinds of locks are made by different persons, each manufacturer confining his operations apparently to one kind of lock; one is a *rim-lock* maker, another a *trunk-lock* maker, a third a *cabinet-lock* maker, a fourth a *padlock* maker, a fifth a *mortice-lock* maker, and so on. But a much more singular feature is, that lock-making is combined with retail dealing of a totally different kind; thus among the occupations put down opposite the names of individuals are, "key-stamper and beer-retailer," "door-lock maker and beer-retailer," "grocer and trunk-lock maker," "Malt-Shovel tavern-keeper and rim-lock maker," "lock-maker and provision-dealer," "grocer and key-maker," "cabinet-lock maker and Woolpack tavern," "key-stamper and registrar of births, &c.," "Hope and Anchor and cabinet-lock maker," "auctioneer and locksmith," "rim-lock and varnish maker," and so forth. It is probable that in some of these cases the wife attends to the retail shop, while the husband attends to the workshop.

Among all the lock-manufacturers of the town there are scarcely half a dozen in what may be termed a large way of business; there are many who employ from five to fifteen pairs of hands, but the great majority are small masters who are themselves working mechanics, and are aided by apprentices from one to four in number, perhaps two on an average. Mr. Horne thinks that there were not fewer than a thousand boys at work in the town, chiefly upon locks and keys. The children and young persons are employed at all ages, from seven up to manhood; from the earliest age, indeed, in which they are able to hold a file. It is a characteristic fact, where so

many of the male inhabitants are employed at the bench from such early years, that a certain distortion of figure is observable; the right shoulder-blade becomes displaced and projects, and the right leg crooks and bends inwards at the knee, like the letter K,—it is the leg which is hindermost in standing at the vice. The right hand also has frequently a marked distortion. "Almost every thing it holds takes the position of the file. If the poor man carries a limp lettuce or a limper mackarel from Wolverhampton market, they are never dangled, but always held like the file. If he carry nothing, his right hand is in just the same position."

The hours of labour among the small masters are scarcely brought within any system at all; for all the work is piece-work, not paid for by the day or hour; and each man works as long as he likes, or as long as his business impels him. Some will file away from four or five in the morning till eleven or twelve at night. In the larger shops, where there are many hands employed, they come to work when they like, leave when they like, and do as much work as they like when there; this freedom of action being spread over a working-day of perhaps sixteen hours. The masters say that the men prefer this system, or want of system, to any thing more precise and regular. In the beginning of the week there is often much idleness and holiday-keeping; and the Willenhall men make up for this by a day of sixteen, eighteen, or even twenty hours' work towards the end of the week. In the beginning of the week, men and boys have defined hours and definite periods for meals; but towards the end of the week, when hurry and drive are the order of the day, they eat their meals while at work, and bolt their victuals standing. "You see a locksmith and his two apprentices, with a plate before each of them, heaped up (at the best of times, when they can get such things) with potatoes and lumps of something or other, but seldom meat, and a large slice of bread in one hand; your attention is called off for two minutes, and on turning round again, you see the man and boys filing at the vice."

In the processes as carried on at Willenhall, they are applied chiefly to the manufacture of mortice, hox, trunk, rim, cahinet, case, hright, dead, closet, and padlocks. Except some of the parts of the hrass-work, which are *cast*, these locks are made hy *forging*, *pressing*, and *filing*. The forging is a light kind of smith's work, aided by a light hammer and a small pair of bellows; children and young persons are largely employed in this process. Pressing is a kind of work hy which certain parts of the lock are pressed or stamped out. The presses are of various sizes, hut all require much strength to work them; the press has a horizontal lever, crossing the top of a vertical screw, and there is generally an iron weight at the end of each arm or half of the lever to increase the power; one of the lever arms is grasped in the right hand of the presser, and whirled round with a jerk; while the fingers of the left hand place the metal in its proper position, and remove it when it has been stamped or pressed. There is, of course, a die or cutter attached to the press, to cut the metal in the proper form. Sometimes the press has only one arm to the lever, and no weight at the end of this, so that the labour of working is much increased. Children and youths are employed at this process, so far as their strength will admit. The last process, *filing*, is that hy which the separate pieces are shaped and smoothed for adjustment in their proper places; here children and youths are almost exclusively employed; they stand upon hlocks so as to be ahle to reach the vice, and then work away with the file, unrelieved hy any change in the nature of the process.

In key-making the processes may be said to comprise *forging*, *stamping*, *piercing*, and *filing*. The forging differs very little from that required in making the pieces for a lock. The stamping is effected hy placing the end of an iron wire, taken red-hot from the forge, into one half of a key-mould made in a hlock or kind of anvil; a heavy weight is then raised hetween an upright framework, in the grooves of which it runs hy means of a cord; the cord is drawn hy both hands, with

the assistance of one foot in a stirrup attached to the end of the cord; at the bottom of the weight thus raised is the other half of the key-mould. Such being the nature of the stamping apparatus, the process is thus conducted: the foot in the stirrup being suddenly raised, and the cord loosed, the weight falls upon the red-hot wire, and the blow stamps it into the two moulds or half-moulds, which are brought accurately together by means of the slides or side-grooves in the framework. The rough key is also trimmed and cleared by the pressing apparatus; that is, the surplus metal all round is cut off by a single blow; and the metal which fills up the ring or handle of the key is cut or pressed out in the same way. This is a heavy part of the key-work, for which the labour of men rather than that of boys is required. The process of *piercing* the key consists in making the pipe or barrel, required for most keys, except those which are intended to open a lock for both sides; the pipe is drilled by a small machine worked with the foot like a lathe; it is a process requiring more skill than strength, relatively to other parts of the manufacture. The *filing* of a key is important; for not only is the whole key made bright, but the wards are cut by the file and chisel. Boys and youths are employed in filing the common keys; but those of better quality are entrusted to men.

The apprenticeship system is carried on to a remarkable extent among the lock and key makers of Willenhall. The small masters take apprentices at any age at which they can work. Some of them employ only apprentices, never paying wages for journeymen, but always taking on a new apprentice as soon as a former one is out of his time. The boys are mostly procured from other towns, and they bring with them a small apprenticeship-fee and a suit or two of clothes. They are bound to the masters by legal indenture or contract; and the masters board and lodge and clothe them during their apprenticeship. One consequence of this system is, that when the apprentice has served his time, he is almost driven to become a small master himself from want of employment as a jour-

neyman; and he then takes apprentices as his master did before him. This accounts for the fact that in Willenhall there are few large manufacturers and few journeymen; while there is a constantly-increasing number of small masters and of apprentices.

The Willenhall makers nearly all look to the Wolverhampton factors or dealers for a market for their wares—so far at least as concerns locks and keys; there are some other articles which they sell more frequently to Birmingham houses. The master and an apprentice, or perhaps two, generally trudge off to Wolverhampton on a Saturday, hearing the stock of locks which he may have to sell; and the money receipts for the locks or keys sold are usually in part spent at the large market of Wolverhampton previous to the homeward journey. The Willenhall men take contracts at so low a price as to prevent the competition of other places; it is stated, that whatever he prices elsewhere, nothing can come below the Willenhall prices for cheap locks. The men work hard for small returns, and yet they have a strong yearning for their own town. A Willenhall girl will seldom marry except to a townsman; and thus they intermarry to an extent which maintains their characteristics as a peculiar community. As an example of their disinclination to leave their own town, Mr. Horne states the following circumstance: "Some years ago a factor, who had projected a manufactory in Brussels, engaged some five-and-twenty Willenhall men, whom he was at the expense of taking over. He gave them all work, and from hard-earned wages of from 9*s.* to 15*s.* a-week, these 'practised hands' found themselves able to earn 3*l.* a-week and upwards. But they were not satisfied, and began to feel uncomfortable; first one left, and returned home; then another; then one or two; till, in the course of a few weeks, every man had returned to Willenhall"—there to work harder and earn less.

It is just possible that the application of the factory system to lock-making may first become important by making the *best* locks cheaper than they can be made by the handicraft method;

for there seems not much probability, at least for a great length of time to come, that any new system will be able to compete with Willenhall in the common locks—those of which more thousands are sold than there are tens of the better locks. In this, however, it would not do to predict rashly. Hand-loom weaving is cheap enough, unfortunately for those who practise it; but yet the factory system comes down as low as the lowest hand-loom weaving.

The editor of Hebert's *Encyclopædia*, after noticing the facilities for opening most locks by copying the key, makes the following announcement: "It affords the editor of this work much satisfaction to state, that he has in his possession a lock, the key of which *cannot be copied*, a locksmith possessing no tools by which an exactly similar one can be made; the machine by which the original one was made is so arranged as to be deprived of the power of producing another like it. The lock is very simple, very strong, and can be very cheaply made. The cost of a complete machine to make them would be about 100*l.*; with that they might be manufactured at one-half the expense of any patent lock. The inventor is desirous to have the subject brought before the public under a patent; but want of time to devote himself to such an object at present obliges him to lay it aside." The invention not being patented, the editor of course gave no diagram or engraving of the lock or machine; nor does there appear to have been a patent obtained during the sixteen or eighteen years which have elapsed since the above notice was published. There are, however, mechanical principles sufficiently well known to lead to a belief that such a machine is practicable; a ticket-printing or numbering machine will, in printing 100,000 tickets, produce such variations that no two impressions shall be identical; and a key-making machine might, after fashioning a particular part of each key, modify the arrangement of certain wheels and pinions so far as to produce a slightly different result when the next key is to be operated on.

In the manufacture of locks and keys generally, there is

no reason why the factory system should not, to a certain extent, be applicable. By this will be understood, the production of similar parts by tools or machines, graduated in respect to each other with more care than can be done by the hand method. If we suppose that a lock of particular construction comprises twenty screws and small pieces of metal, and that there are required, for general disposal in the market, five sizes of such a lock; there would thus be a hundred pieces of metal required for the series, each one differing, either in shape or size, from every one of the others. Now, on the factory or manufacturing system, as compared with the handicraft system, forging, drawing, casting, stamping, and punching, would supersede much of the filing; the drilling machine would supersede the drill-stock and bow, and other machines would supersede other hand-worked tools. This would be done—not merely because the work could be accomplished more quickly or more cheaply—but because an accuracy of adjustment would be attained, such as no hand-work could equal, unless it be such special work as would command a high rate of payment. For any one size in the series, and any one piece of metal in each size of lock, a standard would be obtained which could be copied to any extent, and all the copies would be like each other. To pursue our illustration, the manufacturer might have a hundred boxes or drawers, and might supply each with a hundred copies of the particular piece of metal to which it is appropriated, all so exactly alike that any one copy might be taken as well as any other. Ten pieces, one from each of ten of these boxes, would together form a lock; ten, one from each of another ten boxes, would form a second lock, and so on; and there would be, in the whole of the boxes, materials for a thousand locks of one construction, a hundred of each size.

Now the advantage of the machine or factory mode of producing such articles is this, that they can be made in large numbers at one time, whenever the steam-engine is at work; and that when so made, the pieces are shaped so exactly

alike, the screws have threads so identical, and the holes are bored so equal in diameter, that any one of a hundred copies would act precisely like all the others, thereby giving great advantages to the men employed in putting the lock together.

These principles are being applied by Messrs. Hobbs and Co. in their London establishment. A number of machines, worked by steam-power, are employed in shaping the several pieces of metal contained in a lock; and all the several pieces are deposited in labelled compartments, one to each kind of piece. The machines are employed — in some cases to do coarse work, which they can accomplish more quickly than it can be done by men; and in other cases to do delicate work, which they can accomplish more accurately than men; but so far is this from converting the men into lowly-paid automatons (as some might suppose), that the manufacturers are better able to pay good wages for the handicraft labour necessary in putting the locks together, than for forming the separate parts by hand; just as the "watchmaker," as he is called, who puts the separate parts of the watch together, is a better-paid mechanic than the man who is engaged in fabricating any particular parts of the watch.

It may be observed that the system of manufacturing on a large scale, by many men engaged in one large building, is more nearly universal in the United States than in England. The workshop system, as pursued at Willenhall by the lock-makers, is very little practised in America. Being comparatively a new community, and being at liberty to select for imitation or for improvement whichever of the usages or systems in the old country they may prefer, the Americans have preferred to adopt the factory system rather than the workshop system, and to carry out the former to an extent not yet equalled in England—not yet equalled, we mean, in the number of trades to which it is applied.

CHAPTER XII.

ENGLISH PATENTS FOR LOCKS—AUBIN'S LOCK TROPHY.

We propose to conclude this small work with a few details respecting the various patented inventions in locks, and concerning Mr. Aubin's remarkable lock trophy. These two subjects relate to locks in general, rather than to any specified constructions in particular, and can on that account more conveniently be given here than in connexion with any of the foregoing chapters.

Mr. Chubb, in the appendix to his paper on locks and keys read before the Institution of Civil Engineers, gave a useful list of all the patents taken out in England in relation to this subject, down to the year 1849. We here transcribe this list:

List of Patents for Locks and Latches granted since the Establishment of the Patent Laws.

"As no complete list of the patents granted for locks from the time of James I. has hitherto been published, it is believed that the following list, which has been very carefully drawn up, and which comprises all patents from the year 1774, when the first patent for a lock was granted, to the present time, will be found useful as a reference for all who are interested in the subject.

1774	May	27	Black, George, Berwick-on-Tweed.
,,	,,	,,	Barron, Robert, London
1778	May	29	Martin, Joshua Lover, Fleet street, London.
1779	May	28	Henry, Solomon, Swithin's-lane, London.
1780	March	4	Campion, J. Newcastle-court, Strand, London.
1782	January	18	Hutchinson, Samuel, Marylebone, London.
1784	,,		Bramah, Joseph, Piccadilly, London.
1789	July	7	Cornthwaite, Thomas, Kendal, Westmoreland.

1790	February	23	Rowntree, Thomas, Surrey-street, Blackfriars, London.
,,	October	29	Bird, Moses, Wardour-street, London.
1791	July	19	Ferryman, Rev. Robert, Gloucester.
,,	November	3	Antis, John, Fulneck, near Leeds.
1797	November	18	Langton, Daniel.
1798	May	3	Bramah, Joseph.
,,	December	8	Turner, Thomas.
1799	April	11	Davis, George.
1801	February	10	Scott, Richard, Lieut.-Colonel.
,,	June	24	Holemberg, Samuel, London.
,,			Roux, Albert, Switzerland.
1805	May	18	Stansbury, Abraham Ogier, New York.
,,	December	29	Thompson, William, Birmingham.
1815	March	7	Mitchell, William, Glasgow; and Lawton, John, London.
1816	May	14	Ruxton, Thomas, Esq., Dublin.
1817	February	8	Clark, William, Esq., Bath.
1818	February	3	Chubb, Jeremiah, Portsea.
1819	October	18	Strutt, Anthony Radford, Mackeney.
1820	April	11	Jennings, Henry Constantine, Esq., Middlesex.
,,	December	14	Mallett, William, Dublin.
1823	July	10	Fairbanks, Stephen, Middlesex.
,,	November	13	Ward, John, Middlesex.
1824	June	15	Chubb, Charles, Portsea.
1825	May	14	Young, John, Wolverhampton.
1828	May	17	Chubb, Charles, London.
1829	June	1	Gottlieb, Andrew, Middlesex.
1830	January	18	Carpenter, James, and Young, John, Wolverhampton.
,,	January	26	Arnold, John, Sheffield.
1831	April	14	Rutherford, William, Jedburgh, N.B.
,,	May	23	Barnard, George, Bristol.
,,	July	27	Young, John, Wolverhampton.
1832	December	20	Parsons, Thomas, London.
1833	December	3	Parsons, T., Newport, Salop.
,,	December	20	Chubb, Charles, London, and Hunter, E., Wolverhampton.
1834	September	6	Longfield, William, Otley.
,,	October	11	Audley, Lord Baron Stafford.
1835	March	18	Hill, R., Birmingham.
,,	December	16	Warwick, J., London.
1836	February	10	Fenton, Rev. S., Pembroke.
1838	June	30	Uzielli, M., London.
,,	November	13	Thompson, S., London.
1839	February	21	Uzielli, M., London.
,,	June	12	Sanders, J. Stafford.
,,	July	3	Cochrane, A., Strand, London.
,,	July	20	Schwiese, J. C., London.
,,	August	1	Williams, W. M., London.
,,	December	2	Guest, J., jun., Birmingham.
1840	February	27	Williams, W. M., London.
,,	March	20	Gorish, F. W.
,,	May	2	Pearse, W., Hoxton, Middlesex.
,,	June	13	Wolverson, J., and Rawlett, W., Stafford.
,,	October	22	Clark, T.
,,	December	23	Barlhe, B., London.
1841	March	29	Tildesley and Sanders, Willenhall and Wolverhampton.

1841	May	6	Hancock, James, Sidney-square, Mile End.
,,	July	14	Berry, Miles, Chancery-lane.
,,	September	28	Strong, Theodore Frederick, Goswell-road.
,,	November	9	Smith, Jesse, Wolverhampton.
1842	January	15	Poole, Moses, Lincoln's-inn
,,	May	24	Duce, Joseph, Wolverhampton.
,,	June	13	Williams, W. M , 163 Fenchurch-street.
,,	December	29	Rock, Joseph, jun., Birmingham.
1843	November	25	Tann, E. E. and J., Hackney-road.
,,	,,	,,	Rock, Joseph, jun., Birmingham.
1844	July	30	Fletcher, Rev. William, Moreton House, Buckingham.
1845	April	15	Carter, George, Willenhall.
,,	July	12	Ratcliff, Edmund, Birmingham.
,,	December	4	Poole, Moses, Lincoln's-inn.
,,	December	22	Smith, Philip, High-street, Lambeth.
1846	July	6	De la Fons, John Palmer, Carleton-hill, St. John's Wood.
,,	July	15	Thomas, William, Cheapside.
,,	December	14	Chubb, John, St. Paul's Churchyard.
1847	January	11	Chubb, John, and Hunter, Ebenezer, sen., St. Paul's Churchyard.
,,	April	15	Collett, Charles Minors, 62 Chancery-lane.
1848	September	28	Newall, Robert Stirling, Gateshead.
1849	May	8	Wilkes, Samuel, Wednesbury-heath, Wolverhampton.

Mr. Chubb also gave a list of such papers in the Transactions of the Society of Arts as refer to locks and keys.

List of References to the "Transactions of the Society of Arts," on the subject of Locks.

vol.	page.		vol.	page.	
1.	317	Mr. Moore.	38.	111	Mr. A. Ainger.
2.	187	,, Cornthwaite.	,,	205	,, Bramah.
3.	160	Marquis of Worcester.	42.	125	,, J. Duce.
,,	165	Mr. Taylor.	43.	114	,, W. Friend
,,	163	,, Marshall	45.	123	,, Machin.
18.	239	,, T. Arkwright.	48	132	,, S Mordan.
,,	243	,, Bullock	50.	86	,, A Mackinnon.
19.	290	,, W. Bullock.	51.	128	,, J. Meghan.
36.	111	,, M. Somerford.			

Among the most curious mechanical productions in the Great Exhibition of 1851, was one which attracted very little notice, viz. that forwarded by Mr. C. Aubin of Wolverhampton. Whether it was that attention, so far as regards locks, was too much absorbed by the "lock controversy," or whether there was a deficiency of descriptive cataloguing, no juror or newspaper critic, as far as we are aware, took notice of the production in question. In the *Official Illustrated Catalogue* it is entered simply as "Specimens to illustrate the rise and pro-

gress of the art of making locks, containing forty-four different movements by the most celebrated inventors in the lock trade." This trophy of lock ingenuity (for such it may be justly considered to be) is now in the possession of Mr. Hobbs. Springing from a hexagonal base-piece is a central axis, about three feet in height, supporting four horizontal circular discs, placed at different parts of its height. Each of the vertical faces of the base-piece contains a lock, which is worked by its respective key. Each disc contains a number of locks: 16 on the lowest, 12 on the next above, 9 on the third in height, while a Bramah lock surmounts the whole. All the locks on the discs are so arranged that their bolts shoot outwards, or radially away from the axis of the machine. Every lock has its own proper key inserted in the key-hole; and as the locks lie down horizontally, the shaft of each key is of course vertical. There are delicate pieces of mechanism contained within the central axis and within the discs, consisting of levers, racks, and pinions; and the Bramah lock is contrived so ingeniously, that the Bramah key, by acting upon that lock, acts upon all this mechanism. The Bramah barrel, in rotating horizontally under the action of its key, gives a rotary movement to a rod passing vertically through the centre of the whole apparatus; this rod, at the levels of the several discs, acts upon racks and pinions, and these in turn act upon the key-pins of the several locks. When, therefore, the Bramah key is turned, the whole of these key-pins rotate, each exactly in the same way as if the lock were being closed or opened, and the bolts shoot in or out accordingly. The Bramah key, although it acts as a master-key, is not such as usually obtains that designation; it is simply a means of putting in action certain rack-and-pinion mechanism, which does not belong to lock-work considered *per se*. All the locks are faithful representatives of the several patents or modes of construction to which they severally refer; and each exhibits the works sufficiently open to display the principle on which it is arranged. Each lock is numbered, and is referred to in an accompanying description. The works are finished with

the utmost care and polish; and the trophy being somewhat tastefully arranged, and kept under a glass shade, forms a really elegant specimen of mechanical skill.

For an account of the locks themselves which constitute this trophy, we cannot do better than avail ourselves of the description given in the article "Lock" in Tomlinson's *Cyclopædia of Useful Arts*, adding a few further details in respect to some of the locks of the series. The locks are arranged and numbered according to their similarity of construction; and it is instructive to remark the evidence here afforded, that many patentees would have saved much time and money if they had better known the productions of their predecessors. In describing these locks we shall do so briefly, sufficient to shew their relative principles of construction; many of them having been described more or less fully in former chapters.

No. 1 on the list is called a *Roman lock;* it consists of a single bolt, with a binder-spring for holding the bolt in any position in which it may be placed until a sufficient force is applied to overcome it: it embodies the simple principle on which thousands of common locks are annually made.

No. 2, called a *French lock* (all such designations are of rather doubtful correctness), resembling No. 1 in every thing except having the addition of a friction-roller. The bolt of either of these two locks can easily be forced back by pressing on the end.

No. 3 is marked *Ancient;* it is a bolt-lock, and was found in an ancient building. It exhibits an improvement on both the former specimens, in so far as the bolt requires, before it can be shot, to be pressed down, in order to release it from a catch at the back end of the bolt; this release cannot be effected without the aid of a key or some other implement applied through the key-hole, and thus the bolt answers the purpose both of bolt and tumbler.

No. 4, also marked *Ancient*, is in principle a single-acting tumbler-lock; that is, one in which the tumbler may fail to be lifted high enough, but cannot be raised too high, to release the bolt: whereas a double-acting tumbler, being susceptible

both of too much and too little ascent, must be raised to one definite and precise height to attain the required object.

No. 5, an *old English lock*, exhibits a great advance in principle, being provided with the double-action just described as being wanting in No. 4.

No. 6, *modern English* (no maker's name), is a single-acting tumbler-lock.

No. 7, by *Mace*, is a double-acting tumbler, but without exhibiting any peculiarities of construction.

No. 8 is *Somerford's first patent*. It is a double-acting *draw* tumbler-lock; that is, there is a tumbler which is drawn down instead of being lifted, as in most locks.

No. 9, designated, we know not on what grounds, an *Indian* lock, has a single-acting tumbler with a pin.

No. 10, patented by Thompson in 1805. In this lock there are two tumblers, one of which is single and the other double-acting.

Next follow a considerable number of locks, which differ one from another too slightly to render any formal description necessary. No 11, by *Daniells*, is a single-acting tumbler, differing only in form from those previously used. No. 12 is by *Walton*. No. 13 is *Barron's* first patent, taken out in 1774. No. 14 is by *Bickerton*. No. 15 is a *Dutch* lock. No. 16 is by *Duce*, senior. No. 17, by *Sanders*, is a lock with four double-acting tumblers. No. 18, patented by *Cornthwaite* in 1789, is so nearly like Sanders's, brought before public notice in 1839, as to corroborate what we have said concerning the identity, or at least close resemblance, of inventions widely asunder in point of time. No. 19 is by *Richards and Peers*.

No. 20 is *Somerford's* second patent; a lock which seems to embody the principle of Mr. Tann's "reliance-wards," patented many years later. No. 21 is *Rowntree's* lock, patented in 1790. No. 22 is the first patent lock of *Duce*, junior, dated 1823. No. 23 is *Parsons'* first patent, of 1832. No. 24 is *Bickerton's* second. No. 25, patented by *Price* in 1774; this, so far as at present appears, was the first lock ever constructed

with four double-acting tumblers, bearing a closer resemblance than would generally be supposed to those patented by other persons in more recent years. No. 26 exhibits a somewhat similar coincidence. It was introduced by Aubin in 1830, and is furnished with a *revolving curtain* for the purpose of closing the key-hole during the revolution of the key. Other inventors have since then adopted the revolving curtain; and in a patent taken out so recently as 1852, this appendage is claimed as part of the patent.

No. 27 is *Barron's* second patent, dated 1778; a lock which has perhaps been the model for a larger manufacture of plain simple tumbler-locks than any other. No. 28 is by *Bird*, 1790. No. 29 is the second patent of *Duce*, junior. No. 30 is *Ruxton's*, 1818. No. 31 is *Chubb's* simplified lock, 1834. No. 32 is by *Marr*. No. 33, by *Tann*, is the "reliance-ward" lock adverted to above as having been anticipated, in respect to its leading principle, by *Somerford's* second patent. No. 34 is by *Hunter*, 1833. No. 35 is *Parsons'* second patent, of the same year. No. 36 is by *Lang*, 1830. No. 37 is *Lawton's*, dated 1815. No. 38, patented by *Strutt* in 1839, has an arrangement for holding the tumblers, in the event of a pressure being applied to the bolt; an arrangement bearing a considerable resemblance to one recently adopted in Chubb's bankers' lock. No. 39 is by *Scott*, 1815. No. 40, *Chubb's* patent of 1818, is the original detector-lock of this maker. Most of the detectors since patented by various persons are little other than variations of Chubb's original.

No. 41, *Parsons'* third patent of 1833, is a *changeable* lock of peculiar construction. The elevation of the tumblers is regulated by an adjusting-screw passing through the lock to the inside of the door; this screw changes the positive but not the relative positions of the tumblers; so that the same difference in the steps of the key must be retained, the change being made only in the length of the bit: the number of changes for each lock is very limited.

No. 42, invented by *Pierce* in 1840, seems to be a carrying

ont of the plan suggested hy the Marquis of Worcester in his *Century of Inventions*, where he says that "a lock may be so constructed that if a stranger attempteth to open it, it catches his hand as a trap catcheth a fox; though far from maiming him for life, yet marketh him so, that if once suspected he might easily be detected." In Pierce's lock a steel barh or sharp arrow-head is concealed helow the key-hole, in such a manner that if any person in attempting to open the lock should over-lift the tumbler, the barb would be thrust hy a spring into his hand. It is said that the patentee himself experienced the efficacy of this invention, by receiving the harb into his own hand.

No. 43, by *Ruxton*, patented in 1816, is furnished with a tell-tale, so arranged that if the tumbler be over-lifted in an attempt to pick the lock, a pin or catch is thrown out from the lock, which would he visible on opening the lock with the proper key. This invention preceded Chubb's detector hy two years, and would he entitled to some of the honours of originality were not Chubb's arrangement much more simple and effective.

No. 44 is *Bramah's*, the patent of 1784, and the crowning lock of the trophy, by which all the others are opened. Similar locks hy *Russell* and *Mordan* are applications of the Bramah principle, with little or no variation.

In concluding this small work we would remark that no attempt has been made to describe every variety of lock that has heen introdnced. Several forms of puzzle locks, known as *Russian* and *Chinese locks*, have the forms of various animals, and they are locked and unlocked by pressing upon or moving some portion of the body of the animal: the security of such locks depends in many cases npon keeping the part to he pressed or moved secret. There are also various forms of alarum locks; but these do not greatly differ from common locks, except in having certain appendages, such as a pistol,

Google

which if loaded and properly adjusted, will be fired on any attempt being made to open the lock, either with its own key or some other instrument. Some locks are furnished with a bell or a rattle, which is rung or sprung on attempting to open the lock, and in this way the inmates of the house are informed of the attempt to effect an entrance. It will, however, be evident to any one who has read the preceding pages, that devices of this kind do not add to the security of the lock: they rather tend to degrade the art of the locksmith to that of the toyman. The locksmith, in common with every other artist, can only improve in his art by studying the principles upon which it rests, and illustrating them by the most approved examples which the constructive genius of his predecessors or contemporaries has furnished.

Robson, Levey, and Franklyn, Great New Street and Fetter Lane

In justice to Mr. Smyth, I have inserted in this Re-issue the following:—J. W.

THE BRAMAH LOCKS.

124, Piccadilly, London.

Sir,—Referring to my letter in your "Rudimentary Treatise on Locks, page 130-31," I shall be obliged by your adding, in any future edition of the work, the following facts—

Holding the Bramah Locks to be unpickable, (if properly made), I did not deem it necessary in my communication to you, to do more than point out the fatal defects of the one operated upon; those defects being the sole reason of the lock yielding to the operator, even on the sixteenth day of his exertions. Had the least doubt existed as to the perfect security of the Bramah Locks, as now made, alterations that suggested themselves after the late operations, would have been introduced and patented; but when it is proved that the lock which was tested, (made forty years since), was without those improvements which have for years been used in the Bramah Locks; and bearing in mind that the lock in question occupied the first lock-picker (perhaps) in the world, sixteen days to open, it has not been considered necessary to introduce alterations which would increase the cost to the public of locks admitted, and proved to be secure. In proof of this assertion, I may mention amongst others, that Mr. Hobbs' best workman failed in picking an ordinary 3-inch Bramah Box Lock; and that a person in the employ of Messrs. Johnson & Ravey, of Conduit Street, failed also in his attempt to pick a 6-inch Bramah Cellar-door Lock, though he had, (as

Digitized by Google

Mr. Ravey informed me the other day), the lock in his possession for twelve months, employing his evenings in making instruments and trying to pick it.

I give the most decided contradiction to the statement in the book, that the new lock was removed from the window through any fear of its being opened. It was put up especially to afford an opportunity for Mr. Hobbs to make, if he thought fit, another trial. The same reward, (200 guineas) was attached. It remained in the window four months, and the sole cause of its removal, was to stop the impertinent applications of men and boys, which interfered too much with our general business.

I am, Sir,

Your obedient Servant,

JOHN SMYTH.

To John Weale, Esq., 59, High Holborn.

CATALOGUE

OF

RUDIMENTARY,

EDUCATIONAL, SCIENTIFIC, AND CLASSICAL

WORKS

FOR

COLLEGES, HIGH AND ORDINARY SCHOOLS, AND SELF-INSTRUCTION;

TOGETHER WITH

A LIST OF WORKS ON PRACTICAL SCIENCE.

DESIGNED TO PROMOTE THE OBJECTS OF

MECHANIC INSTITUTES,
LITERARY AND SCIENTIFIC ASSOCIATIONS,
BOROUGH AND CITY FREE LIBRARIES,
OF STUDENTS GENERALLY.

JOHN WEALE, 59, HIGH HOLBORN,
LONDON.
1858-9.

DRAWING BOOKS

For Students' use in Schools, Mechanics' Institutions, and others, desiring to acquire a superior method of Drawing and Shadowing, as practised in the best Schools of France.

COURS ELEMENTAIRES de LAVIS appliqué à L'ARCHITECTURE; folio volume, containing 50 elaborately engraved plates, in shadows and tints, very finely executed by the best artists of France, price 2*l.* 10*s.* *Paris.*

COURS ELEMENTAIRES de LAVIS appliqué à ORNEMENTATION; folio volume, containing 50 elaborately engraved plates, in shadows and tints, very finely executed by the best artists of France, price 2*l.* 10*s.* *Paris.*

ETUDES PROGRESSIVES ET COMPLETES D'ARCHITECTURE de Lavis par J. B Tripon; large folio, 24 fine plates, comprising the Orders of Architecture, mouldings with profiles, ornaments, and forms of their proportion, art of shadowing, doors, balusters, parterres, &c. &c. &c., price 1*l.* 4*s.* *Paris.*

In 4to., with 14 plates, in half cloth, boards, price 7*s.* 6*d.*

PRACTICAL RULES ON DRAWING FOR THE OPERATIVE BUILDER AND YOUNG STUDENT in Architecture.

1. Practical Rules on Drawing, Outlines.
2. Practical Rules on Drawing, the Grecian and Roman Orders.
3. Practical Rules on Light and Shade.
4. Practical Rules on Colour, &c. &c.

In 4to., boards, 8 plates, and 76 woodcuts, price 6*s.*

ARCHITECTURE OF MACHINERY. An Essay on Propriety of Form and Proportion. Intended as a guide to assist the Student in the Drawing and Designing of Machinery. For the use of Students and Schoolmasters.

MR. WEALE'S

SERIES OF RUDIMENTARY WORKS.

MR. WEALE has prepared for publication, in a neat and convenient size, a series of original and useful Volumes, by the most esteemed writers, forming a Rudimentary Course for the easy comprehension of the leading principles of various Sciences.

It has been remarked that "those who are in the ship of Science ought to remember that the disciples cannot arrive without the aid of boats." Popular Treatises are to Science what boats are to large ships: they assist people in getting aboard. But as no one would trust himself to a weak and inefficient boat, as no one ought to begin the study of Science with an imperfect guide. It sometimes happens that popular treatises are made to appear easy by the omission of those very details which are most essential to be known: they state results without going through the necessary processes by which those results are gained: they deal largely in facts, and leave principles untouched

The only method of avoiding this error is to confide to men who are masters of their respective subjects the task of drawing up Popular Introductions to the several branches of Science, as well as uniting elementary principles with practical applications. The Publisher trusts that the following list of names will be a sufficient guarantee to the Public that what he proposes to attempt in the cause of Popular Instruction will be done well; and that these little treatises will fully answer the purposes for which they are intended, namely, to become convenient and accurate Guide-Books to Popular Institutions generally, while their low price will place them within the reach of all classes earning their daily bread, to many of whom a knowledge of the elements, together with the practice, of the Sciences are positive gains in the common pursuits of life, as well as a means of winning from gross tastes, and presenting to the mind noble and worthy objects of study. The series, also, is extended to the Elemental and Practical Science of Mathematics, for those who desire to advance and perfect their studies. Together with an Educational Series. The whole in demy 12mo., as follows:

1. CHEMISTRY, by Prof. Fownes, F.R.S., including Agricultural Chemistry, for the use of Farmers. 4th edition . . . . . 1*s.*
2. NATURAL PHILOSOPHY, by Charles Tomlinson. 3rd edition . . 1*s.*
3. GEOLOGY, by Col. Portlock, F.R.S., &c. 3rd edition . . 1*s.* 6*d.*
4, 5. MINERALOGY, with Mr. Dana's additions, 2 vols. in 1. 2nd edition 2*s.*

6. MECHANICS, by Charles Tomlinson. 4th edition . . . . . 1s.
7. ELECTRICITY, by Sir William Snow Harris, F.R.S. 3rd edition 1s. 6d.
7*. GALVANISM ANIMAL AND VOLTAIC ELECTRICITY Treatise on the General Principles of Galvanic Science, by the same 1s. 6d.
8, 9, 10. MAGNETISM, Concise Exposition of, by the same, 3 vols. . 3s. 6d.
11, 11*. ELECTRIC TELEGRAPH, History of the, by B. Highton, C. E., double Part . . . . . 2s.
12. PNEUMATICS, by Charles Tomlinson. 2nd edition . . . . . 1s.
13, 14, 15 CIVIL ENGINEERING, by Henry Law, C.E., 3 vols.; and 15* Supplement . . . . . 4s. 6d.
16. ARCHITECTURE (Orders of), by W. H. Leeds. 2nd edition . . 1s.
17. ARCHITECTURE (Styles of), by T. Bury, Architect. 2nd edition, with additional cuts . . . . . 1s. 6d.
18, 19. ARCHITECTURE (Principles of Design in), by E. L. Garbett, Architect, 2 vols. . . . . 2s.
20, 21. PERSPECTIVE, by G. Pyne, Artist, 2 vols. 3rd edition . . . 2s.
22. BUILDING, Art of, by E. Dobson, C.E. 2nd edition . . . . . 1s.
23, 24. BRICK-MAKING, TILE-MAKING, &c., Art of, by the same, 2 vols. . . . . 2s.
25, 26. MASONRY AND STONE-CUTTING, Art of, by the same, with illustrations . . . . . 2s.
27, 28. PAINTING, Art of, or a GRAMMAR OF COLOURING, by George Field, 2 vols. 2nd edition . . . . . 2s.
29. DRAINING DISTRICTS AND LANDS, Art of, by G. D. Dempsey, C. E. 2nd edition . . . . . 1s.
30. DRAINING AND SEWAGE OF TOWNS AND BUILDINGS, Art of, by the same. 2nd edition . . . . . 1s. 6d.
31. WELL-SINKING AND BORING, Art of, by G. R. Burnell, C. E. 2nd edition . . . . . 1s.
32. USE OF INSTRUMENTS, Art of the, by J. F. Heather, M. A. 3rd edition . . . . . 1s.
33. CONSTRUCTING CRANES, Art of, by J. Glynn, F.R.S., C.E. 2nd edition . . . . . 1s.
34. STEAM ENGINE, Treatise on the, by Dr. Lardner. 5th edition . 1s.
35. BLASTING ROCKS AND QUARRYING, AND ON STONE, Art of, by Lieut.-Gen. Sir J. Burgoyne, G.C.B., R.E. 2nd edition . . 1s.
36, 37, 38, 39. DICTIONARY OF TERMS used by Architects, Builders, Engineers, Surveyors, Artists, Ship-builders, &c., 4 vols. 2nd edition 4s.
40. GLASS-STAINING, Art of, by Dr. M. A. Gessert . . . . . 1s.
41. PAINTING ON GLASS, Essay on, by E. O. Fromberg . . . . 1s.
42. COTTAGE BUILDING, Treatise on. 2nd edition . . . . . 1s.
43. TUBULAR AND GIRDER BRIDGES, and others, Treatise on, more particularly describing the Britannia and Conway Bridges . . . 1s.
44. FOUNDATIONS, &c., Treatise on, by E. Dobson, C.E. . . . 1s.
45. LIMES, CEMENTS, MORTARS, CONCRETE, MASTICS, &c., Treatise on, by G. R. Burnell, C.E. 2nd edition . . . . . 1s.
46. CONSTRUCTING AND REPAIRING COMMON ROADS, Treatise on the Art of, by H. Law, C.E. 2nd edition . . . . . 1s.
47, 48, 49. CONSTRUCTION AND ILLUMINATION OF LIGHTHOUSES, Treatise on the, by Alan Stevenson, C.E., 3 vols. 3s
50. LAW OF CONTRACTS FOR WORKS AND SERVICES, Treatise on the, by David Gibbons. 2nd edition . . . . . 1s.

Digitized by Google

51, 52, 53. NAVAL ARCHITECTURE, Principles of the Science, Treatise on, by J. Peake, N.A., 3 vols. . . . . 3s.

53*. LAYING OFF SHIPS, being an Introduction to the Mould Loft of Ship-Building, by James Peake . . . . . 1s. 6d.

53**. THE LARGE OUTLINE ILLUSTRATIONS OF DITTO . . 1s.

54. MASTING, MAST-MAKING, AND RIGGING OF SHIPS, Treatise on, by E. Kipping, N.A. . . . . 1s. 6d.

54*. IRON SHIP BUILDING, by J. Grantham, C.E. . . . . 2s. 6d.

55, 56. NAVIGATION, Treatise on THE SAILOR'S SEA-BOOK.—How to keep the Log and work it off—Latitude and Longitude—Great Circle Sailing—Law of Storms and Variable Winds; and an explanation of Terms used, with coloured illustrations of Flags, 2 vols. 2nd edition . . . . . 2s.

57, 58. WARMING AND VENTILATION, Treatise on the Principles of the Art of, by Charles Tomlinson, 2 vols. . . . . 2s.

59. STEAM BOILERS, Treatise on, by R. Armstrong, C. E. . . . . 1s.

60, 61. LAND AND ENGINEERING SURVEYING, Treatise on, by T. Baker, C.E., 2 vols. . . . . 2s.

62. RAILWAY DETAILS, Introductory Sketches of, by Sir M. Stephenson, Vol. I. . . . . 1s.

62*. RAILWAY WORKING IN GREAT BRITAIN, Rudimentary Treatise on; numerous Statistical Details, Table of Capital and Dividends, form of Revenue Account, Railway Clearing-house, &c., &c.; by E. D. Chattaway, Vol. II. . . . . 1s.

63, 64, 65. AGRICULTURAL BUILDINGS, Treatise on the Construction of, on Motive Power, and the Machinery of the Steading; and on Agricultural Machinery, by G. H. Andrews, 3 vols. . . . 3s.

66. CLAY LANDS & LOAMY SOILS, Treatise on, by Prof. Donaldson, A.E. 1s.

67, 68. CLOCK AND WATCH-MAKING, AND ON CHURCH CLOCKS, Treatise on, by E. B. Denison, M.A., 2 vols. . . . . 2s.

69, 70. MUSIC, Practical Treatise on, by C. C. Spencer, 2 vols. 2nd edit. 2s.

71. PIANO-FORTE, Instruction for Playing the, by the same. . . 1s.

72, 73, 74, 75. RECENT FOSSIL SHELLS, Treatise (A Manual of the Mollusca) on, by Samuel P. Woodward, and illustrations, 4 vols. . 4s.

75*. RECENT AND FOSSIL SHELLS, Treatise on, by S. P. Woodward, Supplementary Volume, with Plates . . . . . 1s. 6d.

76, 77. DESCRIPTIVE GEOMETRY, Treatise on, by J. F. Heather, M.A., 2 vols. . . . . 2s.

77*. ECONOMY OF FUEL, Treatise on, and on Reverberatory Furnaces for the Manufacture of Iron and Steam Boilers, by T. S. Prideaux, Esq. 1s.

78, 79. STEAM AS APPLIED TO GENERAL PURPOSES AND LOCOMOTIVE ENGINES, Treatise on, by J. Sewell, C. E., 2 vols. . 2s.

78*. LOCOMOTIVE ENGINE, Treatise on, by G. D. Dempsey, C.E. 1s. 6d.

79*. ATLAS OF PLATES to the above, consisting of existing Examples of Engines for the Broad and Narrow Gauge, the Link Motion, &c., in 4to. 4s. 6d.

79**. RUDIMENTARY WORK ON PHOTOGRAPHY, the Art of Producing Photographic Pictures on any material and in any colour, and also Tables of the Composition and Properties of the Chemical Substances; by Dr. H. Halleur, of Berlin . . . . . 1s.

80, 81. MARINE ENGINES, AND ON THE SCREW, &c., Treatise on, by R. Murray, C.E., 2 vols. 3rd edition . . . . . 2s. 6d.

80*, 81*. EMBANKING LANDS FROM THE SEA, The Practise of, by John Wiggins, F.G.S., 2 vols. . . . . 2s.

82, 82*. POWER OF WATER, AS APPLIED TO FLOUR MILLS, &c, Treatise on the, by Joseph Glynn, F.R.S., C.E. . . . 2s.

Digitized by Google

83. BOOK-KEEPING, Treatise on, by James Haddon, M.A., 2nd edition. 1s.

82**, 83*. 83 (*bis*). COAL GAS, Practical Treatise on the Manufacture and Distribution of, by Samuel Hughes, C.E., 3 vols. . . . . 3s.

82***. WATER WORKS FOR THE SUPPLY OF CITIES AND TOWNS, Treatise on, with Description of Works which have been Executed, and on Pumping from Wells, by Samuel Hughes, F.G.S., C.E., treble volume . . . . . 3s.

83**. CONSTRUCTION OF LOCKS, Treatise on the, with illustrations 1s. 6d.

83 (*bis*). PRINCIPLES OF THE FORMS OF SHIPS AND BOATS, by W. Bland, 2nd edition . . . . . 1s.

84. ARITHMETIC, Elementary Treatise on, the Theory, and numerous Examples for Practice, and for Self-Examination, by Prof. J. R. Young . . . . . 1s. 6d.

84*. KEY to the above, by the same . . . . . 1s. 6d.

85. EQUATIONAL ARITHMETIC: Questions of Interest, Annuities, and General Commerce, by W. Hipsley, 2nd edition . . . 1s.

85*. Supplementary Vol. to the above, containing Tables for the Calculation of Simple Interest, together with Logarithms for Compound Interest and Annuities, &c., &c., by W. Hipsley . . . . . 1s.

86, 87. ALGEBRA, Elements of, for the use of Schools and Self-Instruction, by James Haddon, M.A., 2 vols. . . . . 2s.

86*, 87*. ELEMENTS OF ALGEBRA, Key to the, by Prof. Young . 1s. 6d.

88, 89. GEOMETRY, Principles of, by Henry Law, C.E., 2 vols. . . 2s.

90. GEOMETRY, ANALYTICAL, by James Haun . . . . . 1s.

91, 92. PLAIN AND SPHERICAL TRIGONOMETRY, Treatises on, by the same, 2 vols. . . . . 2s.

93. MENSURATION, Elements and Practice of, by T. Baker, C.E. . . 1s.

94, 95. LOGARITHMS, Treatise on, and Tables for facilitating Nautical, Trigonometrical, and Logarithmic Calculations, by H. Law, C.E., 2 vols. . . . . 2s.

96. POPULAR ASTRONOMY, Elementary Treatise on, by the Rev. Robert Main, M.R.A.S. . . . . 1s.

97. STATICS AND DYNAMICS, Principles and Practice of, by T. Baker, C.E. . . . . 1s.

98, 98*. MECHANISM AND PRACTICAL CONSTRUCTION OF MACHINES, Elements of, by the same, 2 vols. in 1 . . . . . 2s.

99, 100. NAUTICAL ASTRONOMY AND NAVIGATION, Theory and Practice of, by Prof. Young. 2 vols in 1. (TABLES additional, 1s. 6d.) 2s.

101. DIFFERENTIAL CALCULUS, by W. S. B. Woolhouse, F.R.A.S. 1s.

101*. WEIGHTS AND MEASURES OF ALL NATIONS; comprising full information of Distances, Weights, Coins, and the various Divisions of Time, on Rates of Exchange, &c., by W. S. B. Woolhouse, F.R.A.S. . . . . 1s. 6d.

102. INTEGRAL CALCULUS, by Homersham Cox, M.A. . . . 1s.

103. INTEGRAL CALCULUS, Collection of Examples of the, by James Haun . . . . . 1s.

104. DIFFERENTIAL CALCULUS, Collection of Examples of the, by J. Haddon, M.A . . . . . 1s.

105. ALGEBRA, GEOMETRY, AND TRIGONOMETRY, First Mnemonical Lessons in, by the Rev. Thomas Penyngton Kirkman, M.A. 1s. 6d.

106. SHIPS' ANCHORS FOR ALL SERVICES, Rudimentary and Comprehensive, by George Cotsell, upwards of 100 illustrations . 1s. 6d.

107. METROPOLITAN BUILDINGS ACT, passed August, 1855, with Notes . . . . . 2s. 6d.

108. METROPOLITAN LOCAL MANAGEMENT ACT, passed August, 1855, with Notes, and with the Amended Act of 19 & 20 Vict. 1s. 6d.
109. LIMITED LIABILITY AND PARTNERSHIP ACT, passed August, 1855, together with the required references to the Acts of Victoria . 1s.
110. FIVE RECENT LEGISLATIVE ENACTMENTS, for Contractors, Merchants, and Tradesmen . . . . . 1s.
111. THE NUISANCES REMOVAL AND DISEASES PREVENTION ACT . . . . . 1s.

112. DOMESTIC MEDICINE; or complete and comprehensive Instructions for Self-Aid, by M. Raspail, translated for the use of the British public . . . . . 1s. 6d.

113. USE OF FIELD ARTILLERY ON SERVICE, by Capt. Teubert, translated by Captn. H. H. Maxwell . . . . . 1s. 6d.

SUPPLEMENTARY VOLUMES of the Rudimentary Series, Published and Preparing for Publication, for the years 1858 *and* 1859 :—

114. RUDIMENTARY TREATISE OF MACHINERY: The Machine in its Elements, Practice, and Purpose, by Chas. D. Abel, C.E., woodcuts . . . . . 1s. 6d.
115. RUDIMENTARY TREATISE OF MACHINERY, Atlas of Plates to ditto, of several kinds of Machines, drawn to scale for practical application, 14 plates large 4to. . . . . 4s. 6d.
116. RUDIMENTARY TREATISE ON ACOUSTICS: The Elements, Practice, and Distribution of Sound in Public and Private Buildings, by O. R. Burnell, Archt. and C.E. . . . . 1s.
117. RUDIMENTARY TREATISE ON THE PRACTICE IN CANAL AND RIVER NAVIGATION, by O. R. Burnell, C.E., with numerous wood-cuts . . . . . 1s. 6d.
118. RUDIMENTARY SKETCH OF THE CIVIL ENGINEERING OF NORTH AMERICA, by David Stevenson, of Edinburgh, C.E., with Plates, Vol. I. 2nd edition . . . . . 1s. 6d.
119. Ditto, ditto, Vol. II. . . . . 1s. 6d.
120. RUDIMENTARY TREATISE ON HYDRAULICS, by G. R. Burnell, C.E. . . . . 1s. 6d.
121. RUDIMENTARY TREATISE ON RIVER ENGINEERING, by G. R. Burnell, C.E. . . . . 1s. 6d.
122. RUDIMENTARY TREATISE ON FLUIDS, by G. R. Burnell, C.E. 1s.
123. RUDIMENTARY TREATISE ON CARPENTRY AND JOINERY, edited by E. L. Garbett, Archt., with wood-cuts . . . . 1s. 6d.
124. RUDIMENTARY TREATISE ON ROOFS FOR PUBLIC AND PRIVATE BUILDINGS, by E. L. Garbett, Archt, with plates. 1s. 6d.
125. RUDIMENTARY TREATISE ON THE COMBUSTION OF COAL AND THE PREVENTION OF SMOKE, Chemically and Practically Considered, by Chas. Wye Williams, M.I.C.E., with numerous wood-cuts. 3rd edition . . . . . 1s. 6d.
125*. Illustrations to ditto . . . . . 1s. 6d.

*** The above Supplementary Volumes are of an important character, and add considerably to the usefulness of an already admitted and most valuable series of technical works: the established reputation of which, and the extensive sale in all parts of the world, has given a cheering result of a long and laborious task, and on which a very large capital has been expended.

MR. WEALE'S

NEW SERIES OF EDUCATIONAL WORKS.

I., II.

CONSTITUTIONAL HISTORY OF ENGLAND. 2 Vols. By W. D. HAMILTON. 2s.

III., IV.

CONSTITUTIONAL HISTORY OF ENGLAND DOWN TO VICTORIA. By W. D. HAMILTON. 2s.

V.

GUTLINES OF THE HISTORY OF GREECE. By E. LEVIEN, M.A. Vol. I. 1s.

VI.

GUTLINES OF THE HISTORY OF GREECE, VOL. II. TO ITS BECOMING A ROMAN PROVINCE. By E. LEVIEN, M.A. 1s. 6d.

VII.

OUTLINE HISTORY OF ROME. By E. LEVIEN, M.A. Vol. I. 1s.

VIII.

OUTLINE HISTORY OF ROME, VOL. II., TO THE DECLINE. By E. LEVIEN. 1s. 6d.

IX., X.

A CHRONOLOGY OF CIVIL AND ECCLESIASTICAL HISTORY, LITERATURE, ART, AND CIVILISATION, FROM THE EARLIEST PERIOD TO 1855. 2 Vols. 2s 6d.

XI.

GRAMMAR OF THE ENGLISH LANGUAGE, FOR USE IN SCHOOLS AND FOR PRIVATE INSTRUCTION. By HYDE CLARKE, D.C.L. 1s.

XII., XIII.

DICTIONARY OF THE ENGLISH LANGUAGE. A New and Compressed Dictionary of the English Tongue, as Spoken and Written, including above 100,000 Words, or 60,000 more than in any Existing Work, and including 10,000 Additional Meanings of Old Words. By HYDE CLARKE, D.C.L. 2 Vols. in 1. 3s. 6d.

XIV.

GRAMMAR OF THE GREEK LANGUAGE. By H. C. HAMILTON. 1s.

XV., XVI.

DICTIONARY OF THE GREEK AND ENGLISH LANGUAGE. By H. E. HAMILTON. 2 Vols. in 1. 2s.

XVII., XVIII.

DICTIONARY OF THE ENGLISH AND GREEK LANGUAGES. By H. R. HAMILTON. 2 Vols. in 1. 2s.

XIX.

GRAMMAR OF THE LATIN LANGUAGE. By T. GOODWIN, of Greenwich. 1s.

XX., XXI.

DICTIONARY OF THE LATIN AND ENGLISH LANGUAGES, by T. GOODWIN of Greenwich. Vol. I. 2s.

XXII, XXIII.

DICTIONARY OF THE ENGLISH AND LATIN LANGUAGES. By T. Goodwin of Greenwich. Vol. II. 1s. 6d.

XXIV.

GRAMMAR OF THE FRENCH LANGUAGE. By Dr. Strauss, late Lecturer at Besançon. 1s.

XXV.

DICTIONARY OF THE FRENCH AND ENGLISH LANGUAGES. By A. Elwes. Vol. I. 1s.

XXVI.

DICTIONARY OF THE ENGLISH AND FRENCH LANGUAGES. By A. Elwes. Vol. II. 1s. 6d.

XXVII.

GRAMMAR OF THE ITALIAN LANGUAGE. By A. Elwes. 1s.

XXVIII, XXIX.

DICTIONARY OF THE ITALIAN, ENGLISH, AND FRENCH LANGUAGES. By A. Elwes. Vol. I. 2s.

XXX., XXXI.

DICTIONARY OF THE ENGLISH, ITALIAN, AND FRENCH LANGUAGES. By A. Elwes. Vol. II. 2s.

XXXII., XXXIII.

DICTIONARY OF THE FRENCH, ITALIAN, AND ENGLISH LANGUAGES. By A. Elwes. Vol. III. 2s.

XXXIV.

GRAMMAR OF THE SPANISH LANGUAGE. By A. Elwes. 1s.

XXXV., XXXVI.

DICTIONARY OF THE SPANISH AND ENGLISH LANGUAGES. By A. Elwes. Vol. I. 2s.

XXXVII., XXXVIII.

DICTIONARY OF THE ENGLISH AND SPANISH LANGUAGES. By A. Elwes. Vol. II. 2s.

XXXIX.

GRAMMAR OF THE GERMAN LANGUAGE. By Dr. Strauss. 1s.

XL.

CLASSICAL GERMAN READER, FROM THE BEST AUTHORS. 1s.

XLI., XLII, XLIII.

DICTIONARIES OF THE ENGLISH, GERMAN, AND FRENCH LANGUAGES. By N. E. HAMILTON. 3 Vols. 3s.

XLIV., XLV.

DICTIONARY OF THE HEBREW AND ENGLISH, AND ENGLISH AND HEBREW LANGUAGES, Containing all the Biblical and Rabbinical Words 3 Vols. (together with the Grammar, which may be had separately for 1s.) By Dr. Breslau, Hebrew Professor, 10s.

THE

SERIES OF EDUCATIONAL WORKS

ARE ON SALE IN TWO KINDS OF BINDING.

HAMILTON'S Outlines of the History of England, 4 vols. in 1, bound in cloth . 5s.
——— Ditto, in half morocco, gilt, marbled edges . . . . . 5s. 6d.
LEVIEN'S History of Greece, 2 vols. in 1, bound in cloth . . . . . 3s 6d.
——— Ditto, in half morocco, gilt, marbled edges . . . . . 5s.
——— History of Rome, 2 vols. in 1, bound in cloth . . . . . 3s. 6d.
——— Ditto, in half morocco, gilt, marbled edges . . . . . 5s.
CHRONOLOGY of Civil and Ecclesiastical History, Literature, Art, &c., 2 vols. in 1, bound in cloth . . . . . 5s. 6d.
——— Ditto in half morocco, gilt, marbled edges . . . . . 5s.
CLARKE'S Dictionary of the English Language, bound in cloth . . . . 4s. 6d.
——— in half morocco, gilt, marbled edges . . . . . 5s.
——— bound with Dr Clarke's English Grammar, in cloth . . . . 5s. 6d.
——— Ditto, in half morocco, gilt, marbled edges 6s
HAMILTON'S Greek and English and English and Greek Dictionary, 4 vols. in 1, bound in cloth . . . . . 5s.
——— Ditto, in half morocco, gilt, marbled edges . . . . . 5s. 6d.
——— Ditto, with the Greek Grammar, bound in cloth . . . . . 5s.
——— Ditto, with Ditto, in half morocco, gilt, marbled edges . . . . 5s. 6d.
GOODWIN'S Latin and English and English and Latin Dictionary, 2 vols. in 1, bound in cloth . . . . . 4s. 6d.
——— Ditto, in half morocco, gilt, marbled edges . . . . . 5s.
——— Ditto, with the Latin Grammar, bound in cloth . . . . . 3s 6d.
——— Ditto, with Ditto, in half morocco, gilt, marbled edges . . . . 5s.
ELWES'S French and English and English and French Dictionary, 2 vols. in 1, in cloth . . . . . 5s. 6d.
——— Ditto, in half morocco, gilt, marbled edges . . . . . 6s.
——— Ditto, with the French Grammar, bound in cloth . . . . . 5s. 6d.
——— Ditto, with ditto, in half morocco, gilt, marbled edges . . . . . 5s.
FRENCH and English Phrase Book, or Vocabulary of all Conversational Words, elab orately set forth for Travelling Use, as a Self Interpreter bound . 1s. 6d.
ELWES'S Italian, English, and French,—English, Italian, and French,—French, Italian, and English Dictionary, 3 vols. in 1, bound in cloth . . . 7s. 6d.
——— Ditto, in half morocco, gilt, marbled edges . . . . . 8s 6d.
——— Ditto, with the Grammar, bound in embossed cloth, marbled edges 8s. 6d.
——— Ditto, with Ditto, in half morocco, gilt, marbled edges . . . . 9s.
ELWES'S Spanish and English and English and Spanish Dictionary, 4 vols in 1, bound in cloth . . . . . 5s.
——— Ditto, in half morocco, gilt, marbled edges . . . . . 5s. 6d.
——— Ditto, with the Grammar, bound in cloth . . . . . 5s.
——— Ditto, with Ditto, in half morocco, gilt, marbled edges . . . . 6s. 6d.
HAMILTON'S English, German, and French,—German, French, and English,—French, German, and English Dictionary, 3 vols. in 1, bound in cloth . . . 4s.
——— Ditto, in half morocco gilt, marbled edges . . . . . 4s. 6d.
——— Ditto, with the Grammar, bound in embossed cloth, marbled edges . 5s.
——— Ditto, with Ditto, in half morocco, gilt, marbled edges . . . . 5s. 6d.
BRESLAU'S Hebrew and English Dictionary, with the Grammar, 2 vols. in 1, bound in cloth . . . . . 5s. 6d.
——— Ditto, 2 vols. in 1, in half morocco, 3s. 6d —With vol. 2, English and Hebrew . . . . . 12s. 6d.

Now in the course of Publication,

GREEK AND LATIN CLASSICS.

PRICE ONE SHILLING PER VOLUME,

Except in Some Instances, and those are at 1s. 6d. or 2s. each

VERY NEATLY PRINTED ON GOOD PAPER,

A SERIES OF VOLUMES

CONTAINING THE

PRINCIPAL GREEK AND LATIN AUTHORS,

ACCOMPANIED BY

EXPLANATORY NOTES IN ENGLISH, PRINCIPALLY SELECTED FROM THE BEST AND MOST RECENT GERMAN COMMENTATORS,

AND COMPRISING

All those Works that are essential for the Scholar and the Pupil, and applicable for use at the Universities of Oxford, Cambridge, Edinburgh, Glasgow, Aberdeen, and Dublin,—the Colleges at Belfast, Cork, Galway, Winchester, and Eton, and the great Schools at Harrow, Rugby, &c.,—also for Private Tuition and Instruction, and for the Library.

Vols. 1, 2, 3, 4, 5, 6, 7, 8, 9, 16, 17 of the Latin Series have appeared. Of the Greek Series, vols. 1, 2, 3, 4, 5, 6, 9, 18, 41 also have been published, and will be regularly continued.

LATIN SERIES.

1. A New LATIN DELECTUS OR INTRODUCTORY CLASSICAL READER, consisting of Extracts from the best Authors, systematically arranged; accompanied by Grammatical and Explanatory Notes and Copious Vocabularies
2. CÆSAR'S COMMENTARIES ON THE GALLIC WAR: with Grammatical and Explanatory Notes in English, and a complete Geographical Index.
3. CORNELIUS NEPOS; with English Notes, &c.
4. VIRGIL. THE GEORGICS, BUCOLICS, AND DOUBTFUL WORKS; with English Notes, chiefly from the German.
5. VIRGIL'S ÆNEID (on the same plan as the preceding)
6. HORACE. ODES AND EPODES; with English Notes, an Analysis of each Ode, and a full explanation of the metres.
7. HORACE. SATIRES AND EPISTLES, with English Notes, &c.
8. SALLUST. CONSPIRACY OF CATILINE, AND JUGURTHINE WAR.
9. TERENCE. ANDRIA AND HEAUTONTIMORUMENOS.
10. TERENCE. PHORMIO, ADELPHI, AND HECYRA.
11. CICERO. ORATIONS AGAINST CATILINE, FOR SULLA, FOR ARCHIAS, AND FOR THE MANILIAN LAW.

12. CICERO. First and Second Philippics; Orations for Milo, for Marcellus, and for Ligarius.
13. CICERO. De Officiis.
14. CICERO. De Amicitiâ, de Senectute, and Brutus.
15. JUVENAL AND PERSIUS
16. LIVY. Books I. to V., in 2 parts.
17. LIVY. Books XXI and XXII
18. TACITUS. Agricola; Germania; and Annals, Book I.
19. SELECTIONS FROM TIBULLUS, OVID, PROPERTIUS, AND LUCRETIUS.
20. SELECTIONS FROM SUETONIUS, AND THE LATER LATIN WRITERS.

GREEK SERIES.

1. INTRODUCTORY GREEK READER. On the same plan as the Latin Reader.
2. XENOPHON. Anabasis, I., II., III.
3. XENOPHON. Anabasis, IV., V., VI., VII.
4. LUCIAN. Select Dialogues.
5. HOMER. Iliad, I. to VI.
6. HOMER. Iliad, VII. to XII.
7. HOMER. Iliad, XIII. to XVIII.
8. HOMER. Iliad, XIX. to XXIV.
9. HOMER. Odyssey, I. to VI.
10. HOMER. Odyssey, VII. to XII.
11. HOMER. Odyssey, XIII. to XVIII.
12. HOMER. Odyssey, XIX. to XXIV.; and Hymns.
13. PLATO. Apology, Crito, and Phædo.
14. HERODOTUS, I., II.
15. HERODOTUS, III., IV.
16. HERODOTUS, V., VI., and part of VII.
17. HERODOTUS. Remainder of VII., VIII., and IX.
18. SOPHOCLES. Œdipus Rex.
19. SOPHOCLES. Œdipus Coloneus.
20. SOPHOCLES. Antigonê.
21. SOPHOCLES. Ajax.
22. SOPHOCLES. Philoctetes.
23. EURIPIDES. Hecuba.
24. EURIPIDES. Medea.
25. EURIPIDES. Hippolytus.
26. EURIPIDES. Alcestis.
27. EURIPIDES. Orestes.
28. EURIPIDES. Extracts from the Remaining Plays.
29. SOPHOCLES. Extracts from the Remaining Plays.
30. ÆSCHYLUS. Prometheus Vinctus.
31. ÆSCHYLUS. Persæ.
32. ÆSCHYLUS. Septem contra Thebas.
33. ÆSCHYLUS. Choëphoræ.
34. ÆSCHYLUS. Eumenides.
35. ÆSCHYLUS. Agamemnon
36. ÆSCHYLUS. Supplices.
37. PLUTARCH. Select Lives
38. ARISTOPHANES. Clouds.
39. ARISTOPHANES. Frogs.
40. ARISTOPHANES. Selections from the Remaining Comedies.
41. THUCYDIDES, I.
42. THUCYDIDES, II.
43. THEOCRITUS. Select Idyls.
44. PINDAR.
45. ISOCRATES.
46. HESIOD.

Preparing for Publication,

ORATORY AND PUBLIC SPEAKING.

A FIRST BOOK for Youths of Ten Years of Age, of well selected Readings, and for Practice in Oratory and the inculcation of Elocution; adapted for Recitations and Gesture, and the improvement of Voice and Pronunciation. To be used in Schools and for Home Instruction.

SECOND BOOK for Youth of Fifteen Years of Age and upwards. Readings, Speaking, Pronunciation, and Elocution, for Public and Private Schools, and for Home Practice.

THIRD BOOK for Young Men, for Public Speaking, Legislative, Legal, &c., Recitations in Schools and Colleges, selected from the best Greek, Latin, and English Authors.

In one Volume large 8vo., with 13 Plates, Price One Guinea, in half-morocco binding,

MATHEMATICS

FOR

PRACTICAL MEN:

BEING

A COMMON-PLACE BOOK

OF

PURE AND MIXED MATHEMATICS,

DESIGNED CHIEFLY FOR THE USE OF

CIVIL ENGINEERS, ARCHITECTS, AND SURVEYORS.

BY OLINTHUS GREGORY, LL.D., F.R.A.S.

THIRD EDITION, REVISED AND ENLARGED.

BY HENRY LAW,

CIVIL ENGINEER.

CONTENTS.

PART I.—PURE MATHEMATICS.

CHAPTER I.—Arithmetic.

Sect.
1. Definitions and Notation.
2. Addition of Whole Numbers.
3. Subtraction of Whole Numbers.
4. Multiplication of Whole Numbers.
5. Division of Whole Numbers.—Proof of the first Four Rules of Arithmetic.
6. Vulgar Fractions.—Reduction of Vulgar Fractions.—Addition and Subtraction of Vulgar Fractions.—Multiplication and Division of Vulgar Fractions.
7. Decimal Fractions — Reduction of Decimals — Addition and Subtraction of Decimals. — Multiplication and Division of Decimals.
8. Complex Fractions used in the Arts and Commerce.—Reduction.—Addition.—Subtraction and Multiplication.—Division.—Duodecimals.
9. Powers and Roots.—Evolution.
10. Proportion.—Rule of Three.—Determination of Ratios.
11. Logarithmic Arithmetic.—Use of the Tables.—Multiplication and Division by Logarithms.—Proportion, or the Rule of Three, by Logarithms.—Evolution and Involution by Logarithms.
12. Properties of Numbers

CHAPTER II.—Algebra.

1. Definitions and Notation.
2. Addition and Subtraction.
3. Multiplication.
4. Division.
5. Involution.
6. Evolution.
7. Surds.—Reduction — Addition, Subtraction, and Multiplication.—Division, Involution, and Evolution.
8. Simple Equations.—Extermination.—Solution of General Problems
9. Quadratic Equations.
10. Equations in General.
11. Progression. — Arithmetical Progression.—Geometrical Progression.
12. Fractional and Negative Exponents.
13. Logarithms.
14. Computation of Formulæ.

CHAPTER III.—Geometry.

1. Definitions.
2. Of Angles, and Right Lines, and their Rectangles.
3. Of Triangles.
4. Of Quadrilaterals and Polygons.
5. Of the Circle, and Inscribed and Circumscribed Figures.
6. Of Planes and Solids.
7. Practical Geometry.

CHAPTER IV.—Mensuration.

1. Weights and Measures.—1. Measures of Length.—2. Measures of Surface.—3. Measures of Solidity and Capacity.—4. Measures of Weight.—5. Angular Measure.—6. Measure of Time.—Comparison of English and French Weights and Measures
2. Mensuration of Superficies.
3. Mensuration of Solids.

CHAPTER V.—Trigonometry.

1. Definitions and Trigonometrical Formulæ.
2. Trigonometrical Tables.
3. General Propositions.
4. Solution of the Cases of Plane Triangles.—Right-angled Plane Triangles.
5. On the application of Trigonometry to Measuring Heights and Distances.—Determination of Heights and Distances by Approximate Mechanical Methods.

CHAPTER VI.—Conic Sections.

Sect.
1. Definitions.
2. Properties of the Ellipse.—Problems relating to the Ellipse.
3. Properties of the Hyperbola.—Problems relating to the Hyperbola.
4. Properties of the Parabola.—Problems relating to the Parabola.

CHAPTER VII.—Properties of Curves.

Sect.
1. Definitions.
2. The Conchoid
3. The Cissoid.
4. The Cycloid and Epicycloid
5. The Quadratrix.
6. The Catenary.—Tables of Relation of Catenarian Curves.

PART II.—MIXED MATHEMATICS.

CHAPTER I.—Mechanics in General.

CHAPTER II.—Statics.

1. Statical Equilibrium.
2. Center of Gravity.
3. General application of the Principles of Statics to the Equilibrium of Structures.—Equilibrium of Piers or Abutments.—Pressure of Earth against Walls.—Thickness of Walls.—Equilibrium of Polygons.—Stability of Arches.—Equilibrium of Suspension Bridges.

CHAPTER III.—Dynamics.

1. General Definitions.
2. On the General Laws of Uniform and Variable Motion.—Motion uniformly Accelerated.—Motion of Bodies under the Action of Gravity.—Motion over a fixed Pulley.—Motion on Inclined Planes.
3. Motions about a fixed Center, or Axis.—Centers of Oscillation and Percussion.—Simple and Compound Pendulums.—Center of Gyration, and the Principles of Rotation.—Central Forces.—Inquiries connected with Rotation and Central Forces.
4. Percussion or Collision of Bodies in Motion
5. On the Mechanical Powers.—Levers.—Wheel and Axle.—Pulley.—Inclined Plane.—Wedge and Screw

CHAPTER IV.—Hydrostatics.

1. General Definitions.
2. Pressure and Equilibrium of Non-elastic Fluids.
3. Floating Bodies.
4. Specific Gravities.
5. On Capillary Attraction

CHAPTER V.—Hydrodynamics.

1. Motion and Effluence of Liquids.
2. Motion of Water in Conduit Pipes and Open Canals, over Weirs, &c.—Velocities of Rivers.
3. Contrivances to Measure the Velocity of Running Waters.

CHAPTER VI.—Pneumatics.

1. Weight and Equilibrium of Air and Elastic Fluids.
2. Machines for Raising Water by the Pressure of the Atmosphere.
3. Force of the Wind.

CHAPTER VII.—Mechanical Agents.

1. Water as a Mechanical Agent.
2. Air as a Mechanical Agent.—Coulomb's Experiments
3. Mechanical Agents depending upon Heat. The Steam Engine.—Table of Pressure and Temperature of Steam.—General Description of the Mode of Action of the Steam Engine.—Theory of the Steam Engine.—Description of the various kinds of

Digitized by Google

Engines, and the Formulæ for calculating their Power.—Practical application of the foregoing Formulæ.
4. Animal Strength as a Mechanical Agent.

CHAPTER VIII.—STRENGTH OF MATERIALS.

1. Results of Experiments, and Principles upon which they should be practically applied.
2. Strength of Materials to Resist Tensile and Crushing Strains.—Strength of Columns.
3. Elasticity and Elongation of Bodies subjected to a Crushing or Tensile Strain.
4. On the Strength of Materials subjected to a Transverse Strain.—Longitudinal form of Beam of uniform Strength.—Transverse Strength of other Materials than Cast Iron.—The Strength of Beams according to the manner in which the Load is distributed.
5. Elasticity of Bodies subjected to a Transverse Strain.
6. Strength of Materials to resist Torsion.

APPENDIX

I. Table of Logarithmic Differences.
II. Table of Logarithms of Numbers, from 1 to 100.
III. Table of Logarithms of Numbers, from 100 to 10,000.
IV. Table of Logarithmic Sines, Tangents, Secants, &c.
V. Table of Useful Factors, extending to several places of Decimals.
VI. Table of various Useful Numbers, with their Logarithms.
VII. A Table of the Diameters, Areas, and Circumferences of Circles and also the sides of Equal Squares.
VIII. Table of the Relations of the Arc, Abscissa, Ordinate and Subnormal, in the Catenary.
IX. Tables of the Lengths and Vibrations of Pendulums.
X. Table of Specific Gravities.
XI. Table of Weight of Materials frequently employed in Construction.
XII. Principles of Chronometers.
XIII. Select Mechanical Expedients.
XIV. Observations on the Effect of Old London Bridge on the Tides, &c.
XV. Professor Farish on Isometrical Perspective.

In 18mo., in boards, comprising 390 pages, price 5s.

A SYNOPSIS OF PRACTICAL PHILOSOPHY,

alphabetically arranged, containing a great variety of Theorems, Formulæ, and Tables, from the most accurate and recent authorities in various branches of Mathematics and Natural Philosophy: with Tables of Logarithms.

By the Rev. JOHN CARR, M.A., late Fellow of Trinity College, Cambridge.

John Weale's Catalogue of his Publications of Works on Architecture, Civil, Mechanical, Military, and Naval Engineering, gratis; if by post, 1d.

HINTS

TO

YOUNG ARCHITECTS:

COMPRISING

ADVICE TO THOSE WHO, WHILE YET AT SCHOOL ARE DESTINED TO THE PROFESSION;

SUCH AS, HAVING PASSED THEIR PUPILAGE, ARE ABOUT TO TRAVEL

AND TO THOSE WHO, HAVING COMPLETED THEIR EDUCATION, ARE ABOUT TO PRACTISE:

TOGETHER WITH

A MODEL SPECIFICATION:

INVOLVING A GREAT VARIETY OF INSTRUCTIVE AND SUGGESTIVE MATTER CALCULATED TO FACILITATE THEIR PRACTICAL OPERATIONS;

AND TO DIRECT THEM IN THEIR CONDUCT, AS THE RESPONSIBLE AGENTS OF THEIR EMPLOYERS,

AND AS THE RIGHTFUL JUDGES OF A CONTRACTOR'S DUTY.

By GEORGE WIGHTWICK, Architect.

CONTENTS :—

Preliminary Hints to Young Architects on the Knowledge of Drawing.
On Serving his Time.
On Travelling.
His Plate on the Door.
Orders, Plan-drawing.
On his Taste, Study of Interiors.
Interior Arrangements.
Warming and Ventilating
House Building, Stabling.
Cottages and Villas.
Model Specification :—
- General Clauses.
- Foundations.
- Well.
- Artificial Foundations.
- Brickwork.
- Rubble Masonry with Brick Mingled.

Model Specification :
- Stone-cutting.
- ——, Grecian or Italian only.
- ——, Gothic only.
- Miscellaneous.
- Slating.
- Tiling.
- Plaster and Cement-work.
- Carpenters' Work.
- Joiners' Work.
- Iron and Metal work.
- Plumbers' Work.
- Drainage.
- Well-digging.
- Artificial Levels, Concrete, Foundations, Piling and Planking, Paving, Vaulting, Bell-hanging, Plumbing, and Building generally.

In One Large Volume Octavo, Eleven Hundred Pages, with numerous Engravings, price 1*l.* 8*s.*,

A GENERAL TEXT BOOK,

FOR THE

CONSTANT USE AND REFERENCE OF

ARCHITECTS, ENGINEERS, SURVEYORS, SOLICITORS, AUCTIONEERS, LAND AGENTS, AND STEWARDS,

IN ALL THEIR SEVERAL AND VARIED PROFESSIONAL OCCUPATIONS;

AND FOR THE

ASSISTANCE AND GUIDANCE OF

COUNTRY GENTLEMEN AND OTHERS

ENGAGED IN THE

TRANSFER, MANAGEMENT, OR IMPROVEMENT OF LANDED PROPERTY:

CONTAINING

THEOREMS, FORMULÆ, RULES, AND TABLES

IN GEOMETRY, MENSURATION, AND TRIGONOMETRY; LAND MEASURING, SURVEYING, AND LEVELLING; RAILWAY AND HYDRAULIC ENGINEERING; TIMBER MEASURING; THE VALUATION OF ARTIFICERS' WORK, ESTATES, LEASEHOLDS, LIFEHOLDS, ANNUITIES, TILLAGES, FARMING STOCK, AND TENANT RIGHT; THE ASSESSMENT OF PARISHES, RAILWAYS, GAS AND WATER WORKS; THE LAW OF DILAPIDATIONS AND NUISANCES, APPRAISEMENTS AND AUCTIONS, LANDLORD AND TENANT, AGREEMENTS AND LEASES.

TOGETHER WITH EXAMPLES OF VILLAS AND COUNTRY HOUSES.

BY EDWARD RYDE,
Civil Engineer and Land Surveyor, Author of several Professional Works.

TO WHICH ARE ADDED SEVERAL CHAPTERS ON

AGRICULTURE AND LANDED PROPERTY.

BY PROFESSOR DONALDSON,
Author of several Works on Agriculture.

CONTENTS

CHAPTER I.—ARITHMETIC. 1. Notation—2. Proof of the First Four Rules—3. Vulgar Fractions—4. Decimals—5. Duodecimals—6. Powers and Roots—7. Properties of Numbers—8. Logarithms and Mathematical Tables.

II.—PLANE AND SOLID GEOMETRY. 1. Definitions—2. Of Angles and Right Lines, and their Rectangles—3. Of Triangles—4. Of Quadrilaterals and Polygons—5. Of the Circle, and Inscribed and Circumscribing Figures—6. Of Planes and Solids—7. Practical Geometry.

III.—MENSURATION. 1. Comparison of English and French Weights and Measures—2. Mensuration of Superficies—3. Mensuration of Solids.

IV.—TRIGONOMETRY. 1. Definitions and Trigonometrical Formulæ—2. General Propositions—3. Solution of the Cases of Plane Triangles.

V.—CONIC SECTIONS.

VI.—LAND MEASURING. Including Table of Decimals of an Acre—Table of Land Measure, by dimensions taken in yards.

VII.—LAND SURVEYING. 1. Parish and Estate Surveying—2. Trigonometrical Surveying—3. Traverse Surveying—4. Field Instruments, the Prismatic Compass; the Box Sextant; the Theodolite.

VIII.—LEVELLING. Levelling Instruments, the Spirit Level; the Y Level; Troughton's Level; Mr. Gravatt's Level; Levelling Staves—Examples in Levelling.

IX.—PLOTTING. Embracing the Circular Protractor—The T Square and Semicircular Protractor—Plotting Sections.

X.—COMPUTATION OF AREAS. The Pediometer—The Computing Scale—Computing Tables.

XI.—COPYING MAPS. Including a description of the Pentagraph.

XII.—RAILWAY SURVEYING. 1. Exploration and Trial Levels; Standing Orders.—2. Proceedings subsequent to the Passing of the Act; Tables for Setting out Curves; Tables for Setting out Slopes; Tables of Relative Gradients; Specification of Works to be executed in the construction of a Railway; Form of Tender.

XIII.—COLONIAL SURVEYING.

XIV.—HYDRAULICS IN CONNECTION WITH DRAINAGE, SEWERAGE, AND WATER SUPPLY.—With Synopsis of Ryde's Hydraulic Tables—Specifications, Iron Pipes and Castings; Stone-Ware Drain Pipes; Pipe Laying; Reservoir.

XV.—TIMBER MEASURING. Including Timber Tables, Solid Measure, Unequal Sided Timber, Superficial Measure.

XVI.—ARTIFICERS' WORK. 1. Bricklayers' and Excavators'—2. Slaters'—3. Carpenters' and Joiners'—4. Sawyers'—5. Stonemasons'—6. Plasterers'—7. Ironmongers'—8. Painters'—9. Glaziers'—10. Paper Hangers'.

XVII.—VALUATION OF ESTATES. With Tables for the Purchasing of Freehold, Copyhold, or Leasehold Estates, Annuities, and Advowsons, and for Renewing Leases for Terms of Years certain and for Lives.

XVIII.—VALUATION OF TILLAGES AND TENANT RIGHT. With Tables for Measuring and Valuing Hay Ricks.

CONTENTS *(continued)*:—

XIX.—VALUATION OF PARISHES.'

XX.—BUILDERS' PRICES. 1. Carpenters' and Joiners'—2. Masons'—3. Bricklayers'—4. Plasterers'—5. Ironmongers'—6. Drainers'—7. Plumbers'—8. Painters'—9. Paper Hangers' and Decorators'—10. Glaziers'—11. Zinc Workers'—12. Coppersmiths'—13. Wireworkers'.

XXI.—DILAPIDATIONS AND NUISANCES. 1. General Definitions—2. Dilapidations by Tenants for Life and Years—3. Ditto by Mortgagee or Mortgagor—4. Ditto of Party Walls and Fences—5. Ditto of Highways and Bridges—6. Nuisances.

XXII.—THE LAW RELATING TO APPRAISERS AND AUCTIONEERS. 1. The Law relating to Appraisements—2. The Law of Auction.

XXIII.—LANDLORD AND TENANT. 1. Agreements and Leases—2. Notice to Quit—3. Distress—4. Recovery of Possession.

XXIV.—TABLES. Of Natural Sines and Cosines—For Reducing Links into Feet—Decimals of a Pound Sterling.

XXV.—STAMP LAWS.—Stamp Duties—Customs' Duties.

EXAMPLES OF VILLAS AND COUNTRY HOUSES.

ON LANDED PROPERTY, BY PROFESSOR DONALDSON.

I.—Landlord and Tenant—their Position and Connections.

II.—Lease of Land, Conditions, and Restrictions; Choice of Tenant and Assignation of the Deed.

III.—Cultivation of Land, and Rotation of Crops.

IV.—Buildings necessary on Cultivated Lands—Dwelling Houses, Farmeries, and Cottages for Labourers.

V.—Laying-out Farms, Roads, Fences, and Gates.

VI.—Plantations—Young and old Timber.

VII.—Meadows and Embankments, Beds of Rivers, Water Courses, and Flooded Grounds.

VIII.—Land Draining, Open and Covered,—Plan, Execution, and Arrangement between Landlord and Tenant.

IX.—Minerals—Working and Value.

X.—Expenses of an Estate—Regulations of Disbursements—and Relation of the appropriate Expenditures.

XI.—Valuation of Landed Property; of the Soil, of Houses, of Woods, of Minerals, of Manorial Rights, of Royalties, and of Fee Farm Rents.

XII.—Land Steward and Farm Bailiff: Qualifications and Duties.

XIII.—Manor Bailiff, Woodreve, Gardener, and Gamekeeper—their Position and Duties.

XIV.—Fixed days of Audit—Half-Yearly Payments of Rents—Form of Notices, Receipts, and of Cash Books, General Map of Estates, and of each separate Farm—Concluding Observations.

BRIDGES.

45.

In 4 vols. royal 8vo, illustrated by 138 engravings and 92 wood-cuts, bound in 3 vols. half-morocco, price £4. 10*s*.

THE THEORY, PRACTICE, AND ARCHITECTURE OF BRIDGES OF STONE, IRON, TIMBER, AND WIRE;

WITH EXAMPLES ON THE PRINCIPLE OF SUSPENSION.

DIVISIONS OF THE WORK.

THEORY OF BRIDGES. By James Hann, King's College, London.
GENERAL PRINCIPLES OF CONSTRUCTION, &c. Translated from Gauthey.
THEORY OF THE ARCH, &c. By Professor Moseley.
PAPERS ON FOUNDATIONS. By T. Hughes, C.E.
ACCOUNT OF HUTCHESON BRIDGE, GLASGOW, with Specification. By the late Robert Stevenson, C.E.
MATHEMATICAL PRINCIPLES OF DREDGE'S SUSPENSION BRIDGE.
ESSAY AND TREATISES ON THE PRACTICE AND ARCHITECTURE OF BRIDGES. By William Hosking, F.S.A., Archt. and C.E.
SPECIFICATION OF CHESTER DEE BRIDGE.
PRACTICAL DESCRIPTION OF THE TIMBER BRIDGES, &c., ON THE UTICA AND SYRACUSE RAILROAD, U. S. By B. F. Isherwood, C. E., New York.
Description of the Plates.—General Index, &c., &c., &c.

LIST OF PLATES.

1. Centering of Ballater bridge across the river Dee, Aberdeenshire.
2. Town's American timber bridge.
3. Do., sections.
4. Do. do.
5. Ladykirk and Norham timber bridge over the Tweed, by J. Blackmore.
6. Timber bridge over the Clyde at Glasgow, by Robert Stevenson.
7. Elevation of arch of do.
8. Transverse section of do.
9. Section of foot-path on do., &c.
10. Occupation bridge over the Calder and Hebble Navigation, by W. Bull.
11. Newcastle, North Shields, and Tynemouth railway viaduct across Willington Dean, plans and elevations.
12. Do., do.
13. Do., sections.
14. Ditto across Ouse Burn Dean, plan and elevation.
15. Do., do.
16. Isometrical view of the upper wooden bridge at Elysville over the Patapsco, on the Baltimore and Ohio Railroad.
17. Elevation and plan of do.
18. Sections of do.
19. Longitudinal section under the central archway of Old London bridge, showing the sunk weir recommended by Mr. Smeaton to hold the water up for the benefit of the water-works, &c., in 1763; sections of the same.
20. Plan and elevation of timber bridge for Westminster, as designed by Wesley.
21. Half-elevation of ditto for Westminster, as designed by James King.
22. Westminster timber bridge adapted to the stone piers, by C. Labelye.
23. One of the river ribs of the centre on which the middle arch of Westminster bridge was turned, extending 76 feet, designed and executed by James King.
24. Long elevation and plan of Westminster bridge.
25. Elevation of the foot bridge over the Whitadder, at Abbey St. Bathen's.
26. Weymouth bridge, elevation and plan.
27. Very long elevation of Hutcheson bridge, Glasgow, by Robert Stevenson.
28. Longitudinal section of ditto, showing the progress of the works in 1832.
29. Cross section of do., showing the building apparatus and centre frames.
30. Cross section of Hutcheson bridge.
31. Plan of southern abutment of do.
32. Section of abutments of do.
33. Toll-houses of do.
34. Bridge of the Schuylkill at Market Street, Philadelphia.
35. Details of do.

36. Plan of the wood-work in the starling of the small piers of Chepstow bridge.
37. Longitudinal section through one of the large piers.
38. Details of Chepstow bridge.
39. Plan, elevation, and sections of the central arch of London bridge.
40. London and Croydon railway bridge on road from Croydon to Sydenham, plans, elevations, and sections.
41. London and Croydon railway bridge on road from Norwood to Bromley, do.
42. London and Croydon railway bridge at Sydenham, do.
43. Elevation of the Victoria bridge over the valley of the river Wear, on the Durham junction railway.
44. Elevation of Chepstow bridge.
45. Piling and timber foundations of one of the large piers of Chepstow bridge.
46. Plan of pier, elevation of do.
47. Enlarged section of one of the piers.
48. Newcastle and Carlisle railway bridge, over the river Tyne at Scotswood, by John Blackmore, plan and elevation.
49, 50. Sections and details of do.
51. Elevation and plan of bridge over the Eden at Carlisle, by Sir R. Smirke.
52. Elevation of one of the arches, with a pier, and the north abutment.
52a. The centering used for the arches of do.
53. Plan and elevation of the bridge erected over the Thames at Staines.
54. Elevation and plans of the Wellesley bridge at Limerick.
55. Elevation of pier and half-arch, with longitudinal section, plan and section of baluster, transverse section through the crown and spandril.
56. Bridge of Jena, plan and elevation.
57. Do., elevation of one of the land arches, with section of towing-path and retaining wall, transverse section of the bridge at the springing of an arch, plan of do., transverse section of the bridge through the centre of one of the land arches, plan of the abutments, retaining walls, &c
58. Elevation of the Devil's bridge over the Serchio, near Lucca, Italy; plan, elevation, and cross section.
59. Bridge across the river Forth at Stirling, by R. Stevenson, elevation.
60. Longitudinal section of the same.
61. Timber bridge on the Utica and Syracuse Railway, United States, spans of 40 and 30 feet.
62. Do., span of 60 feet.
63. Do., elevation, plan and cross section, span of 88 feet.
63a. Do., isometrical projection.
64. Do., plan, elevation, and cross section, span of 34 feet.
64a. Timber bridge, span of 82 feet.
65. Abutment for a bridge of 82 feet span over the Oneida Creek.
66. Trestle bridge, Oneida Creek Valley, span of 30 feet.
67. Do., elevation of span of 102 feet.
67a. Do., isometrical projection of truss, connection of floor beams, and cross section.
68. Trestle bridge, Onondago Creek Valley, span of 30 feet
69. A great variety of details of joinery.
69a. Pile-driving machine.
70. Isometrical projections.
70a. Isometrical projections of iron plate.
70b Do.
70c. Do.
70d. Do.
70e Do.
70f. Do., culverts.
70g. Viaduct under Erie canal.
71. Remains of the bridge over the Adda, at Trezzo, the Milanese.
72. Elv iron bridge, near cathedral.
73. Details of do.
74. Do.
75. Do.
76. Haddlesey bridge, over the Aire, Yorkshire, details of the iron-work.
77. Do.
78. Do.
79. Do.
80 Do., sections of structure,
81. Do., plan, iron balustrades &c.
82. Do., details.
83. Do., elevation.
84. London and Blackwall Railway bridge over the Lea, elevation and plan.
85. Do, sections and details.
86. Do., sections, enlarged view of railing.
87. Isometrical projection of the suspension bridge at Balloch ferry, constructed on Mr. Dredge's principle.
88. Perronet's design for the bridge over the Seine at Melun, sections, &c.
89 Brighton chain pier, portions of constructive detail.
90. Wreck of do. in Oct. 1833.
91. Do.
92. Longitudinal and transverse sections of cast-iron swing bridge.
93. Longitudinal section and transverse do., plan of turning plate, roller frame, and bed-plate of cast-iron swing bridge.
94. Elevation and plan of cast-iron swing bridge, Plymouth.
95. Gerrard's Hostel bridge, Cambridge, erected by the Butterley Company, (W. C. Mylne,) elevation and plan.
96. Do., sections and details of do.
97 Do., transverse section of do.
98. Friburg suspension bridge, general elevation, with a section of the valley of the Sarine and of the covering shafts, &c.; general plan, ends of main piers, with approaches enlarged, &c.
99. Do., sections and details of do.
100, 100a Do. do.
101. Professor Moseley's diagrams of the arch.
102. Do.
103. Do.
104. Robert Stevenson's elevation of a chain bridge upon the catenarian principle.

In 1 vol. 4to., with 74 plates, extra cloth boards and lettered, price 21s.,

THE CARPENTER'S NEW GUIDE:

OR,

THE BOOK OF LINES FOR CARPENTERS,

GEOMETRICALLY EXPLAINED;

COMPRISING ALL THE ELEMENTARY PRINCIPLES ESSENTIAL FOR ACQUIRING A KNOWLEDGE OF THE THEORY AND PRACTICE OF CARPENTRY.

A NEW EDITION,

FOUNDED ON THAT OF THE LATE PETER NICHOLSON'S STANDARD WORK;

REVISED BY

ARTHUR ASHPITEL, ARCHITECT, F.S.A., F.I.B.A.

TOGETHER WITH

PRACTICAL RULES ON DRAWING,

BY GEORGE PYNE, OF OXFORD, ARTIST.

The Work is divided in Three Divisions, with Seventy-four Illustrative Plates, as follows:

Division A.—Practical Geometry, and of Carpentry, explaining the principles in all its parts, by the late Peter Nicholson. (Pages 1 to 80—Plates 1 to 60.)

Division B.—Practical Mathematics, Mensuration, &c., by Arthur Ashpitel, Architect. (Pages 1 to 32.)

Division C.—Practical Rules on Drawing, for the Operative Builder and Young Student in Architecture. (Pages 1 to 80—Plates 1 to 14.)

With 72 Engravings, new, improved, and extended edition, price 2l. 12s. 6d., extra large 4to, extra cloth boards and lettered,

THE PRACTICAL RAILWAY ENGINEER:

EXAMPLES OF THE MECHANICAL AND ENGINEERING OPERATIONS AND STRUCTURES COMBINED IN THE MAKING OF A RAILWAY.

BY G. D. DEMPSEY, C.E.

CONTENTS.

Section I.—Curves, gradients, gauge, and slopes.

Section II.—Survey and levels for a railway—Parliamentary plan and section—Limits of deviation—Setting out the line—Working plans and sections—Computing quantities—Opening the ground.

Section III.—Earthworks, cuttings, embankments, and drains.

Section IV.—Retaining walls, bridges, tunnels, &c.

Section V.—Permanent way and construction

Section VI.—Stations, &c.

Section VII.—Rolling stock—Carriages, trucks, wheels, and axles—Brakes, and details—Locomotive engines and tenders.

Section VIII.—Signals and electric telegraph.

LIST OF PLATES.

1. Cuttings
2, 3, 4. Earthworks, excavating.
5. Ditto, embanking.
6. Ditto, waggons.
7. Drains under bridges.
8. Brick and stone culverts.
9. Paved crossings.
10. Railway bridges, diagram.
11, 12, 13, 14. Bridges, brick and stone.
15, 16. Ditto, iron.
17, 18, 19, 20, 21. Ditto, timber.
22. Centers for bridges.
23, 24, 25, 26, 27. "Pont de Montlouis."
28. "Pont du Cher."
29. Suspension bridge.
30. Box girder bridge.
31. Trestle bridge and Chepstow bridge.
32. Details of Chepstow bridge.
33. Creosoting, screw piling, &c.
34. Permanent way and rails.
35. Ditto, chairs.
36. Ditto, fish-joints, &c.
37. Ditto, fish joint chairs.
38, 39. Ditto, cast-iron sleepers, &c.
40. Ditto, Stephenson's, Brunel's, Hemans's, Macneill's, and Dockray's.
41. Ditto, crossings.
42. Ditto ditto, details.
43. Ditto, spring-crossings, &c.
44. Ditto, turn table.
45, 46. Terminal station.
47, 48, 49. Stations.
50. Goods stations.
51. Polygonal engine-house.
52. Engine-house.
53. Watering apparatus.—(A). Tanks.
54. Ditto, (B.) Details of pumps.
55. Ditto, (C.) Details of engines.
56. Ditto, (D.) Cranes.
57. Hoisting machinery.
58. Ditto, details.
59. Traversing platform.
60. Ditto, details.
61. Station roof at King's Cross.
62. Ditto, Liverpool.
63. Ditto, Birmingham.
64, 65. Railway carriages.
66. Ditto, details.
67, 68. Railway trucks and wheels.
69. Iron and covered waggons.
70. Details of brakes.
71. Wheels and details.
72. Portrait.

In 1 Vol. 4to, extra cloth, boards and lettered, 67 Engravings, 21s.,

DESIGNS AND EXAMPLES OF COTTAGES, VILLAS, AND COUNTRY HOUSES;

BEING THE STUDIES OF SEVERAL EMINENT ARCHITECTS AND BUILDERS.

CONSISTING OF PLANS, ELEVATIONS, AND PERSPECTIVE VIEWS, WITH APPROXIMATE ESTIMATES OF THE COST OF EACH.

In imperial 8vo., with 13 large folding Plates, extra cloth boards, price 12s.,

A PRACTICAL AND THEORETICAL ESSAY ON OBLIQUE BRIDGES.

By GEORGE WATSON BUCK, M. Inst. C.E.

TOGETHER WITH A

DESCRIPTION TO DIAGRAMS FOR FACILITATING THE CONSTRUCTION OF OBLIQUE BRIDGES.

By W. H. BARLOW, C.E.,

Second Edition, corrected and improved.

In 1 vol 4to., 50 plates, with dimensions, extra cloth boards, price 21s.,

EXAMPLES FOR BUILDERS, CARPENTERS, AND JOINERS;

BEING WELL-SELECTED ILLUSTRATIONS OF RECENT MODERN ART AND CONSTRUCTION.

CONTENTS OF PLATES.

1. Geometrical Staircase.
2. ,, ,,
3. ,, ,,
4. ,, ,,
5. ,, ,,
6. Construction of the Wooden Columns in King's College.
7. Details of do.
8. Plan and Elevation of the Athenæum Club House.
9. Do. do. Arthur's Club, St. James' Street.
10. Do. do. details.
11. Do. do. ,,
12. Design for Verandah.
13. Details of do
14. Design for Verandah.
15. Details of do.
16. Design for Verandah
17. Details of do.
18. Elevation of a Group of New Houses.
19. Joinery of Doors.
20. Base, Surbase, and Dado
21. Plan and Elevation of Doors.
22. Sections do do
23. Section of the framing or frontispiece of an entablature of a Shop front.
24. Roof at Charter House.
25. ,, Clerkenwell Church.
26. Elizabethan terminations of a Shop front entablature
27. Joinery at Windsor Castle.
28. ,, ,,
29. ,, ,,
30. ,, ,,
31. ,, ,,
32. Gate at the town entrance to the Royal Mews, Windsor.
33. Joinery at the Duke of Sutherland's, at Lilleshall.
34. Mullions of Windows, do.
35. Plan and Elevation of a Public-house.
36. Exeter Hall roof.
37. Country mansion.
38. Italian Designs.
39. ,, ,,
40. ,, ,,
41. Longitudinal Section, do.
42. Windows, Doors, &c. do.
43. Windows, &c. do.
44. Grand Staircase, do.
45. An Elegant Italian façade.
46. Penton Mewsey Church, Bell Turret.
47. Plan and South Elevation of do.
48. West Elevation of do.
49. Elevations, with horizontal and vertical sections of the Bell Turret, do.
50. Transverse section of do.